



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

November 14, 2012

CALL NO. 114
CONTRACT ID NO. 121363
Addendum # 3

Subject: Elliott County, STPR 0071 (025)
Letting November 16, 2012

- (1) Revised - Plan Sheet - R2Q
- (2) Revised - Bid Items - 79 thru 83 of 83

Proposal revisions are available at
<http://transportation.ky.gov/Construction-Procurement>

Plan Revisions are available at: <http://www.lynnimaging.com/kytransportation/>

If you have any questions, please contact us at (502) 564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:jj

Enclosures



An Equal Opportunity Employer M/F/D

PIPE DRAINAGE SUMMARY

COUNTY OF	ITEM NO.	SHEET NO.
ELLIOTT	9-126.51	R20

SHEET NO.	SKEW	CULVERT PIPE	CULVERT PIPE	CULVERT PIPE	CULVERT PIPE	36" RCP NO ALTERNATES	CULVERT PIPE	CULVERT PIPE	CULVERT PIPE	CULVERT PIPE	60" EQUIV. ELLIPTICAL CULVERT PIPE	CULVERT PIPE	BORE & JACK PIPE 24"	BORE & JACK PIPE 30"	BORE & JACK PIPE 36"	ENTRANCE PIPE 15"	ENTRANCE PIPE 18"	ENTRANCE PIPE 24"	ENTRANCE PIPE 30"	SAFELOADING	18" S&F BOX INLET-OUTLET	24" S&F BOX INLET-OUTLET	30" S&F BOX INLET-OUTLET	36" S&F BOX INLET-OUTLET	PIPELINE VIDEO INSPECTION	DITCH EXC.	FABRIC GEOTEXTILE TYPE IV (for pipe)	CLASS 'A' CONCRETE	STEEL REINF.	REMARKS						
		18"	24"	30"	36"		42"	48"	54"	60"		72"	21799EN	21800EN	24186EC	440	441	443	445												2690	1450	1451	1452	1453	23131ER701
ITEM CODE		462	464	466	468	468	469	470	471	472	501	474	21799EN	21800EN	24186EC	440	441	443	445	2690	1450	1451	1452	1453	23131ER701		2600	8100	8150							
UNIT TO BID		LINEAR FEET																			CU. YD.	EACH				LIN. FT.	CU. YD.	SQ. YD.	CU. YD.	LBS.						
	4173+07.8	15° R+									198																						2-60" EQ. ELIP. S&F HDWLS.			
	4184+93	10° R+				121																		1	121	118	43	538	2.15	182		1-36" S&F HDWL.				
	4198+01.7	35° R+							194																194	20	1472	7.82	583			2-54" S&F HDWLS.				
	4211+61.8	20° R+							252																252	25	1904	7.82	583			2-54" S&F HDWLS.				
	4248+61	50° L+				145								115											260	11	1156	4.30	363			2-36" S&F HDWLS.				
	4253+68	0°							225 ^①																225	38	1600	6.53	496			2-48" S&F HDWLS.				
	4261+52.8	30° R+				117																			117	42	520	2.15	182			1-36" S&F HDWL.				
	4266+50	0°			111																				111	29	444	1.68	141			1-30" S&F HDWL.				
	4275+39.3	10° L+							245 ^①																245	24	1742	6.53	496			2-48" S&F HDWLS.				
	4278+45	15° L+							248																248	124	1764	6.53	496			2-48" S&F HDWLS.				
	4284+20	0°	138 ^①																						138	16	429	0.93	8			1-18" S&F HDWL.				
	4287+26.4	5° R+				213																			213	56	947	4.30	363			2-36" S&F HDWLS.				
	4293+48.2	0°				177																			177	10	787	4.30	363			2-36" S&F HDWLS.				
	4300+29.2	5° L+			92																				92	48	360									
	4303+27.4	5° R+										122													122	10	987	20.95	1571			2-72" S&F HDWLS.				
	4309+48	15° R+							84 ^①																84	57	560	5.35	430			2-42" S&F HDWLS.				
	4333+14.6	28° R+				434																			434	11	1929	14.02 ^②	363			2-36" S&F HDWLS.				
	4382+10	0°				165 ^①																			165	23	733	2.15	182			1-36" S&F HDWL.				
	4390+75	0°			82 ^①								42												124	29	496	3.36	281			2-30" S&F HDWLS.				
	4402+15	0°							162 ^①																162	25	1080	5.35	430			2-42" S&F HDWLS.				
	4410+84	0°		87 ^①								40													127	13	452									
	KY. 885																																			
	46+50	10° R+			82																						17	328								
	49+26.9	15° R+			50																						38	200								
	HOG CAMP ROAD																																			
	54+55.2	10° L+				52																					11	231	4.30	363			2-36" S&F HDWLS.			
	HOG CONN. #1																																			
	9+32.9	15° L+	84																									261								
	APPR. LT. 4326+50																																			
	46+05	20° L+	30																								13	93	1.86	16			2-18" S&F HDWLS.			
	48+42.4	50° R+	186 ^①																								10	579	1.86	16			2-18" S&F HDWLS.			
	APPR. RT. 4372+00																																			
	52+32	0°		150 ^①																								7	533	2.70	16			2-24" S&F HDWLS.		
	Entr. Lt. 4174+31					50																														
	Entr. Lt. 4199+30									78																										
	Entr. Lt. 4213+75								68																											
	Entr. Lt. 4218+10								68																											
	Entr. Lt. 4220+30					72																														
	Entr. off Old Ky. 7																																			
	129.5' Rt. 4259+59									67																										
	Entr. Lt. 4402+84					62																														
	BOX CULVERTS																																			
	TOTAL PROJECT	438	237	417	1174	434	382	718	446	145	198	122	40	42	115	407	282	275	139	99	3	2	7	3	3809	2341	23,797	125.10	8534							

- ① NO RCP ALTERNATE
- ② INCLUDES 9.72 CU. YDS. FOR 3-36" INTERMEDIATE PIPE ANCHORS

FILE NAME: G:\PWORK\JASON.LITTLETON\00146708\DRAINAGE SUMMARY.DGN
 USER: Jason.Littleton
 DATE PLOTTED: November 13, 2012
 E-SHEET NAME:
 MicroStation v8.11.7.443

PIPE DRAINAGE SUMMARY

△ REVISED 11-13-12

COUNTY OF	ITEM NO.	SHEET NO.
ELLIOTT	9-126.51	R20

SHEET NO.	SKEW	CULVERT PIPE	CULVERT PIPE	CULVERT PIPE	CULVERT PIPE	36" RCP NO ALTERNATES	CULVERT PIPE	CULVERT PIPE	CULVERT PIPE	CULVERT PIPE	60" EQUIV. ELLIPTICAL CULVERT PIPE	CULVERT PIPE	BORE & JACK PIPE 24"	BORE & JACK PIPE 30"	BORE & JACK PIPE 36"	ENTRANCE PIPE 15"	ENTRANCE PIPE 18"	ENTRANCE PIPE 24"	ENTRANCE PIPE 30"	SAFELOADING	18" S&F BOX INLET-OUTLET	24" S&F BOX INLET-OUTLET	30" S&F BOX INLET-OUTLET	36" S&F BOX INLET-OUTLET	PIPELINE VIDEO INSPECTION	DITCH EXC.	FABRIC GEOTEXTILE TYPE IV (for pipe)	CLASS 'A' CONCRETE	STEEL REINF.	REMARKS							
		18"	24"	30"	36"		42"	48"	54"	60"		72"	21799EN	21800EN	24186EC	440	441	443	445												2690	1450	1451	1452	1453	23131ER701	2600
ITEM CODE		462	464	466	468	468	469	470	471	472	501	474	21799EN	21800EN	24186EC	440	441	443	445	2690	1450	1451	1452	1453	23131ER701	2600	8100	8150									
UNIT TO BID		LINEAR FEET																			CU. YD.	EACH				LIN. FT.	CU. YD.	SQ. YD.	CU. YD.	LBS.							
	4173+07.8	15° R+									198																								2-60" EQ. ELIP. S&F HDWLS.		
	4184+93	10° R+				121																		1	121	118	1672	8.16	610				1-36" S&F HDWL.				
	4198+01.7	35° R+							194																194	20	1472	7.82	583				2-54" S&F HDWLS.				
	4211+61.8	20° R+							252																252	25	1904	7.82	583				2-54" S&F HDWLS.				
	4248+61	50° L+				145									115										260	11	1156	4.30	363				2-36" S&F HDWLS.				
	4253+68	0°							225																225	38	1600	6.53	496				2-48" S&F HDWLS.				
	4261+52.8	30° R+				117																		1	117	42	520	2.15	182				1-36" S&F HDWL.				
	4266+50	0°				111																		1	111	29	444	1.68	141				1-30" S&F HDWL.				
	4275+39.3	10° L+							245																245	24	1742	6.53	496				2-48" S&F HDWLS.				
	4278+45	15° L+							248																248	124	1764	6.53	496				2-48" S&F HDWLS.				
	4284+20	0°	138																						1	138	16	429	0.93	8				1-18" S&F HDWL.			
	4287+26.4	5° R+				213																			213	56	947	4.30	363				2-36" S&F HDWLS.				
	4293+48.2	0°				177																			177	10	787	4.30	363				2-36" S&F HDWLS.				
	4300+29.2	5° L+				92																			92	48	360										
	4303+27.4	5° R+										122														122	10	987	20.95	1571				2-72" S&F HDWLS.			
	4309+48	15° R+							84																84	57	560	5.35	430				2-42" S&F HDWLS.				
	4333+14.6	28° R+								434															434	11	1929	14.02	363				2-36" S&F HDWLS.				
	4382+10	0°				165																		1	165	23	733	2.15	182				1-36" S&F HDWL.				
	4390+75	0°				82							42												124	29	496	3.36	281				2-30" S&F HDWLS.				
	4402+15	0°							162																162	25	1080	5.35	430				2-42" S&F HDWLS.				
	4410+84	0°				87							40												127	13	452										
	KY. 885																																				
	46+50	10° R+				82																															
	49+26.9	15° R+				50																															
	HOG CAMP ROAD																																				
	54+55.2	10° L+				52																														2-36" S&F HDWLS.	
	HOG CONN. #1																																				
	9+32.9	15° L+	84																																		
	APPR. LT. 4326+50																																				
	46+05	20° L+	30																																	2-18" S&F HDWLS.	
	48+42.4	50° R+	186																																	2-18" S&F HDWLS.	
	APPR. RT. 4372+00																																				
	52+32	0°				150																														2-24" S&F HDWLS.	
	Entr. Lt. 4174+31					50																															
	Entr. Lt. 4199+30										78																										
	Entr. Lt. 4213+75										68																										
	Entr. Lt. 4218+10										68																										
	Entr. Lt. 4220+30					72																															
	Entr. off Old Ky. 7																																				
	129.5' Rt. 4259+59										67																										
	Entr. Lt. 4402+84					62																															
	BOX CULVERTS																																				
	TOTAL PROJECT	438	237	417	1174	434	382	718	446	145	198	122	40	42	115	407	282	275	139	99	3	2	7	3	3809	2341	23,797	125.10	8534								

- ① NO RCP ALTERNATE
- ② INCLUDES 9.72 CU. YDS. FOR 3-36" INTERMEDIATE PIPE ANCHORS

FILE NAME: G:\PWORK\JASON.LITTLETON\00146708\DRAINAGE SUMMARY.DGN
 USER: Jason.Littleton
 DATE PLOTTED: November 13, 2012
 E-SHEET NAME:
 MicroStation v8.11.7.443

PROPOSAL BID ITEMS

Report Date 11/14/12

Section: 0001 - PAVING (ASPHALT)

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0010	00001		DGA BASE	1,495.00	TON		\$	
0020	00003		CRUSHED STONE BASE	84,131.00	TON		\$	
0030	00020		TRAFFIC BOUND BASE	166.00	TON		\$	
0040	00071		CRUSHED AGGREGATE SIZE NO 57	298.00	TON		\$	
0050	00100		ASPHALT SEAL AGGREGATE	715.00	TON		\$	
0060	00103		ASPHALT SEAL COAT	86.00	TON		\$	
0070	00190		LEVELING & WEDGING PG64-22	626.00	TON		\$	
0080	00212		CL2 ASPH BASE 1.00D PG64-22	55,319.00	TON		\$	
0090	00301		CL2 ASPH SURF 0.38D PG64-22	13,884.00	TON		\$	
0100	02200		ROADWAY EXCAVATION	3,127,564.00	CUYD		\$	
0110	10203ND		PAVEMENT ADJUSTMENT(ASPHALT)	1.00	LS	916,208.00	\$	\$916,208.00

Section: 0002 - PAVING (CONCRETE W/ CONCRETE SHOULDERS)

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0120	00001		DGA BASE	1,495.00	TON		\$	
0130	00003		CRUSHED STONE BASE	79,791.00	TON		\$	
0140	00020		TRAFFIC BOUND BASE	166.00	TON		\$	
0150	00100		ASPHALT SEAL AGGREGATE	715.00	TON		\$	
0160	00103		ASPHALT SEAL COAT	86.00	TON		\$	
0170	00190		LEVELING & WEDGING PG64-22	626.00	TON		\$	
0180	00212		CL2 ASPH BASE 1.00D PG64-22	4,464.00	TON		\$	
0190	00301		CL2 ASPH SURF 0.38D PG64-22	3,298.00	TON		\$	
0200	02078		JPC PAVEMENT-6 IN SHLD	47,735.00	SQYD		\$	
0210	02084		JPC PAVEMENT-8 IN	106,251.00	SQYD		\$	
0220	02200		ROADWAY EXCAVATION	3,126,771.00	CUYD		\$	
0230	10203ND		PAVEMENT ADJUSTMENT	1.00	LS	423,272.00	\$	\$423,272.00

Section: 0003 - PAVING (CONCRETE W/ ASPHALT SHOULDERS)

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0240	00001		DGA BASE	1,495.00	TON		\$	
0250	00003		CRUSHED STONE BASE	84,131.00	TON		\$	
0260	00020		TRAFFIC BOUND BASE	166.00	TON		\$	
0270	00100		ASPHALT SEAL AGGREGATE	715.00	TON		\$	
0280	00103		ASPHALT SEAL COAT	86.00	TON		\$	
0290	00190		LEVELING & WEDGING PG64-22	626.00	TON		\$	
0300	00212		CL2 ASPH BASE 1.00D PG64-22	17,790.00	TON		\$	
0310	00301		CL2 ASPH SURF 0.38D PG64-22	7,286.00	TON		\$	
0320	02084		JPC PAVEMENT-8 IN	95,973.00	SQYD		\$	
0330	02200		ROADWAY EXCAVATION	3,126,771.00	CUYD		\$	
0340	10203ND		PAVEMENT ADJUSTMENT	1.00	LS	423,272.00	\$	\$423,272.00

Section: 0004 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0350	00078		CRUSHED AGGREGATE SIZE NO 2	20.00	TON		\$	

PROPOSAL BID ITEMS

Report Date 11/14/12

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0360	01000		PERFORATED PIPE-4 IN	310.00	LF		\$	
0370	01001		PERFORATED PIPE-6 IN	827.00	LF		\$	
0380	01010		NON-PERFORATED PIPE-4 IN	54.00	LF		\$	
0390	01011		NON-PERFORATED PIPE-6 IN	162.00	LF		\$	
0400	01020		PERF PIPE HEADWALL TY 1-4 IN	1.00	EACH		\$	
0410	01021		PERF PIPE HEADWALL TY 1-6 IN	2.00	EACH		\$	
0420	01029		PERF PIPE HEADWALL TY 3-6 IN	5.00	EACH		\$	
0430	01032		PERF PIPE HEADWALL TY 4-4 IN	4.00	EACH		\$	
0440	01033		PERF PIPE HEADWALL TY 4-6 IN	8.00	EACH		\$	
0450	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	160.00	EACH		\$	
0460	01984		DELINEATOR FOR BARRIER - WHITE	34.00	EACH		\$	
0470	02014		BARRICADE-TYPE III	16.00	EACH		\$	
0480	02091		REMOVE PAVEMENT	8,887.00	SQYD		\$	
0490	02159		TEMP DITCH	15,000.00	LF		\$	
0500	02160		CLEAN TEMP DITCH	7,500.00	LF		\$	
0510	02242		WATER	1,000.00	MGAL		\$	
0520	02351		GUARDRAIL-STEEL W BEAM-S FACE	12,425.00	LF		\$	
0530	02360		GUARDRAIL TERMINAL SECTION NO 1	27.00	EACH		\$	
0540	02367		GUARDRAIL END TREATMENT TYPE 1	7.00	EACH		\$	
0550	02371		GUARDRAIL END TREATMENT TYPE 7	4.00	EACH		\$	
0560	02373		GUARDRAIL END TREATMENT TYPE 3	4.00	EACH		\$	
0570	02381		REMOVE GUARDRAIL	14,965.00	LF		\$	
0580	02429		RIGHT-OF-WAY MONUMENT TYPE 1	115.00	EACH		\$	
0590	02430		RIGHT-OF-WAY MONUMENT TYPE 1A	3.00	EACH		\$	
0600	02431		WITNESS R/W MONUMENT TYPE 2	8.00	EACH		\$	
0610	02475		PLUG WATER WELL	14.00	EACH		\$	
0620	02482		CHANNEL LINING CLASS IA	2,398.00	TON		\$	
0630	02483		CHANNEL LINING CLASS II	4,301.00	TON		\$	
0640	02488		CHANNEL LINING CLASS IV	3,979.00	CUYD		\$	
0650	02545		CLEARING AND GRUBBING(229 ACRES)	1.00	LS		\$	
0660	02562		SIGNS	918.00	SQFT		\$	
0670	02585		EDGE KEY	230.00	LF		\$	
0680	02622		RIFFLE STRUCTURE-GABION	98.00	EACH		\$	
0690	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0700	02651		DIVERSIONS (BY-PASS DETOURS)(2)	1.00	LS		\$	
0710	02651		DIVERSIONS (BY-PASS DETOURS)(1A)	1.00	LS		\$	
0720	02651		DIVERSIONS (BY-PASS DETOURS)(1)	1.00	LS		\$	
0730	02701		TEMP SILT FENCE	26,400.00	LF		\$	
0740	02703		SILT TRAP TYPE A	229.00	EACH		\$	
0750	02704		SILT TRAP TYPE B	229.00	EACH		\$	
0760	02705		SILT TRAP TYPE C	1.00	EACH		\$	
0770	02706		CLEAN SILT TRAP TYPE A	2,061.00	EACH		\$	
0780	02707		CLEAN SILT TRAP TYPE B	2,061.00	EACH		\$	
0790	02708		CLEAN SILT TRAP TYPE C	9.00	EACH		\$	
0800	02709		CLEAN TEMP SILT FENCE	26,400.00	LF		\$	
0810	02711		SEDIMENTATION BASIN	12,436.00	CUYD		\$	
0820	02712		CLEAN SEDIMENTATION BASIN	12,436.00	CUYD		\$	
0830	02726		STAKING	1.00	LS		\$	
0840	02731		REMOVE STRUCTURESTA 4165+50	1.00	LS		\$	

PROPOSAL BID ITEMS

Report Date 11/14/12

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0850	02731		REMOVE STRUCTURE STA 4173+01	1.00	LS		\$	
0860	02731		REMOVE STRUCTURE STA 4197+70	1.00	LS		\$	
0870	02731		REMOVE STRUCTURE STA 4211+94	1.00	LS		\$	
0880	02731		REMOVE STRUCTURE STA 4253+75	1.00	LS		\$	
0890	02731		REMOVE STRUCTURE STA 4303+20	1.00	LS		\$	
0900	02731		REMOVE STRUCTURE STA 4324+53	1.00	LS		\$	
0910	02731		REMOVE STRUCTURE STA 4373+30	1.00	LS		\$	
0920	02731		REMOVE STRUCTURE STA 4400+79	1.00	LS		\$	
0930	03171		CONCRETE BARRIER WALL TYPE 9T	2,070.00	LF		\$	
0940	05026		EASTERN WHITE PINE	50.00	EACH		\$	
0950	05950		EROSION CONTROL BLANKET	35,005.00	SQYD		\$	
0960	05952		TEMP MULCH	784,080.00	SQYD		\$	
0970	05953		TEMP SEEDING AND PROTECTION	784,080.00	SQYD		\$	
0980	05966		TOPDRESSING FERTILIZER	41.00	TON		\$	
0990	05985		SEEDING AND PROTECTION	598,680.00	SQYD		\$	
1000	06417		FLEXIBLE DELINEATOR POST-W	152.00	EACH		\$	
1010	06418		FLEXIBLE DELINEATOR POST-Y	155.00	EACH		\$	
1020	06510		PAVE STRIPING-TEMP PAINT-4 IN	79,200.00	LF		\$	
1030	06514		PAVE STRIPING-PERM PAINT-4 IN	130,955.00	LF		\$	
1040	06550		PAVE STRIPING-TEMP REM TAPE-W	13,200.00	LF		\$	
1050	06551		PAVE STRIPING-TEMP REM TAPE-Y	13,200.00	LF		\$	
1060	06568		PAVE MARKING-THERMO STOP BAR-24IN	195.00	LF		\$	
1070	06574		PAVE MARKING-THERMO CURV ARROW	2.00	EACH		\$	
1080	06585		PAVEMENT MARKER TY IVA-MW TEMP	300.00	EACH		\$	
1090	06586		PAVEMENT MARKER TY IVA-MY TEMP	300.00	EACH		\$	
1100	06588		PAVEMENT MARKER TY IVA-BY TEMP	150.00	EACH		\$	
1110	08019		CYCLOPEAN STONE RIP RAP	206.00	TON		\$	
1120	20738NS112		TEMP CRASH CUSHION	4.00	EACH		\$	
1130	20911ED		HIGH SLUMP 3000 PSI GROUT	62.00	CUYD		\$	
1140	22012NN		CUT AND CAP WATERLINE	1.00	EACH		\$	
1150	23821EC		CENTERLINE RUMBLE STRIPS-12 IN	27,250.00	LF		\$	

PROPOSAL BID ITEMS

Report Date 11/14/12

Section: 0005 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1160	00440		ENTRANCE PIPE-15 IN(REVISED: 10-31-12)	407.00	LF		\$	
1170	00441		ENTRANCE PIPE-18 IN(REVISED: 10-31-12)	282.00	LF		\$	
1180	00443		ENTRANCE PIPE-24 IN	275.00	LF		\$	
1190	00445		ENTRANCE PIPE-30 IN(REVISED: 10-31-12)	139.00	LF		\$	
1200	00462		CULVERT PIPE-18 IN	438.00	LF		\$	
1210	00464		CULVERT PIPE-24 IN(REVISED: 11-14-12)	237.00	LF		\$	
1220	00466		CULVERT PIPE-30 IN(REVISED: 11-14-12)	417.00	LF		\$	
1230	00468		CULVERT PIPE-36 IN(NO ALTERNATES)	434.00	LF		\$	
1240	00468		CULVERT PIPE-36 IN(REVISED: 11-14-12)	1,174.00	LF		\$	
1250	00469		CULVERT PIPE-42 IN	382.00	LF		\$	
1260	00470		CULVERT PIPE-48 IN	718.00	LF		\$	
1270	00471		CULVERT PIPE-54 IN	446.00	LF		\$	
1280	00472		CULVERT PIPE-60 IN	145.00	LF		\$	
1290	00474		CULVERT PIPE-72 IN	122.00	LF		\$	
1300	00501		CULVERT PIPE-60 IN EQUIV	198.00	LF		\$	
1310	01450		S & F BOX INLET-OUTLET-18 IN	3.00	EACH		\$	
1320	01451		S & F BOX INLET-OUTLET-24 IN	2.00	EACH		\$	
1330	01452		S & F BOX INLET-OUTLET-30 IN	7.00	EACH		\$	
1340	01453		S & F BOX INLET-OUTLET-36 IN	3.00	EACH		\$	
1350	02600		FABRIC GEOTEXTILE TY IV FOR PIPE	23,797.00	SQYD	\$2.00	\$	\$47,594.00
1360	02690		SAFELADING	99.00	CUYD		\$	
1370	08100		CONCRETE-CLASS A	125.10	CUYD		\$	
1380	08150		STEEL REINFORCEMENT	8,534.00	LB		\$	
1390	21799EN		BORE AND JACK PIPE-24 IN	40.00	LF		\$	
1400	21800EN		BORE AND JACK PIPE-30 IN	42.00	LF		\$	
1410	23131ER701		PIPELINE VIDEO INSPECTION	3,809.00	LF		\$	
1420	24186EC		BORE AND JACK PIPE-36 IN	115.00	LF		\$	

Section: 0006 - BRIDGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1430	08002		STRUCTURE EXCAV-SOLID ROCK	4,212.00	CUYD		\$	
1440	08003		FOUNDATION PREPARATION(26821)	1.00	LS		\$	
1450	08003		FOUNDATION PREPARATION(26822)	1.00	LS		\$	
1460	08003		FOUNDATION PREPARATION(26823)	1.00	LS		\$	
1470	08003		FOUNDATION PREPARATION(26824)	1.00	LS		\$	
1480	08003		FOUNDATION PREPARATION(26825); (REVISED: 10-31-12)	1.00	LS		\$	
1490	08003		FOUNDATION PREPARATION(26826)	1.00	LS		\$	
1500	08100		CONCRETE-CLASS A	2,918.70	CUYD		\$	
1510	08150		STEEL REINFORCEMENT	473,688.00	LB		\$	

PROPOSAL BID ITEMS

Report Date 11/14/12

Section: 0007 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1520	06400		GMSS GALV STEEL TYPE A	837.00	LB		\$	
1530	06406		SBM ALUM SHEET SIGNS .080 IN	721.00	SQFT		\$	
1540	06411		STEEL POST TYPE 2	2,087.00	LF		\$	
1550	06412		STEEL POST MILE MARKERS	10.00	EACH		\$	
1560	06413		DELINEATORS-WHITE	60.00	EACH		\$	
1570	06414		DELINEATORS-AMBER	2.00	EACH		\$	
1580	06451		REMOVE SIGN SUPPORT BEAM	4.00	EACH		\$	
1590	06490		CLASS A CONCRETE FOR SIGNS	3.70	CUYD		\$	
1600	20419ND		ROADWAY CROSS SECTION	2.00	EACH		\$	
1610	21134ND		REMOVE-STORE AND REINSTALL SIGN	5.00	EACH		\$	
1620	21596ND		GMSS TYPE D	6.00	EACH		\$	
1630	21813NN		REMOVE AND RELOCATE SHEET SIGNS	16.00	EACH		\$	

Section: 0008 - TRAINEES

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1640	02742		TRAINEE PAYMENT REIMBURSEMENT1 CLASS B OPERATOR	1,400.00	HOUR		\$	

Section: 0009 - MOBILIZATION / DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1650	02568		MOBILIZATION	1.00	LS		\$	
1660	02569		DEMOBILIZATION	1.00	LS		\$	