



COMMONWEALTH OF KENTUCKY

**Matthew G. Bevin**  
Governor

March 15, 2016

CALL NO. 114  
CONTRACT ID NO. 164302  
ADDENDUM # 1

Subject: Jefferson County, HSIP 9010 (216)  
Letting March 25, 2016

(1) Revised - Summary Sheets - Pages 32-34 of 103

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:ks  
Enclosures



An Equal Opportunity Employer M/F/D

County	Route	Remove Guardrail	W-Beam	ET TY 1	ET TY 2A	ET TY 3	ET TY 4A	BEC TY A	BEC TY A-1	BEC TY C	TS 1
Jefferson	US-31W	11732	13174	15	1	0	0	2	2	2	6
Jefferson	KY-841	4409	4499	4	3	1	3	5	0	0	0

Total:	16141	17672	19	4	1	3	7	2	2	6
--------	-------	-------	----	---	---	---	---	---	---	---

ADDITIONAL MATERIAL				
24" Pipe	End Anchor	MES TY 1 24"	CL. II CH. LINING	Embankment
40	0.2 CY	2	5 TONS	5 CY

REMOVE GUARDRAIL							INSTALL GUARDRAIL							ADDITIONAL MATERIAL				
LANE	END TREAT.	BEGIN MILEPOINT	END MILEPOINT	END TREAT.	LIN FEET	REMARKS	LANE	END TREAT.	BEGIN MILEPOINT	END MILEPOINT	END TREAT.	LIN FEET	REMARKS	24" Pipe	End Anchor	MES TY 1-24"	CL. II CH. LINING	Embankment
SB	BCT	2.963	2.923	2A	211		SB	1	2.887	2.854	1	174						
SB	RADIUS	2.891	2.857	BCT	180		SB	RADIUS	2.891	2.857	1	180						
SB	BCT	2.488	2.332	2A	824		SB	1	2.488	2.332	1	824						
SB	7	2.265	2.154	A	586		SB	1	2.265	2.154	A	586						
SB	A	2.050	1.744	7	1616		SB	A-1	2.050	1.744	1	1616						
SB	7	0.728	0.280	7	2365		SB	1	0.728	0.158	-	3010	CONNECT TO NEXT STRING					
SB	1	0.158	0.000	C	834		SB	-	0.158	0.000	C	834						
NB	C	0.000	0.060	BCT	317		NB	C	0.000	0.150	1	792						
NB	BCT	0.282	0.443	RADIUS	850		NB	1	0.282	0.443	RADIUS	850						
NB	RADIUS	1.179	1.311	7	697		NB	RADIUS	1.179	1.311	1	697						
NB	BCT	1.495	1.637	RADIUS	750		NB	1	1.495	1.637	RADIUS	750						
NB	RADIUS	1.641	1.879	7	1257		NB	RADIUS	1.577	1.830	2A	1336						
NB	4	1.930	2.044	A	602		NB	1	1.877	2.044	A	882						
NB	A	2.155	2.252	7	512		NB	A-1	2.155	2.252	1	512						
NB	RADIUS	2.905	2.930	7	132		NB	RADIUS	2.905	2.930	1	132						

**\*NOTICE:**

Begin/End Milepoints are estimated to include the entire length of the rail AND the End Treatments. The Engineer may adjust the termini to ensure proper installation of the guardrail system.

**Totals:**

Item	Quantity	Unit
Remove Guardrail	11732	LF
Guardrail-Steel W Beam	13174	LF
ET TY 1	15	EA
ET TY 2A	1	EA
BEC TY A	2	EA
TS 1	6	EA

REMOVE GUARDRAIL							INSTALL GUARDRAIL							ADDITIONAL MATERIAL				
LANE	END TREAT.	BEGIN MILEPOINT	END MILEPOINT	END TREAT.	LIN FEET	REMARKS	LANE	END TREAT.	BEGIN MILEPOINT	END MILEPOINT	END TREAT.	LIN FEET	REMARKS	24" Pipe	End Anchor	MES TY 1-24"	CL. II CH. LINING	Embankment
SB	BCT	9.071	9.026	2A	238		SB	1	9.071	9.026	2A	238						
SB	BCT	8.496	8.456	A	211		SB	4A	8.496	8.456	A	211						
SB	BCT	5.652	5.585	2A	354		SB	1	5.652	5.585	2A	354						
SB	BCT	1.574	1.340	2A	1236		SB	4A	1.781	1.548	2A	1230						
SB	BCT	0.940	0.895	A	238		SB	4A	0.940	0.895	A	238						
SB	BCT	0.465	0.320	A	766		SB	1	0.465	0.320	A	766						
NB	BCT	1.042	1.137	A	502		NB	1	1.042	1.137	A	502						
NB	BCT	2.815	2.945	A	686		NB	1	2.815	2.945	A	686						
NB	3	9.198	9.277	2A	417		NB	3	9.180	9.277	2A	512		40	1	2	5 tons	5 CY

**\*NOTICE:**

Begin/End Milepoints are estimated to include the entire length of the rail AND the End Treatments. The Engineer may adjust the termini to ensure proper installation of the guardrail system.

**Totals:**

Item	Quantity	Unit
Remove Guardrail	4409	LF
Guardrail-Steel W Beam	4499	LF
ET TY 1	4	EA
ET TY 2A	3	EA
BEC TY A	5	EA
ET TY 3	1	EA
ET TY 4A	3	EA