



Matthew G. Bevin
Governor

COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Greg Thomas
Secretary

February 21, 2019

CALL NO. 114
CONTRACT ID NO. 191009
ADDENDUM # 2

Subject: MADISON COUNTY, STP 6271 016
Letting February 22, 2019

(1) Revised - Proposal Bid Items - Pages 204-209(a) of 209

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures



An Equal Opportunity Employer M/F/D

PROPOSAL BID ITEMS

191009

Page 1 of 7

Report Date 2/21/19

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	29,366.00	TON		\$	
0030	00020		TRAFFIC BOUND BASE	29.00	TON		\$	
0050	00100		ASPHALT SEAL AGGREGATE	188.00	TON		\$	
0060	00103		ASPHALT SEAL COAT	23.00	TON		\$	
0070	00190		LEVELING & WEDGING PG64-22	248.00	TON		\$	
0080	00212		CL2 ASPH BASE 1.00D PG64-22	3,160.00	TON		\$	
0090	00214		CL3 ASPH BASE 1.00D PG64-22	7,897.00	TON		\$	
0100	00301		CL2 ASPH SURF 0.38D PG64-22	897.00	TON		\$	
0105	00356		ASPHALT MATERIAL FOR TACK (ADDED: 2-18-19)	8.30	TON		\$	
0120	00388		CL3 ASPH SURF 0.38B PG64-22	2,512.00	TON		\$	
0130	02071		JPC PAVEMENT-11 IN	33,189.00	SQYD		\$	
0142	02223		GRANULAR EMBANKMENT (ADDED: 2-18-19)	13,825.00	CUYD		\$	
0145	02599		FABRIC-GEOTEXTILE TYPE IV (ADDED: 2-18-19)	44,375.00	SQYD		\$	
0150	02677		ASPHALT PAVE MILLING & TEXTURING	668.00	TON		\$	
0170	20071EC		JOINT ADHESIVE	26,880.00	LF		\$	
0180	21289ED		LONGITUDINAL EDGE KEY	14,420.00	LF		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0190	00078		CRUSHED AGGREGATE SIZE NO 2	5,011.00	TON		\$	
0200	01000		PERFORATED PIPE-4 IN	567.00	LF		\$	
0210	01010		NON-PERFORATED PIPE-4 IN	269.00	LF		\$	
0220	01020		PERF PIPE HEADWALL TY 1-4 IN	3.00	EACH		\$	
0230	01028		PERF PIPE HEADWALL TY 3-4 IN	8.00	EACH		\$	
0240	01811		STANDARD CURB AND GUTTER MOD	438.00	LF		\$	
0250	01830		STANDARD INTEGRAL CURB	1,454.00	LF		\$	
0260	01845		ISLAND INTEGRAL CURB	449.00	LF		\$	
0270	01875		STANDARD HEADER CURB	251.00	LF		\$	
0280	01915		STANDARD BARRIER MEDIAN TYPE 1	120.00	SQYD		\$	
0290	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	38.00	EACH		\$	
0300	01983		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	33.00	EACH		\$	
0310	01985		DELINEATOR FOR BARRIER - YELLOW	8.00	EACH		\$	
0320	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	75.00	EACH		\$	
0330	02014		BARRICADE-TYPE III	20.00	EACH		\$	
0340	02091		REMOVE PAVEMENT	2,061.00	SQYD		\$	
0350	02159		TEMP DITCH	8,895.00	LF		\$	
0360	02230		EMBANKMENT IN PLACE (REVISED: 2-21-19)	119,898.00	CUYD		\$	
0370	02242		WATER	700.00	MGAL		\$	
0380	02261		FENCE-WOVEN WIRE	4,039.00	LF		\$	
0390	02351		GUARDRAIL-STEEL W BEAM-S FACE	9,050.00	LF		\$	

PROPOSAL BID ITEMS

191009

Page 2 of 7

Report Date 2/21/19

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0400	02360		GUARDRAIL TERMINAL SECTION NO 1	11.00	EACH		\$	
0410	02363		GUARDRAIL CONNECTOR TO BRIDGE END TY A	4.00	EACH		\$	
0420	02367		GUARDRAIL END TREATMENT TYPE 1	15.00	EACH		\$	
0430	02369		GUARDRAIL END TREATMENT TYPE 2A	9.00	EACH		\$	
0440	02381		REMOVE GUARDRAIL	6,464.00	LF		\$	
0450	02397		TEMP GUARDRAIL	1,437.50	LF		\$	
0460	02429		RIGHT-OF-WAY MONUMENT TYPE 1	71.00	EACH		\$	
0470	02432		WITNESS POST	3.00	EACH		\$	
0480	02545		CLEARING AND GRUBBING ACRES	1.00	LS		\$	
0490	02562		TEMPORARY SIGNS	910.00	SQFT		\$	
0500	02585		EDGE KEY	283.00	LF		\$	
0510	02596		FABRIC-GEOTEXTILE TYPE I	15,000.00	SQYD		\$	
0520	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0530	02654		TRUCK MOUNTED ATTENUATOR	1.00	EACH		\$	
0540	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0550	02690		SAFELOADING	10.00	CUYD		\$	
0560	02701		TEMP SILT FENCE	8,894.00	LF		\$	
0570	02703		SILT TRAP TYPE A	58.00	EACH		\$	
0580	02704		SILT TRAP TYPE B	58.00	EACH		\$	
0590	02705		SILT TRAP TYPE C	58.00	EACH		\$	
0600	02706		CLEAN SILT TRAP TYPE A	58.00	EACH		\$	
0610	02707		CLEAN SILT TRAP TYPE B	58.00	EACH		\$	
0620	02708		CLEAN SILT TRAP TYPE C	58.00	EACH		\$	
0630	02726		STAKING	1.00	LS		\$	
0640	02731		REMOVE STRUCTURE KY 627 OVER I-75	1.00	LS		\$	
0650	02775		ARROW PANEL	4.00	EACH		\$	
0660	03145		CONC MEDIAN BARRIER TYPE 9C2	372.00	LF		\$	
0670	03171		CONCRETE BARRIER WALL TYPE 9T	9,550.00	LF		\$	
0680	04953		TEMP RELOCATION OF SIGNAL HEAD	4.00	EACH		\$	
0690	05950		EROSION CONTROL BLANKET	9,935.00	SQYD		\$	
0700	05952		TEMP MULCH	222,842.00	SQYD		\$	
0710	05953		TEMP SEEDING AND PROTECTION	140,360.00	SQYD		\$	
0720	05963		INITIAL FERTILIZER	12.00	TON		\$	
0730	05964		MAINTENANCE FERTILIZER	12.00	TON		\$	
0740	05985		SEEDING AND PROTECTION	222,842.00	SQYD		\$	
0750	05990		SODDING	1,000.00	SQYD		\$	
0760	05992		AGRICULTURAL LIMESTONE	145.00	TON		\$	
0770	06401		FLEXIBLE DELINEATOR POST-M/W	141.00	EACH		\$	
0780	06403		FLEXIBLE DELINEATOR POST-B/W	78.00	EACH		\$	
0790	06404		FLEXIBLE DELINEATOR POST-M/Y	27.00	EACH		\$	
0800	06510		PAVE STRIPING-TEMP PAINT-4 IN	27,000.00	LF		\$	
0810	06511		PAVE STRIPING-TEMP PAINT-6 IN	46,000.00	LF		\$	
0820	06514		PAVE STRIPING-PERM PAINT-4 IN	37,887.00	LF		\$	
0830	06515		PAVE STRIPING-PERM PAINT-6 IN	38,924.00	LF		\$	
0840	06517		PAVE STRIPING-PERM PAINT-12 IN	3,387.00	LF		\$	
0850	06568		PAVE MARKING-THERMO STOP BAR-24IN	406.00	LF		\$	
0860	06570		PAVE MARKING-PAINT CROSS-HATCH	6,820.00	SQFT		\$	

PROPOSAL BID ITEMS

191009

Page 3 of 7

Report Date 2/21/19

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0870	06572		PAVE MARKING-DOTTED LANE EXTEN	2,677.00	LF		\$	
0880	06574		PAVE MARKING-THERMO CURV ARROW	53.00	EACH		\$	
0890	06575		PAVE MARKING-THERMO COMB ARROW	9.00	EACH		\$	
0900	06576		PAVE MARKING-THERMO ONLY	5.00	EACH		\$	
0910	06578		PAVE MARKING-THERMO MERGE ARROW	4.00	EACH		\$	
0920	06588		PAVEMENT MARKER TY IVA-BY TEMP	320.00	EACH		\$	
0930	08100		CONCRETE-CLASS A	17.20	CUYD		\$	
0940	08150		STEEL REINFORCEMENT	214.00	LB		\$	
0950	08903		CRASH CUSHION TY VI CLASS BT TL3	10.00	EACH		\$	
0960	10020NS		FUEL ADJUSTMENT	28,700.00	DOLL	\$1.00	\$	\$28,700.00
0970	10030NS		ASPHALT ADJUSTMENT	26,000.00	DOLL	\$1.00	\$	\$26,000.00
0980	20362ES403		SHOULDER RUMBLE STRIPS-SAWED	20,896.00	LF		\$	
0990	20430ED		SAW CUT	680.00	LF		\$	
1000	23274EN11F		TURF REINFORCEMENT MAT 1	11,257.00	SQYD		\$	
1010	23877EC		CONC MEDIAN BARRIER WALL TY 14C	67.00	LF		\$	
1020	24489EC		INLAID PAVEMENT MARKER	1,330.00	EACH		\$	
1030	24668EC		STEEL ENCASEMENT PIPE 16 IN	213.00	LF		\$	
1040	24814EC		PIPELINE INSPECTION	1,000.00	LF		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1050	00440		ENTRANCE PIPE-15 IN	241.00	LF		\$	
1060	00441		ENTRANCE PIPE-18 IN	172.00	LF		\$	
1070	00443		ENTRANCE PIPE-24 IN	74.00	LF		\$	
1080	00462		CULVERT PIPE-18 IN	435.00	LF		\$	
1090	00464		CULVERT PIPE-24 IN	226.00	LF		\$	
1100	00466		CULVERT PIPE-30 IN	203.00	LF		\$	
1110	00469		CULVERT PIPE-42 IN	125.00	LF		\$	
1120	00521		STORM SEWER PIPE-15 IN	94.00	LF		\$	
1130	00522		STORM SEWER PIPE-18 IN	230.00	LF		\$	
1140	00524		STORM SEWER PIPE-24 IN	100.00	LF		\$	
1150	00526		STORM SEWER PIPE-30 IN	50.00	LF		\$	
1160	00528		STORM SEWER PIPE-36 IN	451.00	LF		\$	
1170	00529		STORM SEWER PIPE-42 IN	40.00	LF		\$	
1180	00530		STORM SEWER PIPE-48 IN	36.00	LF		\$	
1190	01204		PIPE CULVERT HEADWALL-18 IN	3.00	EACH		\$	
1200	01208		PIPE CULVERT HEADWALL-24 IN	3.00	EACH		\$	
1210	01210		PIPE CULVERT HEADWALL-30 IN	4.00	EACH		\$	
1220	01212		PIPE CULVERT HEADWALL-36 IN	2.00	EACH		\$	
1230	01214		PIPE CULVERT HEADWALL-42 IN	3.00	EACH		\$	
1240	01433		SLOPED BOX OUTLET TYPE 1-18 IN	4.00	EACH		\$	
1250	01434		SLOPED BOX OUTLET TYPE 1-24 IN	1.00	EACH		\$	
1260	01450		S & F BOX INLET-OUTLET-18 IN	6.00	EACH		\$	
1270	01451		S & F BOX INLET-OUTLET-24 IN	6.00	EACH		\$	
1280	01452		S & F BOX INLET-OUTLET-30 IN	1.00	EACH		\$	
1290	01456		CURB BOX INLET TYPE A	4.00	EACH		\$	
1300	01490		DROP BOX INLET TYPE 1	6.00	EACH		\$	

PROPOSAL BID ITEMS

191009

Page 4 of 7

Report Date 2/21/19

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1310	01643		JUNCTION BOX-24 IN	4.00	EACH		\$	
1320	01645		JUNCTION BOX-36 IN	2.00	EACH		\$	
1330	01646		JUNCTION BOX-42 IN	1.00	EACH		\$	
1340	01691		FLUME INLET TYPE 2	4.00	EACH		\$	
1350	01767		MANHOLE TYPE C	5.00	EACH		\$	
1360	02477		CAP CATCH BASIN	1.00	SQYD		\$	
1370	02483		CHANNEL LINING CLASS II	25.00	TON		\$	
1380	02484		CHANNEL LINING CLASS III	670.00	TON		\$	
1390	02600		FABRIC GEOTEXTILE TY IV FOR PIPE	4,022.00	SQYD	\$2.00	\$	\$8,044.00
1400	20211ES706		BORE & JACK PIPE	94.00	LF		\$	

Section: 0004 - BRIDGE- 26899

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1410	02231		STRUCTURE GRANULAR BACKFILL	460.00	CUYD		\$	
1420	02998		MASONRY COATING	1,435.00	SQYD		\$	
1430	03299		ARMORED EDGE FOR CONCRETE	179.60	LF		\$	
1440	08001		STRUCTURE EXCAVATION-COMMON	380.00	CUYD		\$	
1450	08016		REINF CONC SLOPE WALL-6 IN	1,050.00	SQYD		\$	
1460	08033		TEST PILES	218.00	LF		\$	
1470	08039		PRE-DRILLING FOR PILES (REVISED: 2-18-19)	1,176.00	LF		\$	
1480	08046		PILES-STEEL HP12X53	2,980.00	LF		\$	
1490	08094		PILE POINTS-12 IN	106.00	EACH		\$	
1500	08100		CONCRETE-CLASS A	349.20	CUYD		\$	
1510	08104		CONCRETE-CLASS AA	764.80	CUYD		\$	
1520	08135		MECHANICAL REINF COUPLER #10	16.00	EACH		\$	
1530	08150		STEEL REINFORCEMENT	69,862.00	LB		\$	
1540	08151		STEEL REINFORCEMENT-EPOXY COATED	313,759.00	LB		\$	
1550	08635		PRECAST PC I BEAM TYPE 6	2,446.70	LF		\$	
1560	21532ED		RAIL SYSTEM TYPE III	494.10	LF		\$	

Section: 0005 - BRIDGE-26910

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1570	02403		REMOVE CONCRETE MASONRY	9.00	CUYD		\$	
1580	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1590	08100		CONCRETE-CLASS A	21.60	CUYD		\$	
1600	08150		STEEL REINFORCEMENT	1,886.00	LB		\$	

Section: 0006 - BRIDGE-26911

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1610	02403		REMOVE CONCRETE MASONRY	14.00	CUYD		\$	
1620	08003		FOUNDATION PREPARATION	1.00	LS		\$	
1630	08100		CONCRETE-CLASS A	54.20	CUYD		\$	

PROPOSAL BID ITEMS

191009

Page 5 of 7

Report Date 2/21/19

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1640	08150		STEEL REINFORCEMENT	4,833.00	LB		\$	

Section: 0007 - SEWER

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1650	01787		REMOVE MANHOLE	8.00	EACH		\$	
1660	01810		STANDARD CURB AND GUTTER	18.00	LF		\$	
1670	01812		REMOVE CURB AND GUTTER	18.00	LF		\$	
1680	02091		REMOVE PAVEMENT ALL DEPTHS	93.00	SQYD		\$	
1690	02650		MAINTAIN & CONTROL TRAFFIC SANITARY SEWER	1.00	LS		\$	
1700	03387		PVC PIPE-8 IN	341.00	LF		\$	
1710	03389		PVC PIPE-10 IN	824.00	LF		\$	
1720	15000		S BYPASS PUMPING	1.00	EACH		\$	
1730	15020		S ENCASEMENT STEEL OPEN CUT RANGE 1	85.00	LF		\$	
1740	15022		S ENCASEMENT STEEL OPEN CUT RANGE 3 SCH 40 STEEL CASING PIPE	60.00	LF		\$	
1750	15022		S ENCASEMENT STEEL OPEN CUT RANGE 3 SEE PLANS	245.00	LF		\$	
1760	15023		S ENCASEMENT STEEL OPEN CUT RANGE 4 SEE PLANS	215.00	LF		\$	
1770	15029		S FORCE MAIN AIR RLS/VAC VLV SPCL	2.00	EACH		\$	
1780	15061		S FORCE MAIN PVC 08 INCH	2,090.00	LF		\$	
1790	15068		S FORCE MAIN SPECIAL 1.5" SDR21 PVC	130.00	LF		\$	
1800	15092		S MANHOLE	8.00	EACH		\$	
1810	15094		S MANHOLE ADJUST TO GRADE	5.00	EACH		\$	
1820	15099		S MANHOLE TAP EXISTING	5.00	EACH		\$	
1830	15101		S MANHOLE WITH DROP 4" DIAMETER	1.00	EACH		\$	
1840	15101		S MANHOLE WITH DROP INTERNAL DROP	1.00	EACH		\$	
1850	15104		S PIPE DUCTILE IRON 08 INCH	271.00	LF		\$	
1860	15114		S PIPE PVC 12 INCH	162.00	LF		\$	
1870	20757ED		PAVEMENT REPAIR	93.00	SQYD		\$	
1880	21415ND		EROSION CONTROL SANITARY SEWER	1.00	LS		\$	
1890	23300ED		CRUSHED STONE	662.00	TON		\$	
1900	24814EC		PIPELINE INSPECTION	3,859.00	LF		\$	
1910	40095		SEEDING AND MULCHING	3.00	ACRE		\$	

Section: 0008 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1920	06400		GMSS GALV STEEL TYPE A	312.50	LB		\$	
1930	06406		SBM ALUM SHEET SIGNS .080 IN	670.00	SQFT		\$	
1940	06407		SBM ALUM SHEET SIGNS .125 IN	102.00	SQFT		\$	
1950	06410		STEEL POST TYPE 1	1,926.00	LF		\$	

PROPOSAL BID ITEMS

191009

Page 6 of 7

Report Date 2/21/19

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1960	06441		GMSS GALV STEEL TYPE C	256.50	LB		\$	
1970	06451		REMOVE SIGN SUPPORT BEAM	4.00	EACH		\$	
1980	06490		CLASS A CONCRETE FOR SIGNS	9.22	CUYD		\$	
1990	06491		STEEL REINFORCEMENT FOR SIGNS	228.00	LB		\$	
2000	20418ED		REMOVE & RELOCATE SIGNS	2.00	EACH		\$	
2010	21596ND		GMSS TYPE D	15.00	EACH		\$	
2020	24631EC		BARCODE SIGN INVENTORY	371.00	EACH		\$	

Section: 0009 - SIGNALIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2030	04792		CONDUIT-1 IN	88.00	LF		\$	
2040	04795		CONDUIT-2 IN	45.00	LF		\$	
2050	04811		ELECTRICAL JUNCTION BOX TYPE B	9.00	EACH		\$	
2060	04820		TRENCHING AND BACKFILLING	820.00	LF		\$	
2070	04830		LOOP WIRE	3,144.00	LF		\$	
2080	04844		CABLE-NO. 14/5C	1,964.00	LF		\$	
2090	04850		CABLE-NO. 14/1 PAIR	4,695.00	LF		\$	
2100	04885		MESSENGER-10800 LB	970.00	LF		\$	
2110	04895		LOOP SAW SLOT AND FILL	1,288.00	LF		\$	
2120	04931		INSTALL CONTROLLER TYPE 170	2.00	EACH		\$	
2130	04932		INSTALL STEEL STRAIN POLE	8.00	EACH		\$	
2140	20094ES835		TEMP RELOCATION OF SIGNAL HEAD	36.00	EACH		\$	
2150	20188NS835		INSTALL LED SIGNAL-3 SECTION	19.00	EACH		\$	
2160	20390NS835		INSTALL COORDINATING UNIT	2.00	EACH		\$	
2170	23157EN		TRAFFIC SIGNAL POLE BASE	35.10	CUYD		\$	
2180	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	715.00	LF		\$	
2190	24901EC		PVC CONDUIT-2 IN-SCHEDULE 80	60.00	LF		\$	
2200	24955ED		REMOVE SIGNAL EQUIPMENT	2.00	EACH		\$	

Section: 0010 - LIGHTING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2210	04714		POLE 120 FT MTG HT HIGH MAST	9.00	EACH		\$	
2220	04761		LIGHTING CONTROL EQUIPMENT	2.00	EACH		\$	
2230	04797		CONDUIT-3 IN (REVISED: 2-18-19)	1,041.00	LF		\$	
2240	04800		MARKER	15.00	EACH		\$	
2250	04820		TRENCHING AND BACKFILLING	9,962.00	LF		\$	
2260	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	4.00	EACH		\$	
2270	20392NS835		ELECTRICAL JUNCTION BOX TYPE C	4.00	EACH		\$	
2280	21543EN		BORE AND JACK CONDUIT	1,041.00	LF		\$	
2290	23161EN		POLE BASE-HIGH MAST	45.00	CUYD		\$	
2300	24749EC		HIGH MAST LED LUMINAIRE	44.00	EACH		\$	
2310	24851EC		CABLE-NO. 10/3C DUCTED	10,740.00	LF		\$	

191009

PROPOSAL BID ITEMS

Report Date 2/21/19

Page 7 of 7

Section: 0011 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
2320	02568		MOBILIZATION	1.00	LS		\$	
2330	02569		DEMOBILIZATION	1.00	LS		\$	