



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

July 16, 2021

CALL NO. 117
CONTRACT ID NO. 212264
ADDENDUM # 1

Subject: Harlan County, ER 9020 (333)
Letting July 23, 2021

- (1) Revised - Special Note - Page 119 of 183
- (2) Revised - Proposal Bid Items - Pages 182-183 of 183

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

Special Note for Construction Milestone Dates

Harlan Co. US 421; MP 22.8

The Department has established the milestone dates below. The Department will assess liquidated damages of \$1,000.00 per calendar day for any milestone dates that the Contractor does not meet.

Milestone Date	Requirements
December 15, 2021	Install all soldier piles, and install and lock off (at the specified lock-off load) at least 20% of all anchors.
January 31, 2022	Install and lock off (at the specified lock-off load) at least 75% of all anchors with submitted documentation that at least 60% of all anchors meet the acceptance criteria in Section 10.9 of the Special Note for Tieback Walls.
May 31, 2022	100% completion and acceptance of all tieback wall components (including permanent facing and wall cap) and horizontal drains in wall.
July 31, 2022	Entirety of project completed

PROPOSAL BID ITEMS

212264

Page 1 of 2

Report Date 7/16/21

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00212		CL2 ASPH BASE 1.00D PG64-22	1,525.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	410.00	TON		\$	
0030	00356		ASPHALT MATERIAL FOR TACK	3.00	TON		\$	
0040	02697		EDGE LINE RUMBLE STRIPS	3,200.00	LF		\$	
0050	06510		PAVE STRIPING-TEMP PAINT-4 IN	3,200.00	LF		\$	
0060	06542		PAVE STRIPING-THERMO-6 IN W	3,200.00	LF		\$	
0070	06543		PAVE STRIPING-THERMO-6 IN Y	3,200.00	LF		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0080	00001		DGA BASE	920.00	TON		\$	
0090	00078		CRUSHED AGGREGATE SIZE NO 2	2,760.00	TON		\$	
0100	02091		REMOVE PAVEMENT	2,315.00	SQYD		\$	
0105	02545		CLEARING AND GRUBBING APPROX 1 ACRE (ADDED: 7-16-21)	1.00	LS		\$	
0110	02562		TEMPORARY SIGNS	150.00	SQFT		\$	
0120	02572		QUALITY CONTROL	1.00	LS		\$	
0130	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0140	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0150	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0160	02677		ASPHALT PAVE MILLING & TEXTURING	45.00	TON		\$	
0170	02726		STAKING	1.00	LS		\$	
0180	04933		TEMP SIGNAL 2 PHASE	2.00	EACH		\$	
0190	05950		EROSION CONTROL BLANKET	800.00	SQYD		\$	
0200	08003		FOUNDATION PREPARATION	1.00	LS		\$	
0210	08018		RETAINING WALL	18,612.50	SQFT		\$	
0220	08711		BRIDGE CHAIN LINK FENCE-6 FT	650.00	LF		\$	
0230	20610NC		INSTRUMENTATION	1.00	LS		\$	
0240	21415ND		EROSION CONTROL	1.00	LS		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0250	00464		CULVERT PIPE-24 IN	44.00	LF		\$	
0260	00468		CULVERT PIPE-36 IN	92.00	LF		\$	
0270	01208		PIPE CULVERT HEADWALL-24 IN	2.00	EACH		\$	
0280	01212		PIPE CULVERT HEADWALL-36 IN	2.00	EACH		\$	
0290	01310		REMOVE PIPE	136.00	LF		\$	
0300	02220		FLOWABLE FILL	22.00	CUYD		\$	
0310	02602		FABRIC-GEOTEXTILE CLASS 1	5,400.00	SQYD		\$	
0320	22410EN		HORIZONTAL DRAIN	9,600.00	LF		\$	

212264

PROPOSAL BID ITEMS

Page 2 of 2

Report Date 7/16/21

Section: 0004 - GUARDRAIL

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0330	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	33.00	EACH		\$	
0340	02351		GUARDRAIL-STEEL W BEAM-S FACE	1,600.00	LF		\$	
0350	02381		REMOVE GUARDRAIL	725.00	LF		\$	
0360	02391		GUARDRAIL END TREATMENT TYPE 4A	2.00	EACH		\$	

Section: 0005 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0365	02568		MOBILIZATION	1.00	LS		\$	
0370	02569		DEMOBILIZATION	1.00	LS		\$	