

Steven L. Beshear Governor Frankfort, Kentucky 40622 www.transportation.ky.gov/

Michael W. Hancock, P.E. Secretary

October 10, 2012

CALL NO. 200 CONTRACT ID NO. 121042 ADDENDUM # 1

Subject: Barren County, 121GR12D042-IM NH

Letting October 19, 2012

(1) Revised - Plan Sheets - R2G & R88

Proposal revisions are available at $\underline{\text{http://transportation.ky.gov/Construction-}}$ Procurement/.

Plan revisions are available at http://www.lynnimaging.com/kytransportation/.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Ryan Griffith

Director

Division of Construction Procurement

RG:ks

Enclosures



COUNTY OF	ITEM NO.	SHEET NO.
BARREN AND HART	3-14.00	R2G

		1	BARREN COUNTY	HART COUNTY	HART COUNTY	BARREN COUNTY	HART COUNTY	T	T	1	T	<u> </u>	T	T	T	T	T	T	1 AND HA
	DECODIDETION		I-65	I-65	I-65	KY 2746	KY 2746	 								BARREN	HART	PROJECT	NOTES:
ITEM	DESCRIPTION	UNIT	STA. 12823+00 TO	STA. 12848+46 TO	STA. 13017+00 TO	STA. 711+20 TO	STA. 699+28.88	KY 2747	KY 218	KY 335	RAMP A	RAMP B	RAMP C	RAMP D	МОТ	TOTALS	TOTALS	TOTALS	
			12848+46	13017+00	3066+00	714+00	711+20									_			EARTHWORK C
71	CRUSHED AGGREGATE SIZE NO. 57 (18)	TON	22	60	30											22	90	112	109,249 COM
78	CRUSHED AGGREGATE SIZE NO. 2 (17)	TON	6,096	12,192	6,096											6,096	18,288	24,384	384 COM
1015	INSPECT & CERTIFY EDGE DRAIN SYSTEM	LS														1	1	2	4,081 EMB BI
1310	REMOVE PIPE 3	LF	16	100	70				16			4				16	190	206	11 COM
1584	CAP DROP BOX INLET 3	EACH		4												0	4	4	410 EMB BE
1691	FLUME INLET TYPE 2	EACH		1												0	1	1	12,221 COM
1706	REMOVE CATCH BASIN ③	EACH	3	22												3	22	25	1,108 COM
1825	ISLAND CURB AND GUTTER	LF					100									0	100	100	1,646 COM
1845	ISLAND INTEGRAL CURB	LF							71							0	71	71	2,554 COM
1955	CONC MEDIAN BARRIER TYPE 12C1 (50)	LF		150	76											0	226	226	4,092 COM
1967	CONC MEDIAN BARRIER TYPE 12C (50)	LF	2449	15,676	7437						22		10	20		2,449	23,113	25,562	509 COM
1982	DELINEATOR FOR GUARDRAIL - WHITE	EACH	14	182	114	1	31				23	11	10	20		15	391	406	13,776 COM
1983	DELINEATOR FOR GUARDRAIL - YELLOW	EACH		1016	0.4.4		_		1.0		20	2		16		0	18	18	150,041 EXC 149,906 SR
1984	DELINEATOR FOR TEMP BARRIER - WHITE	EACH	448	4,016	844				16 16		20	20				448	4,916	5,364	
1985	DELINEATOR FOR BARRIER - YELLOW	EACH	28	251	1,792		2100		10		1000	20				28	2,099	2,127	299,947 TOTAL
2003	RELOCATE TEMP CONC BARRIER (2)	LF	17675	126,125	31,253	1	2100		<u> </u>		1000	1000			1	17,675	161,478	179,153	36,047 EMB
2014	BARRICADE TYPE III	EACH	2			1	<u> </u>		139		<u> </u>	1			1	3	120	12	19,916 EMB
2081	JPC PAVEMENT 8 IN SHLD	SQ YD	2.746	10.500	10.000	200	446		159							0	139	139	722 EMB
2159	TEMPORARY DITCH	LF	2,746 2746	19,500	10,000	280	446									3026	29,946	32,972	3,213 EMB
2160	CLEAN TEMPORARY DITCH	LF	69	19,500 3,372	10,000 1284	280	440					240	455	142		3026	29,946 5,493	32,972	729 EMB
2165	REMOVE PAVED DITCH	SQYD CU YD	13,498	190,239	67,661	348	4117	421	13754		1108	1646	2554	4601		69		5,562	4,934 EMB
2200	ROADWAY EXCAVATION GRANULAR EMBANKMENT (4)	CU YD	15,496	92	50	346	4117	721	13/34		1100	1040	2334	4001		13,846	286,101 142	299,947	976 EMB
2223	DITCHING (5)	LF	5000	30,000	4000		+									5,000	34,000	39,000	715 EMB
2259	FENCE - TEMPORARY (6)	LF	3,000	13,559	500											3,000	14,059	17,059	948 EMB
2262	FENCE - TEMPORARY (6) FENCE - WOVEN WIRE TYPE 1 (6)	LF	3,000	13,339	62				349				124			0	535	535	68,200 EMB
2265	REMOVE FENCE (6)	LF			131		309		110				1			0	550	550	
2267	REMOVE AND RESET FENCE (VINYL)	LF			131		303		288							0	288	288	① APPROX. 80 AC
2268	REMOVE AND REPLACE FENCE (WOVEN WIRE TYPE 1)	LF	5,080	33,906	9,274		215		813		1003	1445	533	253		5,080	47,442	52,522	② ASSUMES A TO
2351	GUARDRAIL-STEEL W BEAM-S FACE	LF	3,000	33,300	3)271		1625		1862.5		1700	650	400	1962.5		0	8,200	8,200	TEMP BARRIER W
2360	GUARDRAIL TERMINAL SECTION NO 1	EACH					1										1	1	OF THAT 35,160 AND RETURNED
2363	GUARDRAIL CONNECTOR TO BRIDGE END TYPE A	EACH					4		2							0	6	6	1 AND 33,843 LF
2367	GUARDRAIL END TREATMENT TYPE 1	EACH	1	9		1	1									2	10	12	BY THE CONTRACTOR
2369	GUARDRAIL END TREATMENT TYPE 2A	EACH	2	8	5							2	1	2		2	18	20	COMPLETION OF
2371	GUARDRAIL END TREATMENT TYPE 7	EACH					1	2								0	3	3	3 INCLUDES QUANT
2373	GUARDRAIL END TREATMENT TYPE 3	EACH			1											0	1	1	PIPE DRAINAGE
2381	REMOVE GUARDRAIL (8)	LF	1,385	11,654	4450	42	1,570		2,287			546	374	1914		1,427	22,795	24,222	4 NOMINAL QUANT
2391	GUARDRAIL END TREATMENT TYPE 4A	EACH			4				2					2		0	8	8	CAPPING SINKH
2429	RIGHT-OF-WAY MONUMENT TYPE 1	EACH					3		7							0	10	10	5 FOR CLEANING (
2432	WITNESS POST	EACH					3									0	3	3	DROP BOXES
2469	CLEAN SINKHOLE	EACH		7	5											0	12	12	6 CONTRACTOR SH
2483	CHANNEL LINING CLASS II (18)	TON	43	301	91		5.3									43	397.3	440.3	COORDINATE WI
2484	CHANNEL LINING CLASS III	TON		98	604							88	87	71		0	948	948	KYTC ALONG EX
2545	CLEARING AND GRUBBING (1)	LS														1	1	2	LIVESTOCK.
2555	CONCRETE - CLASS B 4	CYUYD		19	14											0	33	33	7 CONTRARY TO S
2562	SIGNS	SQ FT			1500				350		100	100	100	100	392		2,642	2,642	GUARDRAIL POS
2568	MOBILIZATION	LS														1	1	1	8 REMOVE ALL EX
2569	DEMOBILIZATION	LS														1	1	1	PROJECT LIMITS
2570	PROJECT CPM SCHEDULE (9)	LS														1	1	2	CENTRAL SIGN S AT 1224 WILKERS
2585	EDGE KEY	LF	72		72	28	28		48	32			4	4.5-		100	180	280	
2596	FABRIC - GEOTEXTILE TYPE I (18)	SQ YD	83	367	1,466		11					240	455	142		83	2681	2,764	
2599	FABRIC - GEOTEXTILE TYPE IV (4)	SQ YD	21,183	42,604	21,293									400		21,183	63,897	85,080	THE CPM SCHEE
2600	FABRIC - GEOTEXTILE TYPE IV FOR PIPE	SQ YD	518	7,201	1,780		128		919			12		423		518	10,463	10,981	_
2625	REMOVE HEADWALL	EACH			1		1		2					2		0	6	6	50% OF THE TO
2650	MAINTAIN AND CONTROL TRAFFIC	LS														1	1	2	INSTALLED PIPE TYPE (SEE SUPPL
2671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2	2	10	1	1							1		3	13	16	THE VOLC OUTL
2676	MOBILIZATION FOR MILLING & TEXTURING	LS											1	10	1	1	1	2	(1) CLEAN PERMANEN
2690	SAFELOADING	CU YD	4.16	13	15								1	12		4.16	40	44.16	BASED ON 3 CLE
2696	SHOULDER RUMBLE STRIPS - SAWED	LF	10,184	67,416	36,386	222	4.4.0									10,184	103,802		SEASON, 2 CONS NOTES CONTINUED
2701	TEMPORARY SILT FENCE	LF	2,546	17,700	9,700	280	446								<u> </u>	2,826	27,846	30,672	INDIES CONTINUED

V	O	T	E	S :	

EARTHWORK	CALCULATIONS
100 010 001	(05)

Ε	ARTHWO	RK (CALCUL	ATIONS
	109,249	СОМ		(65)
	384	COM		(2746)
	4,081	EMB	BENCH	(2746)
	11	COM		(2747)
	410	EMB	BENCH	(2747)
	12,221	COM		(218)
	1,108	COM		RAMPA
	1,646	COM		RAMPB
	2,554	COM		RAMPC
	4,092	COM		RAMPD
	509	COM		RAMPD-TR
_	13,776	COM		MEDIAN ACCESS
	150,041			
	149,906	SR		
-	299,947	TOTA	L EXCAVA	ΓΙΟΝ
	36,047	ЕМВ		(65)
	19,916	EMB		(2746)
	722	EMB		(2747)
	3,213	EMB		(218)
	729	EMB		RAMPA
	4,934	EMB		RAMPB
	976	EMB		RAMPB-TR
	715	EMB		RAMPC

APPROX. 80 ACRES (6 BARREN/74 HART)

RAMPD

- ASSUMES A TOTAL OF 69,003 LF OF TEMP BARRIER WALL WILL BE REQUIRED OF THAT 35,160 LF WILL BE RELOCATED AND RETURNED TO REST AREA (MP 55) AND 33,843 LF IS TO BE FURNISHED BY THE CONTRACTOR AND WILL REMAIN THE CONTRACTORS PROPERTY UPON COMPLETION OF CONSTRUCTION
- INCLUDES QUANTITIES CARRIED OVER FROM PIPE DRAINAGE SUMMARY SHEETS
- NOMINAL QUANTITY TO BE USED FOR CAPPING SINKHOLES & ACCESS GATES
- FOR CLEANING OF EXISTING PIPES AND DROP BOXES
- CONTRACTOR SHALL CONTACT AND COORDINATE WITH ANY OWNERS AND THE KYTC ALONG EXISTING FENCE THAT HAS LIVESTOCK.
- CONTRARY TO STANDARD DRAWING GUARDRAIL POSTS WILL BE 7' IN LENGTH
- REMOVE ALL EXIST. GUARDRAIL ALONG PROJECT LIMITS AND TRANSPORT TO THE CENTRAL SIGN SHOP AND RECYCLE CENTER AT 1224 WILKERSON BLVD. IN FRANKFORT.
- THE PRECONSTRUCTION MEETING WILL NOT BE SCHEDULED UNTIL AFTER THE CPM SCHEDULE IS SUBMITTED.
- 50% OF THE TOTAL LINEAR FEET OF ALL INSTALLED PIPE REGARDLESS OF MATERIAL TYPE (SEE SUPPLEMENTAL SPECIFICATIONS).
- CLEAN PERMANENT CONTAINMENT FEATURE. BASED ON 3 CLEANING PER CONSTRUCTION SEASON, 2 CONSTRUCTION SEASON. NOTES CONTINUED SEE SHEET R2H

⚠ REVISED 10-4	-12
----------------	-----

SHEET NO. COUNTY OF ITEM NO. 3-14.00 R2G AND HART

			BARREN COUNTY	HART COUNTY	HART COUNTY	BARREN COUNTY	Y HART COUNTY												AND HA
ITEM	DESCRIPTION	UNIT	I-65 STA, 12823+00	I-65 STA. 12848+46	I-65 STA. 13017+00	KY 2746 STA. 711+20	KY 2746 STA. 699+28.88	KY 2747	KY 218	KY 335	RAMP A	RAMP B	RAMP C	RAMP D	мот	BARREN	HART TOTALS	PROJECT	NOTES:
			T0 12848+46	T0 13017+00	T0 3066+00	T0 714+00	T0 711+20									TOTALS	TUTALS	TOTALS	EARTHWORK CA
71	CRUSHED AGGREGATE SIZE NO. 57 (18)	TON	22	60	30											22	90	112	109,249 COM
78	CRUSHED AGGREGATE SIZE NO. 2 (17)	TON	6,096	12,192	6,096											6,096	18,288	24,384	384 COM
1015	INSPECT & CERTIFY EDGE DRAIN SYSTEM	LS	0,030	12,132	0,030											1	10,200	24,364	4,081 EMB BE
1310	REMOVE PIPE (3)	LF	16	100	70				16			4				16	190	206	11 COM
1584	CAP DROP BOX INLET (3)	EACH		4	, ,											0	4	4	410 EMB BE
1691	FLUME INLET TYPE 2	EACH		1												0	1	1	12,221 COM
1706	REMOVE CATCH BASIN (3)	EACH	3	22												3	22	25	1,108 COM
1825	ISLAND CURB AND GUTTER	LF					100									0	100	100	1,646 COM
1845	ISLAND INTEGRAL CURB	LF							71							0	71	71	2,554 COM
1955	CONC MEDIAN BARRIER TYPE 12C1 (50)	LF		150	76											0	226	226	4,092 COM
1967	CONC MEDIAN BARRIER TYPE 12C (50)	LF	2449	15,676	7437											2,449	23,113	25,562	509 COM
1982	DELINEATOR FOR GUARDRAIL - WHITE	EACH	14	182	114	1	31				23	11	10	20		15	391	406	13,776 COM
1983	DELINEATOR FOR GUARDRAIL - YELLOW	EACH										2		16		0	18	18	150,041 EXC
1984	DELINEATOR FOR TEMP BARRIER - WHITE	EACH	448	4,016	844				16		20	20				448	4,916	5,364	149,906 SR
1985	DELINEATOR FOR BARRIER - YELLOW	EACH	28	251	1,792				16		20	20				28	2,099	2,127	299,947 TOTAL
2003	RELOCATE TEMP CONC BARRIER ②	LF	17675	126,125	31,253		2100				1000	1000				17,675	161,478	179,153	76 047 540
2014	BARRICADE TYPE III	EACH	2			1	1		5		1	1			1	3	9	12	36,047 EMB
2081	JPC PAVEMENT 8 IN SHLD	SQ YD							139							0	139	139	19,916 EMB
2159	TEMPORARY DITCH	LF	2,746	19,500	10,000	280	446									3026	29,946	32,972	722 EMB
2160	CLEAN TEMPORARY DITCH	LF	2746	19,500	10,000	280	446									3026	29,946	32,972	3,213 EMB 729 EMB
2165	REMOVE PAVED DITCH	SQYD	69	3,372	1284							240	455	142		69	5,493	5,562	4,934 EMB
2200	ROADWAY EXCAVATION	CU YD	13,498	190,239	67,661	348	4117	421	13754		1108	1646	2554	4601		13,846	286,101	299,947	4,934 EMB 976 EMB
2223	GRANULAR EMBANKMENT (4)	CU YD		92	50											0	142	142	715 EMB
2237	DITCHING (5)	LF	5000	30,000	4000											5,000	34,000	39,000	948 EMB
2259	FENCE - TEMPORARY (6)	LF	3,000	13,559	500											3,000	14,059	17,059	
2262	FENCE - WOVEN WIRE TYPE 1 6	LF			62				349				124			0	535	535	68,200 EMB
2265	REMOVE FENCE (6)	LF			131		309		110							0	550	550	(1) APPROX 80 AC
2267	REMOVE AND RESET FENCE (VINYL)	LF							288		1002		522	252		0	288	288	(1) APPROX, 80 AC
2268	REMOVE AND REPLACE FENCE (WOVEN WIRE TYPE 1)	LF	5,080	33,906	9,274		215		813		1003	1445	533	253		5,080	47,442	52,522	(2) ASSUMES A TOT TEMP BARRIER W
2351	GUARDRAIL-STEEL W BEAM-S FACE	LF					1625		1862.5		1700	650	400	1962.5		0	8,200	8,200	> OF THAT 35,160
2360	GUARDRAIL TERMINAL SECTION NO 1	EACH					1										1	1	AND RETURNED TAND 33,843 LF
2363	GUARDRAIL CONNECTOR TO BRIDGE END TYPE A	EACH					4		2							0	6	6	BY THE CONTRAC
2367	GUARDRAIL END TREATMENT TYPE 1	EACH	1	9	_	1	1					2	1	1 2		2	10	12	THE CONTRACTOR COMPLETION OF
2369	GUARDRAIL END TREATMENT TYPE 2A	EACH	2	8	5		1	2				2	1	2		2	18	20	3) INCLUDES QUANT
2371	GUARDRAIL END TREATMENT TYPE 7	EACH			1		<u> </u>									0	3	3	PIPE DRAINAGE
2373	GUARDRAIL END TREATMENT TYPE 3	EACH LF	1 205	11 654	4450	42	1,570		2,287			546	374	1914		1 427	22.705	24 222	(4) NOMINAL QUANT
2381	REMOVE GUARDRAIL (8)	EACH	1,385	11,654	4430	42	1,570		2,267			340	374	2		1,427	22,795	24,222	CAPPING SINKH
2391 2429	GUARDRAIL END TREATMENT TYPE 4A	EACH			4		2		7		1					0	10	10	
2429	RIGHT-OF-WAY MONUMENT TYPE 1 WITNESS POST	EACH					3		,							0	2	10	⑤ FOR CLEANING (DROP BOXES
2469	CLEAN SINKHOLE	EACH		7	5											0	12	12	
2483	CHANNEL LINING CLASS II (18)	TON	43	301	91		5.3				1					43	397.3	440.3	⑥ CONTRACTOR SH COORDINATE WI
2484	CHANNEL LINING CLASS III	TON	1 73	98	604		3.3					88	87	71		0	948	948	KYTC ALONG EX
2545	CLEARING AND GRUBBING (1)	LS		30	001									'-		1	1	2	LIVESTOCK.
2555	CONCRETE - CLASS B (4)	CYUYD		19	14											0	33	33	(7) CONTRARY TO S
2562	SIGNS	SQ FT			1500				350		100	100	100	100	392		2,642	2,642	GUARDRAIL POS
2568	MOBILIZATION	LS														1	1	1	
2569	DEMOBILIZATION	LS									1					1	1	1	8 REMOVE ALL EXT PROJECT LIMITS
2570	PROJECT CPM SCHEDULE (9)	LS							1				†			1	1	2	CENTRAL SIGN S
2585	EDGE KEY	LF	72		72	28	28		48	32						100	180	280	AT 1224 WILKERS
2596	FABRIC - GEOTEXTILE TYPE I (18)	SQ YD	83	367	1,466		11					240	455	142		83	2681	2,764	9 THE PRECONSTR
2599	FABRIC - GEOTEXTILE TYPE IV (4)	SQ YD	21,183	42,604	21,293		1			1			1			21,183	63,897	85,080	WILL NOT BE S
2600	FABRIC - GEOTEXTILE TYPE IV FOR PIPE	SQ YD	518	7,201	1,780		128		919			12		423		518	10,463	10,981	THE CPM SCHEE
2625	REMOVE HEADWALL	EACH		,	1		1		2				1	2		0	6	1	
2650	MAINTAIN AND CONTROL TRAFFIC	LS														1	1	2	INSTALLED PIPE
2671	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2	2	10	1	1									3	13	16	TYPE (SEE SUPPL
2676	MOBILIZATION FOR MILLING & TEXTURING	LS													1	1	1		(1) CLEAN PERMANEN
2690	SAFELOADING	CU YD	4.16	13	15									12		4.16	40	44.16	BASED ON 3 CLE
2696	SHOULDER RUMBLE STRIPS - SAWED	LF	10,184	67,416	36,386											10,184	103,802	113,986	SEASON, 2 CONS
				1		1	1 - 446		1									1	NOTES CONTINUED

9,700

280

17,700

2,546

LF

446

ALS	EARTHWC	RK CAL	_CUL.	ATION	S
12	109,249	СОМ		(65)	
384	384	COM		(2746)	
2	4,081	EMB BEN	CH	(2746)	
06	11	COM		(2747)	
4	410	EMB BEN	CH	(2747)	
1.5	12,221	COM		(218)	
.5	1,108	COM		RAMPA	
00	1,646	COM		RAMPB	
1	2,554	COM		RAMPC	
26	4,092	COM		RAMPD	
562	509	COM		RAMPD-	TR
06	13,776	СОМ		MEDIAN	ACCES
.8	150,041	EXC			
364	149,906	SR			
L27	299,947	TOTAL EX	XCAVA	ΓΙΟΝ	

APPROX. 80 ACRES (6 BARREN/74 HART)

(65)

(2746)

(2747)

RAMPA

RAMPB

RAMPC

RAMPD

RAMPB-TR

(218)

- ASSUMES A TOTAL OF 69,003 LF OF TEMP BARRIER WALL WILL BE REQUIRED OF THAT 35,160 LF WILL BE RELOCATED AND RETURNED TO REST AREA (MP 55)
- AND 33,843 LF IS TO BE FURNISHED BY THE CONTRACTOR AND WILL REMAIN THE CONTRACTORS PROPERTY UPON COMPLETION OF CONSTRUCTION INCLUDES QUANTITIES CARRIED OVER FROM
- PIPE DRAINAGE SUMMARY SHEETS NOMINAL QUANTITY TO BE USED FOR
- CAPPING SINKHOLES & ACCESS GATES FOR CLEANING OF EXISTING PIPES AND DROP BOXES
- CONTRACTOR SHALL CONTACT AND COORDINATE WITH ANY OWNERS AND THE KYTC ALONG EXISTING FENCE THAT HAS LIVESTOCK.
- CONTRARY TO STANDARD DRAWING GUARDRAIL POSTS WILL BE 7'IN LENGTH
- REMOVE ALL EXIST. GUARDRAIL ALONG PROJECT LIMITS AND TRANSPORT TO THE CENTRAL SIGN SHOP AND RECYCLE CENTER AT 1224 WILKERSON BLVD. IN FRANKFORT.
- THE PRECONSTRUCTION MEETING WILL NOT BE SCHEDULED UNTIL AFTER THE CPM SCHEDULE IS SUBMITTED.
- 50% OF THE TOTAL LINEAR FEET OF ALL INSTALLED PIPE REGARDLESS OF MATERIAL TYPE (SEE SUPPLEMENTAL SPECIFICATIONS).
- CLEAN PERMANENT CONTAINMENT FEATURE. BASED ON 3 CLEANING PER CONSTRUCTION SEASON, 2 CONSTRUCTION SEASON. NOTES CONTINUED SEE SHEET R2H

8: PEC E: 10/4 NAME:

2701

TEMPORARY SILT FENCE

GENERAL SUMMARY I-65 WIDENING

27,846

30,672

2,826

GENERAL

ALL TRAFFIC CONTROL DEVICES SHALL COMPLY WITH THE CURRENT STANDARD DRAWINGS AND THE CURRENT MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

THE CONTRACTOR SHALL MAINTAIN TWO LANES IN EACH DIRECTION WITH A MINIMUM LANE WIDTH OF 11' EXCEPT WHERE NOTED. THE CONTRACTOR SHALL NOTIFY THE BARREN AND HART COUNTY POLICE A MINIMUM OF 2 WEEKS IN ADVANCE OF ANY CLOSURE ON MAINLINE. IF POLICE ASSISTANCE IS DEEMED NECCESSARY BY THE CONTRACTOR. IT SHALL BE AT THEIR EXPENSE.

THE TEMPORARY CONCRETE BARRIER WALLS ARE TO BE CONSTRUCTED OR OBTAINED BY THE CONTRACTOR AS PER NOTE 2 ON R2G

THE CONTRACTOR WILL NOT BE ALLOWED TO HAUL EQUIPMENT OR DRIVE ACROSS THE MEDIAN FROM ONE SIDE OF THE INTERSTATE TO THE OTHER UNLESS APPROPRIATE BARRIER WALL GATES HAVE BEEN INSTALLED. ALL OTHER EQUIPMENT MOVEMENTS FROM ONE SIDE OF THE INTERSTATE TO THE OTHER SHALL UTILIZE THE NEAREST INTERCHANGE. HAULING EQUIPMENT THAT USES I-65 SHALL BE RESTRICTED TO LICENSED VEHICLES ONLY. VEHICLES SHALL NOT STOP OR PARK IN AREAS NOT DESIGNATED BY THE ENGINEER. ANY SHOULDER USED FOR A DECELERATION OR ACCELERATION LANE SHALL BE WIDENED AND PAVED TO ADEQUATELY SUPPORT HEAVY TRUCK TRAFFIC. ALL EXPENSES INCURRED TO CONSTRUCT BARRIER WALL GATES AND REMOVAL THEREOF SHALL BE BORNE BY THE CONTRACTOR AND BE INCIDENTAL TO THE CONTRACT. PAVEMENT NEEDED TO CONSTRUCT BARRIER WALL GATES INCORPORATED IN THE PERMANENT WORK SHALL BE MEASURED FOR PAYMENT.

THE CONSTRACTOR SHALL EXPEDITE EXCAVATION OF ALL ROCK CUTS AND OTHER EXCAVATION IN A CONTINOUS MANNER ONCE WORK HAS STARTED. IF THE CONTRACTOR STOPS WORK IN ANY ONE AREA FOR MORE THAN 2 DAYS. (EXCLUDING HOLIDAYS LISTED WITHIN THESE NOTES). THEN LIQUIDATED DAMAGES WILL BE ASSESSED AT THE CONTRACT RATE FOR EVERY DAY UNTIL WORK RESUMES.

IF THE CONTRACTOR DECIDES TO DEVIATE FROM THE TRAFFIC CONTROL SCHEME AND CONSTRUCTION SCHEDULE OUTLINED IN THESE PLANS OR PROPOSAL, AN ALTERNATE PLAN SHALL BE SUBMITTED IN WRITING TO THE ENGINEER. THE ALTERNATE PLAN MAY BE USED ONLY IF APPROVED IN WRITING BY THE KENTUCKY DIVISION OF DESIGN, TRAFFIC, CONSTRUCTION AND FHWA.

OTHER MAINTENANCE OF TRAFFIC PROPOSALS WILL BE CONSIDERED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS: HOWEVER, ALTERNATE MAINTENANCE OF TRAFFIC SCHEMES WILL NOT BE SUBJECT TO VALUE ENGINEERING UNDER SECTION 111.

THE REQUIREMENTS FOR ALTERNATE MAINTENANCE OF TRAFFIC SCHEMES SHALL BE AT LEAST 11 FOOT LANES FOR THROUGH TRAFFIC. TWO LANES PER DIRECTION SHALL BE OPEN TO TRAFFIC AT ALL TIMES, UNLESS OTHERWISE SPECIFIED IN THE MAINTENANCE OF TRAFFIC PLANS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING POSITIVE DRAINAGE IN SAG AREAS AT MEDIAN INLETS. WHEN THE MEDIAN IS USED AS A TRAVEL LANE AND BEFORE FINISHED ASPHALT IS PLACED, WEDGING IS REQUIRED AT ALL DRAINAGE INLETS. WEDGING IS INCIDENTAL TO THE DRAINAGE INLET. ALL SILT TRAP TYPE C MUST BE REMOVED FROM ALL MEDIAN INLETS PRIOR TO TRAFFIC BEING ALLOWED IN MEDIAN.

THE CONTRACTOR SHALL SUBMIT IN WRITING, PLANS FOR APPROVAL BY THE DEPARTMENT AND THE FHWA BEFORE STOPPING TRAFFIC.

NORMAL CONSIDERATION SHOULD BE GIVEN TO PROPERTY OWNERS FOR THEIR ACCESS.

REPAIR AND/OR UPGRADE PAVEMENT ALONG AND ACROSS EXISTING ROADS WHERE CONSTRUCTION TRAFFIC CROSSES, ACCESS TO ALL PUBLIC ROADS IS TO BE MAINTAINED EXCEPT AS INDICATED IN THE MAINTENANCE OF TRAFFIC NOTES.

CONSTRUCT EROSION CONTROLS AT POINTS WHERE RUNOFF LEAVES THE PROJECT SITE. BEGIN EARTHWORK, UTILIZING TEMPORARY DIVERSION DITCHES TO DIRECT RUNOFF TO EROSION CONTROLS.

THE CONTRACTOR MUST NOTIFY THE DISTRICT PUBLIC INFORMATION OFFICE (PIO), KEIRSTEN JAGGER (DISTRICT 3). AT 270-746-7898 (OFFICE) OR 270-202-0446 (CELL) AND CHRIS JESSIE (DISTRICT 4) 270-401-3193 (OFFICE) WITHIN THE FOLLOWING TIME FRAMES OF PENDING CHANGES IN THEIR WORK SCHEDULE WHICH WILL AFFECT TRAFFIC PATTERNS:

1) AT LEAST FOURTEEN (14) DAYS PRIOR TO BEGINNING PHASE I CONSTRUCTION IN EITHER DIRECTION 2) AT LEAST FIVE (5) DAYS PRIOR TO A RAMP CLOSURE 3) IF A DECISION IS MADE NOT TO CLOSE A RAMP, NOTICE MUST BE GIVEN TO THE PIO 5 DAYS PRIOR TO THE PROPOSED CLOSURE. LANE CLOSURES

WHEN CONSTRUCTION WITHIN 8 FEET OF THE TRAVELED WAY IS IN PROGRESS AND/OR WHEN INSTALLING BARRIER WALL ADJACENT TO A TRAVELED WAY, ONE LANE MAY BE CLOSED. LANE CLOSURES SHALL ONLY BE DURING HOURS OF "LOW TRAFFIC VOLUMES" AS OUTLINED IN THESE TRAFFIC CONTROL NOTES. ALL SIGN PLACEMENT SHALL ALSO BE DONE DURING HOURS OF "LOW TRAFFIC VOLUMES".

ONCE CONSTRUCTION ADJACENT TO A TRAVELED WAY HAS BEGUN, THAT CONSTRUCTION SHALL BE EXPEDITED UNTIL COMPLETED. IF CONSTRUCTION CANNOT BE COMPLETED DURING ONE PERIOD OF "LOW TRAFFIC VOLUMES". THE CONTRACTOR SHALL REMOVE THE LANE CLOSURE AND SHALL PROVIDE THE PROPER SIGNING AND DELINEATION FOR A SHOULDER CLOSURE.

CONTRARY TO THE SPECIFICATIONS, LANE CLOSURE WILL NOT BE A PAY ITEM ON THE CONTRACT AND ALL SIGNS, LABOR, DELINEATORS, ETC, FOR LANE CLOSURES SHALL BE INCIDENTAL TO THE BID ITEM "MAINTAIN & CONTROL TRAFFIC".

SHOULDER CLOSURES

IN OPEN CONTRUCTION AREAS WITHIN 30 FEET OF THE EDGE OF A TRAVELED WAY THE SHOULDER SHALL BE CLOSED UNLESS POSITIVE SEPARATION HAS BEEN PROVIDED. USE STANDARD DRAWING TTC-135 CURRENT EDITION (SHOULDER CLOSURE) FOR DELINEATION OF OPEN CONSTRUCTION AREAS ADJACENT TO PAVEMENT. DRUMS OR BARRICADES MAY BE REQUIRED BY THE ENGINEER REGARDLESS OF THE TIME OF SHOULDER CLOSURE.

HOURS OF LOW TRAFFIC VOLUMES

IN THESE NOTES AND FOLLOWING SEQUENCE OF CONSTRUCTION, THE PHRASE "HOURS OF LOW TRAFFIC VOLUMES" IS USED TO SPECIFY A PERIOD OF TIME IN WHICH A LANE CLOSURE MAY BE INSTALLED FOR CONSTRUCTION OPERATIONS ADJACENT TO A TRAVELED WAY. LISTED BELOW ARE THE HOURS OF LOW TRAFFIC VOLUMES.

PRIOR TO THE CONTRACTOR PERFORMING ANY CONSTRUCTION SEQUENCE, HE MUST APPLY IN WRITING TO THE ENGINEER FOR APPROVAL OF THE PERIOD OF TIME SELECTED. THE ENGINEER, AT HIS DISCRETION. CAN CANCEL OR SHORTEN ANY PERIOD OF TIME BEFORE AND DURING A CONSTRUCTION SEQUENCE. IF THE ENGINEER SHORTENS A PERIOD OF TIME BEFORE AND DURING A CONSTRUCTION SEQUENCE, THE CONTRACTOR SHALL REMOVE ALL EQUIPMENT AND INSTALL PROPER TRAFFIC CONTROL

SOUTHBOUND	NORTHBOUND
MON 7:00 PM - TUE 7:00 AM	MON 7:00 PM - TUE 7:00 AM
TUE 7:00 PM - WED 7:00 AM	TUE 7:00 PM - WED 7:00 AM
WED 7:00 PM - THU 7:00 AM	WED 7:00 PM - THU 7:00 AM
THU 7:00 PM - FRI 7:00 AM	THU 7:00 PM - FRI 7:00 AM
FRI 10:00 PM - SAT 7:00 AM	FRI 8:00 PM - SAT 7:00 AM
SAT 7:00 PM - SUN 7:00 AM	SAT 7:00 PM - SUN 7:00 AM
SUN 7:00 PM - MON 7:00 AM	SUN 10:00 PM - MON 7:00 AM

HOURS OF MINIMUM TRAFFIC VOLUMES

IN THESE NOTES AND FOLLOWING SEQUENCE OF CONSTRUCTION. THE PHRASE "HOURS OF MINIMUM TRAFFIC VOLUMES" IS USED TO SPECIFY A TIME FRAME IN WHICH A ROADWAY CAN BE COMPLETELY CLOSED BETWEEN TWO ADJACENT INTERCHANGES IN ORDER TO PERFORM A PARTICULAR CONSTRUCTION SEQUENCE. LISTED BELOW ARE PERIODS OF TIME EACH WEEK THAT ARE CONSIDERED "HOURS OF MINIMUM TRAFFIC VOLUMES". PRIOR TO THE CONTRACTOR PERFORMING ANY CONSTRUCTION SEQUENCE. HE MUST APPLY IN WRITING TO THE ENGINEER FOR APPROVAL OF THE PERIOD TIME SELECTED. THE ENGINEER, AT HIS DISCRETION, CAN CANCEL OR SHORTEN TIME PERIOD OF TIME BEFORE AND DURING A CONSTRUCTION SEQUENCE. IF THE ENGINEER SHORTENS A PERIOD OF TIME BEOFRE AND DURING A CONSTRUCTION SEQUENCE, THE CONTRACTOR SHALL REMOVE ALL EQUIPMENT AND INSTALL PROPER TRAFFIC CONTROL DEVICÉS. THE TIME A CONTRACTOR CAN COMPLETELEY CLOSE DOWN THE ROADWAY SHALL NOT EXCEED 15 MINUTES. THESE INTERRRUPTIONS TO TRAFFIC SHALL NOT OCCUR MORE OFTEN THAN ONCE IN A SINGLE PERIOD OF "MINIMUM TRAFFIC VOLUMES" UNLESS TRAFFIC HAS BEEN RESTORED IN THE OPINION OF THE ENGINEER.

SOUTHBOUND	NORTHBOUND
MON 10:00 PM - TUE 5:00 AM	MON 10:00 PM - TUE 5:00 AM
TUE 10:00 PM - WED 5:00 AM	TUE 10:00 PM - WED 5:00 AM
WED 10:00 PM - THU 5:00 AM	WED 10:00 PM - THU 5:00 AM
THU 10:00 PM - FRI 5:00 AM	THU 10:00 PM - FRI 5:00 AM
FRI MIDNIGHT - SAT 5:00 AM	FRI MIDNIGHT - SAT 5:00 AM
SAT MIDNIGHT - SUN 5:00 AM	SAT MIDNIGHT - SUN 5:00 AM
SUN MIDNIGHT - MON 5:00 AM	SUN MIDNIGHT - MON 5:00 AM

HOLIDAYS AND SPECIAL EVENTS

LISTED BELOW ARE DATES AND TIMES FOR HOLIDAYS AND SPECIAL EVENTS WHEN ROAD CLOSURES, LANE CLOSURES AND BLASTING WILL NOT BE ALLOWED.

THANKSGIVING 6:00 AM NOVEMBER 21 TO 6:00 AM NOVEMBER 26 CHRISTMAS/NEWYEARS 6:00 AM DECEMBER 17 TO 6:00 AM JANUARY 2

KEA (SPRING BREAK) TO BE DETERMINED BY THE DEPARTMENT. EASTER 6:00 AM MARCH 31 TO 6:00 AM APRIL 1 MEMORIAL DAY 6:00 AM MAY 24 TO 6:00 AM MAY 28 JULY 4TH 6:00 AM JULY 3 TO 6:00 AM JULY 8 6:00 AM AUGUST 30 TO 6:00 AM SEPTEMBER 3 LABOR DAY

FUTURE HOLIDAY DATES SHALL BE DETERMINED BY THE DEPARTMENT IF NECESSARY, COMPARABLE TO

PAVEMENT EDGE DROP-OFFS

A PAVEMENT EDGE THAT TRAFFIC IS EXPECTED TO CROSS IN A LANE CHANGE SITUATION SHALL NOT HAVE AN ELEVATION DIFFERENCE GREATER THAN 11/2 INCHES. THIS MAY BE INCREASED TO 2 INCHES FOR LOW SPEED SITUATIONS, WARNING SIGNS SHALL BE PLACED IN ADVANCE AND THROUGHOUT THE DROP-OFF AREA WHEN DROP-OFFS ARE GREATER THAN 1/2 INCH. MODIFICATIONS WILL BE AS DIRECTED BY THE ENGINEER.

PAVEMENT EDGES THAT TRAFFIC IS NOT EXPECTED TO CROSS SHALL BE TREATED AS FOLLOWS: OR, AS DIRECTED BY THE ENGINEER:

ABOVE DATES. THE ABOVE DATES ARE SUBJECT TO CHANGE IF THE DEPARTMENT DEEMS NECESSARY.

LESS THAN 1/2 INCH - NO PROTECTION REQUIRED.

 $\frac{1}{2}$ to 2 inches - Warning signs shall be placed in advance and throughout the drop-off area.

2 TO 4 INCHES - PLASTIC DRUMS, VERTICAL PANELS, OR BARRICADES SHALL BE PLACED EVERY 50 FEET FOR SPEEDS LESS THAN 50 MILES PER HOUR AND EVERY 100 FEET FOR SPEEDS OF 50 MILES PER HOUR AND GREATER. CONES MAY BE USED IN PLACE OF PLASTIC DRUMS, VERTICAL PANELS, AND BARRICADES DURING DAYLIGHT HOURS. SPACING FOR TAPERS SHALL BE IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

4 INCHES AND GREATER - POSITIVE SEPARATION NEEDED OR WEDGE WITH 3:1 OR FLATTER SLOPE. IF THERE IS 5 FEET OR MORE DISTANCE BETWEEN THE EDGE OF PAVEMENT AND DROP-OFF, PLASTIC DRUMS, VERTICAL PANELS OR BARRICADES MAY BE USED, IF CONCRETE BARRIERS ARE USED, SPECIAL REFLECTIVE DEVICES OR STEADY BURN LIGHTS SHALL BE USED FOR OVERNIGHT INSTALLATIONS.

FOR TEMPORARY CONDITIONS, DROP-OFFS 4 INCHES AND GREATER MAY BE PROTECTED WITH PLASTIC DRUMS, VERTICAL PANELS, OR BARRICADES FOR SHORT DISTANCES WHILE WORK IS BEING DONE IN THE DROP-OFF AREA IF THERE IS 8 FEET OR MORE OF SEPERATION BETWEEN DROP OFF AND TRAVELED WAY.

PAYMENT WILL BE ALLOWED FOR CSB MATERIAL USED FOR WEDGING.

DOUBLE FINE NOTE

LOCATIONS NOT ROUTINELY PROTECTED BY A BARRIER WALL ARE ELIGIBLE FOR DOUBLE FINE SIGNS. A HIGHWAY ZONE WHICH HAS BARRIER WALLS BUT IN WHICH UNUSUAL OR HAZARDOUS CONDITIONS EXIST WHICH EXPOSE THE WORKERS TO TRAFFIC HAZARDS SHALL ALSO BE ELIGIBLE FOR DOUBLE FINE SIGNS. HOWEVER, THE SIGNS SHALL ONLY BE PLACED IN PORTIONS OF WORK ZONES IN WHICH WORKERS ARE EXPOSED TO TRAFFIC HAZARDS.

THE CONTRACTOR SHALL NOTIFY THE ENGINEER A MINIMUM OF 12 HOURS PRIOR TO USING DOUBLE FINE

AT THE BEGINNING OF THE HIGHWAY WORK ZONE, THE "FINE DOUBLED IN WORK ZONE" SIGN SHALL BE PLACED. AT THE END OF THE WORK ZONE THE "END DOUBLE FINE" SIGN SHALL BE PLACED. THE SIGNS SHALL BE COVERED OR REMOVED WHEN THE HIGHWAY WORK ZONE DOES NOT HAVE WORKERS FOR MORE THAN A 2 HOUR PERIOD.

PAYMENT FOR THE SIGNS SHALL BE MADE AT THE UNIT BID PRICE FOR SIGNS ERECTED. THE MOVING AND COVERING OF SIGNS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM SIGNS.

TEMPORARY BARRIER WALL DELINEATORS

CONTRARY TO THE STANDARD DRAWINGS BARRIER WALL DELINEATORS SHALL BE INSTALLED EVERY 25

LIQUIDATED DAMAGES AND DISINCENTIVES

THE FOLLOWING DAMAGES SHALL BE ASSESSED IF ROAD CLOSURES ARE KEPT FOR LONGER THAN 15 MINUTES.

15	ТО	30	MINUTES	\$1,000.00
30	ΤO	45	MINUTES	\$2,000.00
45	ΤO	60	MINUTES	\$15,000.00

ALL ROAD CLOSURES LEFT IN PLACE FOR MORE THAN 60 MINUTES WILL BE ASSESSED DAMAGES OF \$15,000.00 PER HOUR OR FRACTION THEREOF. DISINCETIVES OF \$1,300.00 PER LANE CLOSURE PER HOUR WILL BE CHARGED EACH HOUR OR FRACTION OF AN HOUR THAT TWO LANES IN EACH DIRECTION ARE NOT OPEN EXCEPT FOR PERMITTED HOURS DURING HOURS OF LOW TRAFFIC VOLUME. THE \$1,300.00 DISINCENTIVE SHALL ALSO APPLY TO ANY SINGLE LANE OF TRAFFIC NOT SPECIFICALLY PERMITTED IN THE TRAFFIC CONTROL PLAN. LANE CLOSURES IN PLACE FOR MORE THAN ONE HOUR IN EXPRESS OF PERMITTED HOURS WILL BE ASSESSED AT A GREATER RATE. THE SECOND HOUR OR FRACTION THEREOF WILL BE ASSESSED AT THE RATE OF \$2,600.00 PER HOUR. THE THIRD HOUR OR FRACTION THEREOF AND ALL ADDITIONAL HOURS SHALL BE ASSESSED AT THE RATE \$15,000.00 PER HOUR.

SIGNS

ADDITIONAL TRAFFIC CONTROL SIGNS IN ADDITION TO NORMAL LANE CLOSRUE SIGNING DETAILED ON THE LANE CLOSURE STANDARD DRAWINGS MAY BE REQUIRED BY THE ENGINEER. ADDITIONAL SIGNS NEEDED FOR LANE CLOSURES MAY INCLUDE, BUT ARE NOT LIMITED TO DUAL MOUNTED LEFT/RIGHT LANE CLOSED 1 MILE, LEFT/RIGHT LANE CLOSED 2 MILE, LEFT/RIGHT LANE CLOSED 3 MILE, SLOWED/STOPPED TRAFFIC AHEAD, KEEP RIGHT, KEEP LEFT, ETC.

CONTRARY TO SECTION 112.04.02, LOW SHOULDER SIGNS WILL NOT BE MEASURED FOR PAYMENT, BUT WILL BE INCIDENTAL TO MAINTAIN & CONTROL TRAFFIC. CONTRARY TO SECTION 112.04.02 ONLY LONG TERM SIGNS (SIGNS INTENDED TO BE CONTINOUSLY IN PLACE FOR MORE THAN THREE DAYS) WILL BE MEASURED FOR PAYMENT; SHORT TERM SIGNS (SIGNS INTENDED TO BE LEFT IN PLACE FOR THREE DAYS OR LESS) WILL NOT BÉ MEASURED FOR PAYMENT BUT WILL INCIDENTAL TO MAINTAIN & CONTROL TRAFFIC. INDIVIDUAL SIGNS WILL BE MEASURED ONLY ONCE FOR PAYMENT, REGARDLESS OF HOW MANY TIMES THEY ARE SET, RESET, REMOVED, AND RELOCATED DURING THE DURATION OF THE PROJECT. REPLACEMENTS FOR DAMAGED SIGNS DIRECTED BY THE ENGINEER TO BE REPLACED DUE TO POOR CONDITION OR REFLECTIVITY WILL NOT BE MEASURED FOR PAYMENT, TEMPORARY TRAFFIC CONTROL DEVICES (I.E. PAVEMENT MARKINGS AND SIGNS) SHALL BE REMOVED AS SOON AS POSSIBLE WHEN THEY ARE NO LONGER NEEDED AS PER THE MUTCD PART 6 CHAPTER 6B. PAVEMENT MARKINGS CONTRARY TO CURRENT TRAFFIC PATTERNS MUST BE COVERED OR REMOVED IMMEDIATELY WHEN IN CONFORMANCE WITH CURRENT TRAFFIC PATTERNS AND NO LONGER APPROPRIATE.

PORTABLE CHANGEABLE MESSAGE SIGNS

PROVIDE A MINIMUM OF TWO PORTABLE CHANGEABLE MESSAGE SIGNS IN ADVANCE OF OR ON THE PROJECT AT LOCATIONS TO BE DETERMINED BY THE ENGINEER. IF WORK IS IN PROGRESS CONCURRENTLY IN BOTH DIRECTIONS OF TRAVEL, PROVIDE ADDITIONAL PORTABLE CHANGEABLE MESSAGE SIGNS AS DIRECTED BY THE ENGINEER. THE LOCATIONS DESIGNATED MAY VARY AS THE WORK PROGRESSES. THE MESSAGE REQUIRED TO BE PROVIDED SHALL BE DESIGNATED BY THE ENGINEER. THE PORTABLE CHANGEABLE MESSAGE SIGNS SHALL BE IN OPERATION AT ALL TIMES. IN THE EVENT OF DAMAGE OR MECHANICAL/ELECTRICAL FAILURE, THE CONTRACTOR SHALL IMMEDIATELY REPAIR OR REPLACE THE PORTABLE CHANGEABLE MESSAGE SIGN. PORTABLE CHANGEABLE MESSAGE SIGNS WILL REMAIN THE PROPERTY OF THE CONTRACTOR AFTER CONSTRUCTION IS COMPLETE.

MAINTENANCE RAFFIC

AND HART ⚠ REVISED 10-4-12

GENERAL

ALL TRAFFIC CONTROL DEVICES SHALL COMPLY WITH THE CURRENT STANDARD DRAWINGS AND THE CURRENT MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

THE CONTRACTOR SHALL MAINTAIN TWO LANES IN EACH DIRECTION WITH A MINIMUM LANE WIDTH OF 11' EXCEPT WHERE NOTED. THE CONTRACTOR SHALL NOTIFY THE BARREN AND HART COUNTY POLICE A MINIMUM OF 2 WEEKS IN ADVANCE OF ANY CLOSURE ON MAINLINE. IF POLICE ASSISTANCE IS DEEMED NECCESSARY BY THE CONTRACTOR, IT SHALL BE AT THEIR EXPENSE.

THE TEMPORARY CONCRETE BARRIER WALLS ARE TO BE CONSTRUCTED OR OBTAINED BY THE CONTRACTOR AS PER NOTE 2 ON R2G

THE CONTRACTOR WILL NOT BE ALLOWED TO HAUL EQUIPMENT OR DRIVE ACROSS THE MEDIAN FROM ONE SIDE OF THE INTERSTATE TO THE OTHER UNLESS APPROPRIATE BARRIER WALL GATES HAVE BEEN INSTALLED. ALL OTHER EQUIPMENT MOVEMENTS FROM ONE SIDE OF THE INTERSTATE TO THE OTHER SHALL UTILIZE THE NEAREST INTERCHANGE. HAULING EQUIPMENT THAT USES I-65 SHALL BE RESTRICTED TO LICENSED VEHICLES ONLY. VEHICLES SHALL NOT STOP OR PARK IN AREAS NOT DESIGNATED BY THE ENGINEER. ANY SHOULDER USED FOR A DECELERATION OR ACCELERATION LANE SHALL BE WIDENED AND PAVED TO ADEQUATELY SUPPORT HEAVY TRUCK TRAFFIC. ALL EXPENSES INCURRED TO CONSTRUCT BARRIER WALL GATES AND REMOVAL THEREOF SHALL BE BORNE BY THE CONTRACTOR AND BE INCIDENTAL TO THE CONTRACT. PAVEMENT NEEDED TO CONSTRUCT BARRIER WALL GATES INCORPORATED IN THE PERMANENT WORK SHALL BE MEASURED FOR PAYMENT.

THE CONSTRACTOR SHALL EXPEDITE EXCAVATION OF ALL ROCK CUTS AND OTHER EXCAVATION IN A CONTINOUS MANNER ONCE WORK HAS STARTED. IF THE CONTRACTOR STOPS WORK IN ANY ONE AREA FOR MORE THAN 2 DAYS, (EXCLUDING HOLIDAYS LISTED WITHIN THESE NOTES), THEN LIQUIDATED DAMAGES WILL BE ASSESSED AT THE CONTRACT RATE FOR EVERY DAY UNTIL WORK RESUMES.

IF THE CONTRACTOR DECIDES TO DEVIATE FROM THE TRAFFIC CONTROL SCHEME AND CONSTRUCTION SCHEDULE OUTLINED IN THESE PLANS OR PROPOSAL, AN ALTERNATE PLAN SHALL BE SUBMITTED IN WRITING TO THE ENGINEER. THE ALTERNATE PLAN MAY BE USED ONLY IF APPROVED IN WRITING BY THE KENTUCKY DIVISION OF DESIGN, TRAFFIC, CONSTRUCTION AND FHWA.

OTHER MAINTENANCE OF TRAFFIC PROPOSALS WILL BE CONSIDERED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS: HOWEVER, ALTERNATE MAINTENANCE OF TRAFFIC SCHEMES WILL NOT BE SUBJECT TO VALUE ENGINEERING UNDER SECTION 111.

THE REQUIREMENTS FOR ALTERNATE MAINTENANCE OF TRAFFIC SCHEMES SHALL BE AT LEAST 11 FOOT LANES FOR THROUGH TRAFFIC. TWO LANES PER DIRECTION SHALL BE OPEN TO TRAFFIC AT ALL TIMES, UNLESS OTHERWISE SPECIFIED IN THE MAINTENANCE OF TRAFFIC PLANS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING POSITIVE DRAINAGE IN SAG AREAS AT MEDIAN INLETS. WHEN THE MEDIAN IS USED AS A TRAVEL LANE AND BEFORE FINISHED ASPHALT IS PLACED, WEDGING IS REQUIRED AT ALL DRAINAGE INLETS. WEDGING IS INCIDENTAL TO THE DRAINAGE INLET. ALL SILT TRAP TYPE C MUST BE REMOVED FROM ALL MEDIAN INLETS PRIOR TO TRAFFIC BEING ALLOWED IN MEDIAN.

THE CONTRACTOR SHALL SUBMIT IN WRITING, PLANS FOR APPROVAL BY THE DEPARTMENT AND THE FHWA BEFORE STOPPING TRAFFIC.

NORMAL CONSIDERATION SHOULD BE GIVEN TO PROPERTY OWNERS FOR THEIR ACCESS.

REPAIR AND/OR UPGRADE PAVEMENT ALONG AND ACROSS EXISTING ROADS WHERE CONSTRUCTION TRAFFIC CROSSES, ACCESS TO ALL PUBLIC ROADS IS TO BE MAINTAINED EXCEPT AS INDICATED IN THE MAINTENANCE OF TRAFFIC NOTES.

CONSTRUCT EROSION CONTROLS AT POINTS WHERE RUNOFF LEAVES THE PROJECT SITE, BEGIN EARTHWORK, UTILIZING TEMPORARY DIVERSION DITCHES TO DIRECT RUNOFF TO EROSION CONTROLS.

THE CONTRACTOR MUST NOTIFY THE DISTRICT PUBLIC INFORMATION OFFICE (PIO), KEIRSTEN JAGGER (DISTRICT 3). AT 270-746-7898 (OFFICE) OR 270-202-0446 (CELL) AND CHRIS JESSIE (DISTRICT 4) 270-401-3193 (OFFICE) WITHIN THE FOLLOWING TIME FRAMES OF PENDING CHANGES IN THEIR WORK SCHEDULE WHICH WILL AFFECT TRAFFIC PATTERNS:

1) AT LEAST FOURTEEN (14) DAYS PRIOR TO BEGINNING PHASE I CONSTRUCTION IN EITHER DIRECTION 2) AT LEAST FIVE (5) DAYS PRIOR TO A RAMP CLOSURE 3) IF A DECISION IS MADE NOT TO CLOSE A RAMP, NOTICE MUST BE GIVEN TO THE PIO 5 DAYS PRIOR TO THE PROPOSED CLOSURE. LANE CLOSURES

WHEN CONSTRUCTION WITHIN 8 FEET OF THE TRAVELED WAY IS IN PROGRESS AND/OR WHEN INSTALLING BARRIER WALL ADJACENT TO A TRAVELED WAY, ONE LANE MAY BE CLOSED. LANE CLOSURES SHALL ONLY BE DURING HOURS OF "LOW TRAFFIC VOLUMES" AS OUTLINED IN THESE TRAFFIC CONTROL NOTES. ALL SIGN PLACEMENT SHALL ALSO BE DONE DURING HOURS OF "LOW TRAFFIC VOLUMES".

ONCE CONSTRUCTION ADJACENT TO A TRAVELED WAY HAS BEGUN, THAT CONSTRUCTION SHALL BE EXPEDITED UNTIL COMPLETED. IF CONSTRUCTION CANNOT BE COMPLETED DURING ONE PERIOD OF "LOW TRAFFIC VOLUMES". THE CONTRACTOR SHALL REMOVE THE LANE CLOSURE AND SHALL PROVIDE THE PROPER SIGNING AND DELINEATION FOR A SHOULDER CLOSURE.

CONTRARY TO THE SPECIFICATIONS, LANE CLOSURE WILL NOT BE A PAY ITEM ON THE CONTRACT AND ALL SIGNS, LABOR, DELINEATORS, ETC, FOR LANE CLOSURES SHALL BE INCIDENTAL TO THE BID ITEM "MAINTAIN & CONTROL TRAFFIC".

SHOULDER CLOSURES

IN OPEN CONTRUCTION AREAS WITHIN 30 FEET OF THE EDGE OF A TRAVELED WAY THE SHOULDER SHALL BE CLOSED UNLESS POSITIVE SEPARATION HAS BEEN PROVIDED. USE STANDARD DRAWING TTC-135 CURRENT EDITION (SHOULDER CLOSURE) FOR DELINEATION OF OPEN CONSTRUCTION AREAS ADJACENT TO PAVEMENT. DRUMS OR BARRICADES MAY BE REQUIRED BY THE ENGINEER REGARDLESS OF THE TIME OF SHOULDER CLOSURE.

HOURS OF LOW TRAFFIC VOLUMES

IN THESE NOTES AND FOLLOWING SEQUENCE OF CONSTRUCTION, THE PHRASE "HOURS OF LOW TRAFFIC VOLUMES" IS USED TO SPECIFY A PERIOD OF TIME IN WHICH A LANE CLOSURE MAY BE INSTALLED FOR CONSTRUCTION OPERATIONS ADJACENT TO A TRAVELED WAY. LISTED BELOW ARE THE HOURS OF LOW TRAFFIC VOLUMES.

PRIOR TO THE CONTRACTOR PERFORMING ANY CONSTRUCTION SEQUENCE. HE MUST APPLY IN WRITING TO THE ENGINEER FOR APPROVAL OF THE PERIOD OF TIME SELECTED. THE ENGINEER, AT HIS DISCRETION, CAN CANCEL OR SHORTEN ANY PERIOD OF TIME BEFORE AND DURING A CONSTRUCTION SEQUENCE. IF THE ENGINEER SHORTENS A PERIOD OF TIME BEFORE AND DURING A CONSTRUCTION SEQUENCE, THE CONTRACTOR SHALL REMOVE ALL EQUIPMENT AND INSTALL PROPER TRAFFIC CONTROL

SOUTHBOUND	NORTHBOUND
MON 7:00 PM - TUE 7:00 AM	MON 7:00 PM - TUE 7:00 AM
TUE 7:00 PM - WED 7:00 AM	TUE 7:00 PM - WED 7:00 AM
WED 7:00 PM - THU 7:00 AM	WED 7:00 PM - THU 7:00 AM
THU 7:00 PM - FRI 7:00 AM	THU 7:00 PM - FRI 7:00 AM
FRI 10:00 PM - SAT 7:00 AM	FRI 8:00 PM - SAT 7:00 AM
SAT 7:00 PM - SUN 7:00 AM	SAT 7:00 PM - SUN 7:00 AM
SUN 7:00 PM - MON 7:00 AM	SUN 10:00 PM - MON 7:00 AM

HOURS OF MINIMUM TRAFFIC VOLUMES

IN THESE NOTES AND FOLLOWING SEQUENCE OF CONSTRUCTION. THE PHRASE "HOURS OF MINIMUM TRAFFIC VOLUMES" IS USED TO SPECIFY A TIME FRAME IN WHICH A ROADWAY CAN BE COMPLETELY CLOSED BETWEEN TWO ADJACENT INTERCHANGES IN ORDER TO PERFORM A PARTICULAR CONSTRUCTION SEQUENCE. LISTED BELOW ARE PERIODS OF TIME EACH WEEK THAT ARE CONSIDERED "HOURS OF MINIMUM TRAFFIC VOLUMES". PRIOR TO THE CONTRACTOR PERFORMING ANY CONSTRUCTION SEQUENCE, HE MUST APPLY IN WRITING TO THE ENGINEER FOR APPROVAL OF THE PERIOD TIME SELECTED. THE ENGINEER, AT HIS DISCRETION, CAN CANCEL OR SHORTEN TIME PERIOD OF TIME BEFORE AND DURING A CONSTRUCTION SEQUENCE. IF THE ENGINEER SHORTENS A PERIOD OF TIME BEOFRE AND DURING A CONSTRUCTION SEQUENCE, THE CONTRACTOR SHALL REMOVE ALL EQUIPMENT AND INSTALL PROPER TRAFFIC CONTROL DEVICÉS. THE TIME A CONTRACTOR CAN COMPLETELEY CLOSE DOWN THE ROADWAY SHALL NOT EXCEED 15 MINUTES. THESE INTERRRUPTIONS TO TRAFFIC SHALL NOT OCCUR MORE OFTEN THAN ONCE IN A SINGLE PERIOD OF "MINIMUM TRAFFIC VOLUMES" UNLESS TRAFFIC HAS BEEN RESTORED IN THE OPINION OF THE ENGINEER.

SOUTHBOUND	NORTHBOUND
MON 10:00 PM - TUE 5:00 AM	
MON 10:00 PM - 10E 3:00 AM	MON 10:00 PM - TUE 5:00 AM
TUE 10:00 PM - WED 5:00 AM	TUE 10:00 PM - WED 5:00 AM
WED 10:00 PM - THU 5:00 AM	WED 10:00 PM - THU 5:00 AM
THU 10:00 PM - FRI 5:00 AM	THU 10:00 PM - FRI 5:00 AM
FRI MIDNIGHT - SAT 5:00 AM	FRI MIDNIGHT - SAT 5:00 AM
SAT MIDNIGHT - SUN 5:00 AM	SAT MIDNIGHT - SUN 5:00 AM
SUN MIDNIGHT - MON 5:00 AM	SUN MIDNIGHT - MON 5:00 AM

HOLIDAYS AND SPECIAL EVENTS

LISTED BELOW ARE DATES AND TIMES FOR HOLIDAYS AND SPECIAL EVENTS WHEN ROAD CLOSURES. LANE CLOSURES AND BLASTING WILL NOT BE ALLOWED.

THANKSGIVING 6:00 AM NOVEMBER 21 TO 6:00 AM NOVEMBER 26 CHRISTMAS/NEWYEARS 6:00 AM DECEMBER 17 TO 6:00 AM JANUARY 2

KEA (SPRING BREAK) TO BE DETERMINED BY THE DEPARTMENT.

EASTER 6:00 AM MARCH 31 TO 6:00 AM APRIL 1 MEMORIAL DAY 6:00 AM MAY 24 TO 6:00 AM MAY 28 JULY 4TH 6:00 AM JULY 3 TO 6:00 AM JULY 8 6:00 AM AUGUST 30 TO 6:00 AM SEPTEMBER 3 LABOR DAY

FUTURE HOLIDAY DATES SHALL BE DETERMINED BY THE DEPARTMENT IF NECESSARY, COMPARABLE TO ABOVE DATES. THE ABOVE DATES ARE SUBJECT TO CHANGE IF THE DEPARTMENT DEEMS NECESSARY.

PAVEMENT EDGE DROP-OFFS

A PAVEMENT EDGE THAT TRAFFIC IS EXPECTED TO CROSS IN A LANE CHANGE SITUATION SHALL NOT HAVE AN ELEVATION DIFFERENCE GREATER THAN 11/2 INCHES. THIS MAY BE INCREASED TO 2 INCHES FOR LOW SPEED SITUATIONS, WARNING SIGNS SHALL BE PLACED IN ADVANCE AND THROUGHOUT THE DROP-OFF AREA WHEN DROP-OFFS ARE GREATER THAN 1/2 INCH. MODIFICATIONS WILL BE AS DIRECTED BY THE ENGINEER.

PAVEMENT EDGES THAT TRAFFIC IS NOT EXPECTED TO CROSS SHALL BE TREATED AS FOLLOWS: OR, AS DIRECTED BY THE ENGINEER:

LESS THAN 1/2 INCH - NO PROTECTION REQUIRED.

 $\frac{1}{2}$ to 2 inches - Warning signs shall be placed in advance and throughout the drop-off area.

2 TO 4 INCHES - PLASTIC DRUMS, VERTICAL PANELS, OR BARRICADES SHALL BE PLACED EVERY 50 FEET FOR SPEEDS LESS THAN 50 MILES PER HOUR AND EVERY 100 FEET FOR SPEEDS OF 50 MILES PER HOUR AND GREATER. CONES MAY BE USED IN PLACE OF PLASTIC DRUMS, VERTICAL PANELS, AND BARRICADES DURING DAYLIGHT HOURS. SPACING FOR TAPERS SHALL BE IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

4 INCHES AND GREATER - POSITIVE SEPARATION NEEDED OR WEDGE WITH 3:1 OR FLATTER SLOPE. IF THERE IS 5 FEET OR MORE DISTANCE BETWEEN THE EDGE OF PAVEMENT AND DROP-OFF, PLASTIC DRUMS, VERTICAL PANELS OR BARRICADES MAY BE USED, IF CONCRETE BARRIERS ARE USED, SPECIAL REFLECTIVE DEVICES OR STEADY BURN LIGHTS SHALL BE USED FOR OVERNIGHT INSTALLATIONS.

FOR TEMPORARY CONDITIONS, DROP-OFFS 4 INCHES AND GREATER MAY BE PROTECTED WITH PLASTIC DRUMS, VERTICAL PANELS, OR BARRICADES FOR SHORT DISTANCES WHILE WORK IS BEING DONE IN THE DROP-OFF AREA IF THERE IS 8 FEET OR MORE OF SEPERATION BETWEEN DROP OFF AND TRAVELED WAY.

PAYMENT WILL BE ALLOWED FOR CSB MATERIAL USED FOR WEDGING.

DOUBLE FINE NOTE

LOCATIONS NOT ROUTINELY PROTECTED BY A BARRIER WALL ARE ELIGIBLE FOR DOUBLE FINE SIGNS. A HIGHWAY ZONE WHICH HAS BARRIER WALLS BUT IN WHICH UNUSUAL OR HAZARDOUS CONDITIONS EXIST WHICH EXPOSE THE WORKERS TO TRAFFIC HAZARDS SHALL ALSO BE ELIGIBLE FOR DOUBLE FINE SIGNS. HOWEVER, THE SIGNS SHALL ONLY BE PLACED IN PORTIONS OF WORK ZONES IN WHICH WORKERS ARE EXPOSED TO TRAFFIC HAZARDS.

THE CONTRACTOR SHALL NOTIFY THE ENGINEER A MINIMUM OF 12 HOURS PRIOR TO USING DOUBLE FINE

AT THE BEGINNING OF THE HIGHWAY WORK ZONE, THE "FINE DOUBLED IN WORK ZONE" SIGN SHALL BE PLACED. AT THE END OF THE WORK ZONE THE "END DOUBLE FINE" SIGN SHALL BE PLACED. THE SIGNS SHALL BE COVERED OR REMOVED WHEN THE HIGHWAY WORK ZONE DOES NOT HAVE WORKERS FOR MORE THAN A 2 HOUR PERIOD.

PAYMENT FOR THE SIGNS SHALL BE MADE AT THE UNIT BID PRICE FOR SIGNS ERECTED. THE MOVING AND COVERING OF SIGNS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM SIGNS.

TEMPORARY BARRIER WALL DELINEATORS

CONTRARY TO THE STANDARD DRAWINGS BARRIER WALL DELINEATORS SHALL BE INSTALLED EVERY 25

LIQUIDATED DAMAGES AND DISINCENTIVES

THE FOLLOWING DAMAGES SHALL BE ASSESSED IF ROAD CLOSURES ARE KEPT FOR LONGER THAN 15 MINUTES.

15 TO 30 MINUTES \$1,000.00 \$2,000.00 30 TO 45 MINUTES 45 TO 60 MINUTES \$15,000.00

ALL ROAD CLOSURES LEFT IN PLACE FOR MORE THAN 60 MINUTES WILL BE ASSESSED DAMAGES OF \$15,000.00 PER HOUR OR FRACTION THEREOF. DISINCETIVES OF \$1,300.00 PER LANE CLOSURE PER HOUR WILL BE CHARGED EACH HOUR OR FRACTION OF AN HOUR THAT TWO LANES IN EACH DIRECTION ARE NOT OPEN EXCEPT FOR PERMITTED HOURS DURING HOURS OF LOW TRAFFIC VOLUME. THE \$1,300.00 DISINCENTIVE SHALL ALSO APPLY TO ANY SINGLE LANE OF TRAFFIC NOT SPECIFICALLY PERMITTED IN THE TRAFFIC CONTROL PLAN. LANE CLOSURES IN PLACE FOR MORE THAN ONE HOUR IN EXPRESS OF PERMITTED HOURS WILL BE ASSESSED AT A GREATER RATE. THE SECOND HOUR OR FRACTION THEREOF WILL BE ASSESSED AT THE RATE OF \$2,600.00 PER HOUR. THE THIRD HOUR OR FRACTION THEREOF AND ALL ADDITIONAL HOURS SHALL BE ASSESSED AT THE RATE \$15,000.00 PER HOUR.

SIGNS

ADDITIONAL TRAFFIC CONTROL SIGNS IN ADDITION TO NORMAL LANE CLOSRUE SIGNING DETAILED ON THE LANE CLOSURE STANDARD DRAWINGS MAY BE REQUIRED BY THE ENGINEER. ADDITIONAL SIGNS NEEDED FOR LANE CLOSURES MAY INCLUDE, BUT ARE NOT LIMITED TO DUAL MOUNTED LEFT/RIGHT LANE CLOSED 1 MILE, LEFT/RIGHT LANE CLOSED 2 MILE, LEFT/RIGHT LANE CLOSED 3 MILE, SLOWED/STOPPED TRAFFIC AHEAD, KEEP RIGHT, KEEP LEFT, ETC.

CONTRARY TO SECTION 112.04.02, LOW SHOULDER SIGNS WILL NOT BE MEASURED FOR PAYMENT, BUT WILL BE INCIDENTAL TO MAINTAIN & CONTROL TRAFFIC. CONTRARY TO SECTION 112.04.02 ONLY LONG TERM SIGNS (SIGNS INTENDED TO BE CONTINOUSLY IN PLACE FOR MORE THAN THREE DAYS) WILL BE MEASURED FOR PAYMENT; SHORT TERM SIGNS (SIGNS INTENDED TO BE LEFT IN PLACE FOR THREE DAYS OR LESS) WILL NOT BÉ MEASURED FOR PAYMENT BUT WILL INCIDENTAL TO MAINTAIN & CONTROL TRAFFIC. INDIVIDUAL SIGNS WILL BE MEASURED ONLY ONCE FOR PAYMENT, REGARDLESS OF HOW MANY TIMES THEY ARE SET, RESET, REMOVED, AND RELOCATED DURING THE DURATION OF THE PROJECT. REPLACEMENTS FOR DAMAGED SIGNS DIRECTED BY THE ENGINEER TO BE REPLACED DUE TO POOR CONDITION OR REFLECTIVITY WILL NOT BE MEASURED FOR PAYMENT, TEMPORARY TRAFFIC CONTROL DEVICES (I.E. PAVEMENT MARKINGS AND SIGNS) SHALL BE REMOVED AS SOON AS POSSIBLE WHEN THEY ARE NO LONGER NEEDED AS PER THE MUTCD PART 6 CHAPTER 6B. PAVEMENT MARKINGS CONTRARY TO CURRENT TRAFFIC PATTERNS MUST BE COVERED OR REMOVED IMMEDIATELY WHEN IN CONFORMANCE WITH CURRENT TRAFFIC PATTERNS AND NO LONGER APPROPRIATE.

PORTABLE CHANGEABLE MESSAGE SIGNS

PROVIDE A MINIMUM OF TWO PORTABLE CHANGEABLE MESSAGE SIGNS IN ADVANCE OF OR ON THE PROJECT AT LOCATIONS TO BE DETERMINED BY THE ENGINEER. IF WORK IS IN PROGRESS CONCURRENTLY IN BOTH DIRECTIONS OF TRAVEL, PROVIDE ADDITIONAL PORTABLE CHANGEABLE MESSAGE SIGNS AS DIRECTED BY THE ENGINEER. THE LOCATIONS DESIGNATED MAY VARY AS THE WORK PROGRESSES. THE MESSAGE REQUIRED TO BE PROVIDED SHALL BE DESIGNATED BY THE ENGINEER. THE PORTABLE CHANGEABLE MESSAGE SIGNS SHALL BE IN OPERATION AT ALL TIMES. IN THE EVENT OF DAMAGE OR MECHANICAL/ELECTRICAL FAILURE, THE CONTRACTOR SHALL IMMEDIATELY REPAIR OR REPLACE THE PORTABLE CHANGEABLE MESSAGE SIGN. PORTABLE CHANGEABLE MESSAGE SIGNS WILL REMAIN THE PROPERTY OF THE CONTRACTOR AFTER CONSTRUCTION IS COMPLETE.

MAINTENANCE RAFFIC