



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

December 1, 2014

CALL NO. 200
CONTRACT ID NO. 144129
ADDENDUM # 1

Subject: Boone County, 008GR14T014-HSIP & FE01
Letting December 12, 2014

- (1) Replace - Page 17 of 126
- (2) Replace - Page 36 of 126
- (3) Revised - Material Summary - Pages 55-56 of 126
- (4) Revised - Bid Items - Page 126 of 126

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Diana Castle Radcliffe".

Diana Castle Radcliffe
Director
Division of Construction Procurement

DR:ks
Enclosures



An Equal Opportunity Employer M/F/D

NATIONAL HIGHWAY

Be advised this project is on the NATIONAL HIGHWAY SYSTEM.

DGA BASE FOR SHOULDERS

Unless otherwise noted, the Department estimates the rate of application for DGA Base for Shoulders to be 115 lbs/sy per inch of depth. The Department will not measure necessary grading and/or shaping of existing shoulders prior to placing of DGA Base, but shall be incidental to the Contract unit price per ton for DGA Base.

Accept payment at the Contract unit price per ton as full compensation for all labor, materials, equipment, and incidentals for grading and/or shaping of existing shoulders and furnishing, placing, and compacting the DGA Base.

SPECIAL NOTE FOR DIAMOND GRINDING RIDE QUALITY

Conform to Sections 501.03.19(B) and 503.03.09 of the Standard Specifications, with the following exceptions:

When requesting tests on partially completed pavement, the Department will perform one test at no charge. The Department will perform additional requested testing and retesting for corrective work or pavement replacement at a cost of \$300 per lane-mile. The Department will deduct charges for additional requested testing and retesting for corrective work from monies due on the Contract.

RIDE QUALITY ADJUSTMENT SCHEDULE

<u>IRI</u>	<u>Pay Value Adjustment</u>
Target IRI or less	\$0
Target IRI + 1	-\$30
Target IRI + 2	-\$70
Target IRI + 3	-\$120
Target IRI + 4	-\$180
Target IRI + 5	-\$250
Target IRI + 6	-\$330
Target IRI + 7	-\$420
Target IRI + 8	-\$520
Target IRI + 9	-\$630
Target IRI + 10	-\$750
Target IRI + 11	corrective work*

*When it is in the best interest of the Department, a minimum pay value deduction of \$1,200.00 per 0.1-lane-mile section may be applied in lieu of corrective work.

MATERIAL SUMMARY

CONTRACT ID: 144129

008GR14T014 - HSIP & FE01

0600800751401

OFF RAMP (I-75 SB TO KY-717/KY-842) BEGINNING AT THE I-75 182 EXIT AND EXTENDING NORTHWEST TO THE INTERSECTION OF KY-717 (THOROUGHbred BLVD.) & KY-842 (HOUSTON RD.) JPC PAVEMENT REPAIRS - DIAMOND GRINDING, A DISTANCE OF .4 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0001	00001	DGA BASE	245.00	TON
0002	00078	CRUSHED AGGREGATE SIZE NO 2	5.00	TON
0003	00100	ASPHALT SEAL AGGREGATE	22.50	TON
0004	00103	ASPHALT SEAL COAT	2.70	TON
0005	01691	FLUME INLET TYPE 2	1.00	EACH
0006	01982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	15.00	EACH
0007	02060	PCC PAVEMENT DIAMOND GRINDING	6,280.00	SQYD
0008	02069	JPC PAVEMENT-10 IN	486.00	SQYD
0009	02115	SAW-CLEAN-RESEAL TVERSE JOINT	4,615.00	LF
0010	02116	SAW-CLEAN-RESEAL LONGIT JOINT	5,602.00	LF
0011	02220	FLOWABLE FILL	5.00	CUYD
0012	02237	DITCHING	1,916.00	LF
0013	02383	REMOVE & RESET GUARDRAIL	50.00	LF
0014	02562	TEMPORARY SIGNS	150.00	SQFT
0015	02650	MAINTAIN & CONTROL TRAFFIC - OFF RAMP	1.00	LS
0016	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0017	02775	ARROW PANEL	1.00	EACH
0018	04941	REMOVE POLE BASE	1.00	EACH
0019	05950	EROSION CONTROL BLANKET	1,703.00	SQYD
0020	06401	FLEXIBLE DELINEATOR POST-M/W	10.00	EACH
0021	06404	FLEXIBLE DELINEATOR POST-M/Y	25.00	EACH
0022	06406	SBM ALUM SHEET SIGNS .080 IN	10.00	SQFT
0023	06407	SBM ALUM SHEET SIGNS .125 IN	105.00	SQFT
0024	06410	STEEL POST TYPE 1	140.00	LF
0025	06556	PAVE STRIPING-DUR TY 1-6 IN W	2,819.00	LF
0026	06557	PAVE STRIPING-DUR TY 1-6 IN Y	1,942.00	LF
0027	23269ES717	PAVE MARK TY 1 TAPE-COMBO ARROW	6.00	EACH
0028	23270ES717	PAVE MARK TY 1 TAPE-CURV ARROW	6.00	EACH
0029	24631EC	BARCODE SIGN INVENTORY	11.00	EACH
0030	02569	DEMobilIZATION	1.00	LS
0031	02058	REMOVE PCC PAVEMENT - (ADDED: 12-1-14)	486.00	SQYD

MATERIAL SUMMARY

CONTRACT ID: 144129

008GR14T014 - HSIP & FE01

0600800751402

ON RAMP (KY-717/KY-842 TO I-75 SB) BEGINNING AT THE INTERSECTION OF KY-717 (THOROUGHbred BLVD.) & KY-842 (HOUSTON RD.) AND EXTENDING SOUTHWEST FOR THE LENGTH OF THE I-75 ON RAMP JPC PAVEMENT REPAIRS - DIAMOND GRINDING, A DISTANCE OF .45 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0001	00001	DGA BASE	280.00	TON
0002	00100	ASPHALT SEAL AGGREGATE	40.00	TON
0003	00103	ASPHALT SEAL COAT	5.00	TON
0004	02060	PCC PAVEMENT DIAMOND GRINDING	4,232.00	SQYD
0005	02069	JPC PAVEMENT-10 IN	174.00	SQYD
0006	02115	SAW-CLEAN-RESEAL TVERSE JOINT	3,550.00	LF
0007	02116	SAW-CLEAN-RESEAL LONGIT JOINT	5,324.00	LF
0008	02237	DITCHING	3,364.00	LF
0009	02562	TEMPORARY SIGNS	150.00	SQFT
0010	02650	MAINTAIN & CONTROL TRAFFIC - ON RAMP	1.00	LS
0011	02671	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH
0012	02775	ARROW PANEL	1.00	EACH
0013	05950	EROSION CONTROL BLANKET	2,990.00	SQYD
0014	06401	FLEXIBLE DELINEATOR POST-M/W	19.00	EACH
0015	06404	FLEXIBLE DELINEATOR POST-M/Y	19.00	EACH
0016	06406	SBM ALUM SHEET SIGNS .080 IN	10.00	SQFT
0017	06407	SBM ALUM SHEET SIGNS .125 IN	105.00	SQFT
0018	06410	STEEL POST TYPE 1	140.00	LF
0019	06556	PAVE STRIPING-DUR TY 1-6 IN W	2,801.00	LF
0020	06557	PAVE STRIPING-DUR TY 1-6 IN Y	1,861.00	LF
0021	24631EC	BARCODE SIGN INVENTORY	7.00	EACH
0022	02569	DEMOBILIZATION	1.00	LS
0023	02058	REMOVE PCC PAVEMENT - (ADDED: 12-1-14)	174.00	SQYD

PROPOSAL BID ITEMS

144129

Page 1 of 1

Report Date 12/1/14

Section: 0001 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	525.00	TON		\$	
0020	00078		CRUSHED AGGREGATE SIZE NO 2	5.00	TON		\$	
0030	00100		ASPHALT SEAL AGGREGATE	62.50	TON		\$	
0040	00103		ASPHALT SEAL COAT	7.70	TON		\$	
0050	01691		FLUME INLET TYPE 2	1.00	EACH		\$	
0060	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	15.00	EACH		\$	
0069	02058		REMOVE PCC PAVEMENT (ADDED: 12-1-14)	660.00	SQYD		\$	
0070	02060		PCC PAVEMENT DIAMOND GRINDING	10,512.00	SQYD		\$	
0080	02069		JPC PAVEMENT-10 IN	660.00	SQYD		\$	
0090	02115		SAW-CLEAN-RESEAL TVERSE JOINT	8,165.00	LF		\$	
0100	02116		SAW-CLEAN-RESEAL LONGIT JOINT	10,926.00	LF		\$	
0110	02220		FLOWABLE FILL	5.00	CUYD		\$	
0120	02237		DITCHING	5,280.00	LF		\$	
0130	02383		REMOVE & RESET GUARDRAIL	50.00	LF		\$	
0140	02562		TEMPORARY SIGNS	300.00	SQFT		\$	
0150	02650		MAINTAIN & CONTROL TRAFFIC ON RAMP	1.00	LS		\$	
0160	02650		MAINTAIN & CONTROL TRAFFIC OFF RAMP	1.00	LS		\$	
0170	02671		PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH		\$	
0180	02775		ARROW PANEL	2.00	EACH		\$	
0190	04941		REMOVE POLE BASE	1.00	EACH		\$	
0200	05950		EROSION CONTROL BLANKET	4,693.00	SQYD		\$	
0210	06401		FLEXIBLE DELINEATOR POST-M/W	29.00	EACH		\$	
0220	06404		FLEXIBLE DELINEATOR POST-M/Y	44.00	EACH		\$	
0230	06406		SBM ALUM SHEET SIGNS .080 IN	20.00	SQFT		\$	
0240	06407		SBM ALUM SHEET SIGNS .125 IN	210.00	SQFT		\$	
0250	06410		STEEL POST TYPE 1	280.00	LF		\$	
0260	06556		PAVE STRIPING-DUR TY 1-6 IN W	5,620.00	LF		\$	
0270	06557		PAVE STRIPING-DUR TY 1-6 IN Y	3,803.00	LF		\$	
0280	23269ES717		PAVE MARK TY 1 TAPE-COMBO ARROW	6.00	EACH		\$	
0290	23270ES717		PAVE MARK TY 1 TAPE-CURV ARROW	6.00	EACH		\$	
0300	24631EC		BARCODE SIGN INVENTORY	18.00	EACH		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0310	02569		DEMOBILIZATION	1.00	LS		\$	