



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

August 14, 2020

CALL NO. 200
CONTRACT ID NO. 201028
ADDENDUM # 2

Subject: HARDIN-BULLITT COUNTIES, 121GR20D028-NHPP
Letting August 21, 2020

- (1) Revised - Special Note - Page 52 of 260
- (2) Revised - Material Summary - Pages 204-207(a) of 260
- (3) Revised - Proposal Bid Items - Pages 257-260 of 260

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

10. All “green” milepost signs shall be replaced with this project. Payment for these signs will be made by “each” for the bid item “Steel Milepost Marker”.
11. Removed guardrail shall be delivered to the Guardrail and Sign Recycling Center in Frankfort and shall be coordinated with the Resident Engineer. A “Guardrail Delivery and Verification Sheet” has been included in this proposal and must be completed for verification of the components delivered.
12. Existing pavement markers in the mainline concrete shall have the lenses removed or covered during times when traffic is shifted and the existing markers are not on the appropriate edge line for the actual traffic configuration. Removing or covering of the existing pavement marker lenses will be considered incidental to the lump sum bid item for “Maintain and Control Traffic”.
13. Existing grates may have become dislocated during mowing or other operations. The contractor will be required to "re-set" the existing grates that are not in their proper location. “Resetting Grates” will be considered incidental to the bid item “Ditching”. Grates that have been damaged and will need to be replaced and will be paid for under the bid item "Replace Grate" and will be paid for by “each”.
14. Delineators shall meet the requirements of Section 830 and 838 of the Standard Specifications. Delineators shall be placed in accordance with Section 3F of the M.U.T.C.D.
15. Existing median u-turn locations within the project limits are not to be disturbed with this project.
16. A quantity of Channel Lining Class III has been included to be applied to eroded areas around the drainage outlets and for some of the areas that will need to be ditched. The Engineer will make the determination whether a ditch receives ditching and/or channel lining. Geotextile Fabric Class 1 will not be measured for payment but will be considered incidental to the bid item “Channel Lining Class III”.
17. The cleaning of existing pipe culvert inlets and outlets 36 inches or less in diameter are incidental to the bid item for "Ditching" in accordance with Section 209.03.01 of the Current Edition of the Standard Specifications for Road and Bridge Construction. There is a list of locations that have been identified to be cleaned. This list may not be complete and therefore there may be additional outlets which require cleaning. The Engineer will determine any additional outlets to be cleaned.
18. Any light poles damaged during construction are to be replaced at the Contractor’s expense.
19. Traffic cameras within the project limits are not to be disturbed and shall remain operational at all times. Any traffic cameras damaged or service interrupted during construction are to be repaired/replaced at the Contractor’s expense.

MATERIAL SUMMARY

CONTRACT ID: 201028

121GR20D028-NHPP

DE01500652028

I-65 REMOVE AND REPLACE JPC PAVEMENT ON I-65 FROM MP 103.30 TO MP 104.70 IN BULLITT COUNTY
JPC PAVEMENT REPAIRS, A DISTANCE OF 1.4 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0440	00001	DGA BASE	3,967.00	TON
0445	00003	CRUSHED STONE BASE	6,453.00	TON
0450	00078	CRUSHED AGGREGATE SIZE NO 2	175.00	TON
0455	00100	ASPHALT SEAL AGGREGATE	123.00	TON
0460	00103	ASPHALT SEAL COAT	15.00	TON
0465	00214	CL3 ASPH BASE 1.00D PG64-22	2,933.00	TON
0470	01890	ISLAND HEADER CURB TYPE 1	775.00	LF
0475	01982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	70.00	EACH
0480	01983	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	14.00	EACH
0485	01984	DELINEATOR FOR BARRIER - WHITE	210.00	EACH
0490	01985	DELINEATOR FOR BARRIER - YELLOW	543.00	EACH
0495	02003	RELOCATE TEMP CONC BARRIER	16,100.00	LF
0500	02058	REMOVE PCC PAVEMENT	73,609.00	SQYD
0505	02070	JPC PAVEMENT-12 IN	73,609.00	SQYD
0510	02115	SAW-CLEAN-RESEAL TVERSE JOINT	8,255.00	LF
0515	02200	ROADWAY EXCAVATION	15,338.00	CUYD
0520	02237	DITCHING	6,879.00	LF
0525	02352	GUARDRAIL-STEEL W BEAM-D FACE	137.50	LF
0530	02363	GUARDRAIL CONNECTOR TO BRIDGE END TY A	4.00	EACH
0535	02365	CRASH CUSHION TYPE IX-A	1.00	EACH
0540	02367	GUARDRAIL END TREATMENT TYPE 1	1.00	EACH
0545	02369	GUARDRAIL END TREATMENT TYPE 2A	2.00	EACH
0550	02381	REMOVE GUARDRAIL	4,150.00	LF
0555	02387	GUARDRAIL CONNECTOR TO BRIDGE END TY A-1	2.00	EACH
0560	02391	GUARDRAIL END TREATMENT TYPE 4A	2.00	EACH
0565	02484	CHANNEL LINING CLASS III	64.00	TON
0570	02562	TEMPORARY SIGNS	1,300.00	SQFT
0575	02602	FABRIC-GEOTEXTILE CLASS 1	200.00	SQYD
0580	02604	FABRIC-GEOTEXTILE CLASS 1A	200.00	SQYD
0585	02650	MAINTAIN & CONTROL TRAFFIC - BULLITT	1.00	LS
0590	02671	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0595	02726	STAKING - BULLITT	1.00	LS
0600	02775	ARROW PANEL	2.00	EACH
0605	02898	RELOCATE CRASH CUSHION	3.00	EACH
0610	03225	TUBULAR MARKERS	68.00	EACH
0615	06401	FLEXIBLE DELINEATOR POST-M/W	128.00	EACH
0620	06412	STEEL POST MILE MARKERS	2.00	EACH
0625	06511	PAVE STRIPING-TEMP PAINT-6 IN	72,232.00	LF
0630	06549	PAVE STRIPING-TEMP REM TAPE-B	10,884.00	LF
0635	06550	PAVE STRIPING-TEMP REM TAPE-W	53,362.00	LF
0640	06551	PAVE STRIPING-TEMP REM TAPE-Y	66,690.00	LF
0645	08903	CRASH CUSHION TY VI CLASS BT TL3	1.00	EACH

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0650	10020NS	FUEL ADJUSTMENT	11,974.00	DOLL
0655	10030NS	ASPHALT ADJUSTMENT	5,300.00	DOLL
0660	20259ED	TEMPORARY MEDIAN CROSSOVER	1.00	EACH
0665	20411ED	LAW ENFORCEMENT OFFICER	500.00	HOURL
0670	21802EN	G/R STEEL W BEAM-S FACE (7 FT POST)	3,850.00	LF
0675	22664EN	WATER BLASTING EXISTING STRIPE	14,870.00	LF
0680	23007EN	CONC MEDIAN BARRIER TY 9T	16,100.00	LF
0685	23147EN	HIGH TENSION CABLE-ROPE BARRIER	2,000.00	LF
0690	23148EN	END ANCHORS	2.00	EACH
0695	23864EC	CHANNEL LINING CLASS III-MOD	25.00	TON
0700	23871EC	PAVE STRIPE-WET REF TAPE-6 IN Y	14,870.00	LF
0705	23872EC	PAVE STRIPE-WET REF TAPE-6 IN W	22,305.00	LF
0710	23979EC	CRASH CUSHION TY VI CLASS C TL3	1.00	EACH
0715	24255EC	REMOVE CABLE GUARDRAIL BARRIER SYSTEM	2,000.00	LF
0720	24489EC	INLAID PAVEMENT MARKER	348.00	EACH
0725	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	17.00	TON
0730	25019EC	GROOVE FOR PAVE STRIPING - 7 IN	44,622.00	LF
0735	25090EC	SINUSOIDAL RUMBLE STRIPS	13,760.00	LF
0740	26121EC	PAVE STRIPE-CONTRAST TAPE-6 IN B	7,447.00	LF
0745	00018	DRAINAGE BLANKET-TYPE II-ASPH	18,402.00	TON
0750	00461	CULVERT PIPE-15 IN	8.00	LF
0755	01000	PERFORATED PIPE-4 IN	19,768.00	LF
0760	01010	NON-PERFORATED PIPE-4 IN	1,221.00	LF
0765	01020	PERF PIPE HEADWALL TY 1-4 IN	9.00	EACH
0770	01028	PERF PIPE HEADWALL TY 3-4 IN	52.00	EACH
0775	01032	PERF PIPE HEADWALL TY 4-4 IN	14.00	EACH
0780	01202	PIPE CULVERT HEADWALL-15 IN	1.00	EACH
0785	01691	FLUME INLET TYPE 2	5.00	EACH
0790	01705	REMOVE CURB & GUTTER BOX INLET	3.00	EACH
0795	01740	CORED HOLE DRAINAGE BOX CON-4 IN	10.00	EACH
0800	02701	TEMP SILT FENCE	13,720.00	LF
0805	02704	SILT TRAP TYPE B	4.00	EACH
0810	02705	SILT TRAP TYPE C	5.00	EACH
0815	02707	CLEAN SILT TRAP TYPE B	4.00	EACH
0820	02708	CLEAN SILT TRAP TYPE C	5.00	EACH
0825	05950	EROSION CONTROL BLANKET	15,437.00	SQYD
0830	05963	INITIAL FERTILIZER	.49	TON
0835	05964	MAINTENANCE FERTILIZER	.80	TON
0840	05985	SEEDING AND PROTECTION	6,175.00	SQYD
0845	03295	EXPAN JOINT REPLACE 2 IN	10.00	LF
0850	08526	CONC CLASS M FULL DEPTH PATCH	1.00	CUYD
0855	08549	BLAST CLEANING	363.00	SQYD
0860	23331EC	EPOXY-URETHANE WATERPROOFING	3,260.00	SQFT
0865	24981EC	BRIDGE CLEANING - 015B00067L-BULLITT	1.00	LS
0870	02220	FLOWABLE FILL	4.00	CUYD
0875	22146EN	CONCRETE PATCHING REPAIR	230.00	SQFT
0880	23331EC	EPOXY-URETHANE WATERPROOFING	6,520.00	SQFT
0885	24981EC	BRIDGE CLEANING - 015B00067R-BULLITT	1.00	LS
0890	24983EC	BEARING LUBRICATION	10.00	EACH
0895	02568	MOBILIZATION	1.00	LS

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0900	02569	DEMOBILIZATION	1.00	LS
0905	04793	CONDUIT-1 1/4 IN	60.00	LF
0910	04795	CONDUIT-2 IN	30.00	LF
0915	04820	TRENCHING AND BACKFILLING	80.00	LF
0920	04829	PIEZOELECTRIC SENSOR	6.00	EACH
0925	04830	LOOP WIRE	2,900.00	LF
0930	04895	LOOP SAW SLOT AND FILL	540.00	LF
0935	20359NN	GALVANIZED STEEL CABINET	2.00	EACH
0940	20360ES818	WOOD POST	4.00	EACH
0945	20391NS835	ELECTRICAL JUNCTION BOX TYPE A	2.00	EACH

CONTRACT ID: 201028

121GR20D028-NHPP

DE04700652028

I-65 REMOVE AND REPLACE JPC PAVEMENT ON I-65 FROM MP 102.10 TO MP 103.3 IN HARDIN COUNTY JPC PAVEMENT REPAIRS, A DISTANCE OF 1.2 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00001	DGA BASE	3,967.00	TON
0010	00003	CRUSHED STONE BASE	7,016.00	TON
0015	00078	CRUSHED AGGREGATE SIZE NO 2	163.00	TON
0020	00100	ASPHALT SEAL AGGREGATE	109.00	TON
0025	00103	ASPHALT SEAL COAT	13.00	TON
0030	00214	CL3 ASPH BASE 1.00D PG64-22	2,933.00	TON
0035	01890	ISLAND HEADER CURB TYPE 1	50.00	LF
0040	01904	REMOVE CURB	36.00	LF
0045	01982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	66.00	EACH
0050	01984	DELINEATOR FOR BARRIER - WHITE	173.00	EACH
0055	01985	DELINEATOR FOR BARRIER - YELLOW	593.00	EACH
0060	02003	RELOCATE TEMP CONC BARRIER	13,940.00	LF
0065	02058	REMOVE PCC PAVEMENT	75,283.00	SQYD
0070	02070	JPC PAVEMENT-12 IN	75,283.00	SQYD
0075	02115	SAW-CLEAN-RESEAL TVERSE JOINT	7,361.00	LF
0080	02200	ROADWAY EXCAVATION	15,240.00	CUYD
0085	02237	DITCHING	6,134.00	LF
0090	02363	GUARDRAIL CONNECTOR TO BRIDGE END TY A	1.00	EACH
0095	02369	GUARDRAIL END TREATMENT TYPE 2A	4.00	EACH
0100	02381	REMOVE GUARDRAIL	2,975.00	LF
0105	02387	GUARDRAIL CONNECTOR TO BRIDGE END TY A-1	1.00	EACH
0110	02391	GUARDRAIL END TREATMENT TYPE 4A	5.00	EACH
0115	02484	CHANNEL LINING CLASS III	99.00	TON
0120	02562	TEMPORARY SIGNS	1,300.00	SQFT
0125	02570	PROJECT CPM SCHEDULE	1.00	LS
0130	02602	FABRIC-GEOTEXTILE CLASS 1	300.00	SQYD
0135	02604	FABRIC-GEOTEXTILE CLASS 1A	300.00	SQYD
0140	02650	MAINTAIN & CONTROL TRAFFIC - HARDIN	1.00	LS
0145	02671	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0150	02726	STAKING - HARDIN	1.00	LS
0155	02775	ARROW PANEL	2.00	EACH
0160	02898	RELOCATE CRASH CUSHION	2.00	EACH
0165	03225	TUBULAR MARKERS	68.00	EACH
0170	06401	FLEXIBLE DELINEATOR POST-M/W	158.00	EACH
0175	06412	STEEL POST MILE MARKERS	2.00	EACH
0180	06511	PAVE STRIPING-TEMP PAINT-6 IN	64,408.00	LF
0185	06549	PAVE STRIPING-TEMP REM TAPE-B	10,002.00	LF
0190	06550	PAVE STRIPING-TEMP REM TAPE-W	46,666.00	LF
0195	06551	PAVE STRIPING-TEMP REM TAPE-Y	58,226.00	LF
0200	08903	CRASH CUSHION TY VI CLASS BT TL3	2.00	EACH
0205	10020NS	FUEL ADJUSTMENT	10,679.00	DOLL
0210	10030NS	ASPHALT ADJUSTMENT	5,300.00	DOLL
0215	20259ED	TEMPORARY MEDIAN CROSSOVER	1.00	EACH
0220	20366NN	REPLACE GRATE - (REVISED: 8-14-20)	2.00	EACH
0225	20411ED	LAW ENFORCEMENT OFFICER	500.00	HOURL
0230	21802EN	G/R STEEL W BEAM-S FACE (7 FT POST)	2,787.50	LF
0235	22664EN	WATER BLASTING EXISTING STRIPE	12,838.00	LF
0240	23007EN	CONC MEDIAN BARRIER TY 9T	13,940.00	LF
0245	23147EN	HIGH TENSION CABLE-ROPE BARRIER	2,000.00	LF
0250	23148EN	END ANCHORS	2.00	EACH
0255	23864EC	CHANNEL LINING CLASS III-MOD	10.00	TON
0260	23871EC	PAVE STRIPE-WET REF TAPE-6 IN Y	12,837.00	LF
0265	23872EC	PAVE STRIPE-WET REF TAPE-6 IN W	30,950.00	LF
0270	23979EC	CRASH CUSHION TY VI CLASS C TL3	1.00	EACH
0275	24255EC	REMOVE CABLE GUARDRAIL BARRIER SYSTEM	2,000.00	LF
0280	24489EC	INLAID PAVEMENT MARKER	611.00	EACH
0285	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	18.00	TON
0290	25019EC	GROOVE FOR PAVE STRIPING - 7 IN	50,205.00	LF
0295	25090EC	SINUSOIDAL RUMBLE STRIPS	12,416.00	LF
0300	26121EC	PAVE STRIPE-CONTRAST TAPE-6 IN B	6,418.00	LF
0305	00018	DRAINAGE BLANKET-TYPE II-ASPH	18,821.00	TON
0310	01000	PERFORATED PIPE-4 IN	15,963.00	LF
0315	01010	NON-PERFORATED PIPE-4 IN	1,014.00	LF
0320	01020	PERF PIPE HEADWALL TY 1-4 IN	10.00	EACH
0325	01028	PERF PIPE HEADWALL TY 3-4 IN	49.00	EACH
0330	01032	PERF PIPE HEADWALL TY 4-4 IN	4.00	EACH
0335	01691	FLUME INLET TYPE 2	2.00	EACH
0340	01705	REMOVE CURB & GUTTER BOX INLET	2.00	EACH
0345	01740	CORED HOLE DRAINAGE BOX CON-4 IN	13.00	EACH
0350	02701	TEMP SILT FENCE	12,300.00	LF
0355	02704	SILT TRAP TYPE B	3.00	EACH
0360	02707	CLEAN SILT TRAP TYPE B	3.00	EACH
0365	05950	EROSION CONTROL BLANKET	13,363.00	SQYD
0370	05963	INITIAL FERTILIZER	.42	TON
0375	05964	MAINTENANCE FERTILIZER	.69	TON
0380	05985	SEEDING AND PROTECTION	5,345.00	SQYD
0385	23386EC	JOINT SEAL REPLACEMENT	236.00	LF
0390	24094EC	PARTIAL DEPTH PATCHING	6.50	CUYD
0395	24981EC	BRIDGE CLEANING - 047B00133L-HARDIN	1.00	LS

MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0400	24983EC	BEARING LUBRICATION	10.00	EACH
0405	02220	FLOWABLE FILL	4.00	CUYD
0410	23386EC	JOINT SEAL REPLACEMENT	236.00	LF
0415	24094EC	PARTIAL DEPTH PATCHING	1.00	CUYD
0420	24981EC	BRIDGE CLEANING - 047B00133R-HARDIN	1.00	LS
0425	24983EC	BEARING LUBRICATION	10.00	EACH
0430	02568	MOBILIZATION	1.00	LS
0435	02569	DEMOBILIZATION	1.00	LS

PROPOSAL BID ITEMS

Report Date 8/14/20

Section: 0001 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	7,934.00	TON		\$	
0020	00003		CRUSHED STONE BASE	13,469.00	TON		\$	
0030	00078		CRUSHED AGGREGATE SIZE NO 2	338.00	TON		\$	
0040	00100		ASPHALT SEAL AGGREGATE	232.00	TON		\$	
0050	00103		ASPHALT SEAL COAT	28.00	TON		\$	
0060	00214		CL3 ASPH BASE 1.00D PG64-22	5,866.00	TON		\$	
0070	01890		ISLAND HEADER CURB TYPE 1	825.00	LF		\$	
0080	01904		REMOVE CURB	36.00	LF		\$	
0090	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	136.00	EACH		\$	
0100	01983		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	14.00	EACH		\$	
0110	01984		DELINEATOR FOR BARRIER - WHITE	383.00	EACH		\$	
0120	01985		DELINEATOR FOR BARRIER - YELLOW	1,136.00	EACH		\$	
0130	02003		RELOCATE TEMP CONC BARRIER	30,040.00	LF		\$	
0140	02058		REMOVE PCC PAVEMENT	148,892.00	SQYD		\$	
0150	02070		JPC PAVEMENT-12 IN	148,892.00	SQYD		\$	
0160	02115		SAW-CLEAN-RESEAL TVERSE JOINT	15,616.00	LF		\$	
0170	02200		ROADWAY EXCAVATION	30,578.00	CUYD		\$	
0180	02237		DITCHING	13,013.00	LF		\$	
0190	02352		GUARDRAIL-STEEL W BEAM-D FACE	137.50	LF		\$	
0200	02363		GUARDRAIL CONNECTOR TO BRIDGE END TY A	5.00	EACH		\$	
0210	02365		CRASH CUSHION TYPE IX-A	1.00	EACH		\$	
0220	02367		GUARDRAIL END TREATMENT TYPE 1	1.00	EACH		\$	
0230	02369		GUARDRAIL END TREATMENT TYPE 2A	6.00	EACH		\$	
0240	02381		REMOVE GUARDRAIL	7,125.00	LF		\$	
0250	02387		GUARDRAIL CONNECTOR TO BRIDGE END TY A-1	3.00	EACH		\$	
0260	02391		GUARDRAIL END TREATMENT TYPE 4A	7.00	EACH		\$	
0270	02484		CHANNEL LINING CLASS III	163.00	TON		\$	
0280	02562		TEMPORARY SIGNS	2,600.00	SQFT		\$	
0290	02570		PROJECT CPM SCHEDULE	1.00	LS		\$	
0300	02602		FABRIC-GEOTEXTILE CLASS 1	500.00	SQYD		\$	
0310	02604		FABRIC-GEOTEXTILE CLASS 1A	500.00	SQYD		\$	
0320	02650		MAINTAIN & CONTROL TRAFFIC BULLITT	1.00	LS		\$	
0330	02650		MAINTAIN & CONTROL TRAFFIC HARDIN	1.00	LS		\$	
0340	02671		PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH		\$	
0350	02726		STAKING BULLITT	1.00	LS		\$	
0360	02726		STAKING HARDIN	1.00	LS		\$	
0370	02775		ARROW PANEL	4.00	EACH		\$	
0380	02898		RELOCATE CRASH CUSHION	5.00	EACH		\$	
0390	03225		TUBULAR MARKERS	136.00	EACH		\$	
0400	06401		FLEXIBLE DELINEATOR POST-M/W	286.00	EACH		\$	
0410	06412		STEEL POST MILE MARKERS	4.00	EACH		\$	

PROPOSAL BID ITEMS

Report Date 8/14/20

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0420	06511		PAVE STRIPING-TEMP PAINT-6 IN	136,640.00	LF		\$	
0430	06549		PAVE STRIPING-TEMP REM TAPE-B	20,886.00	LF		\$	
0440	06550		PAVE STRIPING-TEMP REM TAPE-W	100,028.00	LF		\$	
0450	06551		PAVE STRIPING-TEMP REM TAPE-Y	124,916.00	LF		\$	
0460	08903		CRASH CUSHION TY VI CLASS BT TL3	3.00	EACH		\$	
0470	10020NS		FUEL ADJUSTMENT	22,653.00	DOLL	\$1.00	\$	\$22,653.00
0480	10030NS		ASPHALT ADJUSTMENT	10,600.00	DOLL	\$1.00	\$	\$10,600.00
0490	20259ED		TEMPORARY MEDIAN CROSSOVER	2.00	EACH		\$	
0500	20366NN		REPLACE GRATE	2.00	EACH		\$	
0510	20411ED		LAW ENFORCEMENT OFFICER	1,000.00	HOURL		\$	
0520	21802EN		G/R STEEL W BEAM-S FACE (7 FT POST)	6,637.50	LF		\$	
0530	22664EN		WATER BLASTING EXISTING STRIPE	27,708.00	LF		\$	
0540	23007EN		CONC MEDIAN BARRIER TY 9T	30,040.00	LF		\$	
0550	23147EN		HIGH TENSION CABLE-ROPE BARRIER	4,000.00	LF		\$	
0560	23148EN		END ANCHORS	4.00	EACH		\$	
0570	23864EC		CHANNEL LINING CLASS III-MOD	35.00	TON		\$	
0580	23871EC		PAVE STRIPE-WET REF TAPE-6 IN Y	27,707.00	LF		\$	
0590	23872EC		PAVE STRIPE-WET REF TAPE-6 IN W	53,255.00	LF		\$	
0600	23979EC		CRASH CUSHION TY VI CLASS C TL3	2.00	EACH		\$	
0610	24255EC		REMOVE CABLE GUARDRAIL BARRIER SYSTEM	4,000.00	LF		\$	
0620	24489EC		INLAID PAVEMENT MARKER	959.00	EACH		\$	
0630	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	35.00	TON		\$	
0640	25019EC		GROOVE FOR PAVE STRIPING - 7 IN	94,827.00	LF		\$	
0650	25090EC		SINUSOIDAL RUMBLE STRIPS	26,176.00	LF		\$	
0660	26121EC		PAVE STRIPE-CONTRAST TAPE-6 IN B	13,865.00	LF		\$	

Section: 0002 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0670	00018		DRAINAGE BLANKET-TYPE II-ASPH	37,223.00	TON		\$	
0680	00461		CULVERT PIPE-15 IN	8.00	LF		\$	
0690	01000		PERFORATED PIPE-4 IN	35,731.00	LF		\$	
0700	01010		NON-PERFORATED PIPE-4 IN	2,235.00	LF		\$	
0710	01020		PERF PIPE HEADWALL TY 1-4 IN	19.00	EACH		\$	
0720	01028		PERF PIPE HEADWALL TY 3-4 IN	101.00	EACH		\$	
0730	01032		PERF PIPE HEADWALL TY 4-4 IN	18.00	EACH		\$	
0740	01202		PIPE CULVERT HEADWALL-15 IN	1.00	EACH		\$	
0750	01691		FLUME INLET TYPE 2	7.00	EACH		\$	
0760	01705		REMOVE CURB & GUTTER BOX INLET	5.00	EACH		\$	
0770	01740		CORED HOLE DRAINAGE BOX CON-4 IN	23.00	EACH		\$	
0780	02701		TEMP SILT FENCE	26,020.00	LF		\$	
0790	02704		SILT TRAP TYPE B	7.00	EACH		\$	
0800	02705		SILT TRAP TYPE C	5.00	EACH		\$	
0810	02707		CLEAN SILT TRAP TYPE B	7.00	EACH		\$	
0820	02708		CLEAN SILT TRAP TYPE C	5.00	EACH		\$	
0830	05950		EROSION CONTROL BLANKET	28,800.00	SQYD		\$	
0840	05963		INITIAL FERTILIZER	.91	TON		\$	

PROPOSAL BID ITEMS

Report Date 8/14/20

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0850	05964		MAINTENANCE FERTILIZER	1.49	TON		\$	
0860	05985		SEEDING AND PROTECTION	11,520.00	SQYD		\$	

Section: 0003 - BRIDGE-015B00067L

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0870	03295		EXPAN JOINT REPLACE 2 IN	10.00	LF		\$	
0880	08526		CONC CLASS M FULL DEPTH PATCH	1.00	CUYD		\$	
0890	08549		BLAST CLEANING	363.00	SQYD		\$	
0900	23331EC		EPOXY-URETHANE WATERPROOFING	3,260.00	SQFT		\$	
0910	24981EC		BRIDGE CLEANING 015B00067L-BULLITT	1.00	LS		\$	

Section: 0004 - BRIDGE-047B00133L

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0920	23386EC		JOINT SEAL REPLACEMENT	236.00	LF		\$	
0930	24094EC		PARTIAL DEPTH PATCHING	6.50	CUYD		\$	
0940	24981EC		BRIDGE CLEANING 047B00133L-HARDIN	1.00	LS		\$	
0950	24983EC		BEARING LUBRICATION	10.00	EACH		\$	

Section: 0005 - BRIDGE-015B00067R

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0960	02220		FLOWABLE FILL	4.00	CUYD		\$	
0970	22146EN		CONCRETE PATCHING REPAIR	230.00	SQFT		\$	
0980	23331EC		EPOXY-URETHANE WATERPROOFING	6,520.00	SQFT		\$	
0990	24981EC		BRIDGE CLEANING 015B00067R-BULLITT	1.00	LS		\$	
1000	24983EC		BEARING LUBRICATION	10.00	EACH		\$	

Section: 0006 - BRIDGE-047B00133R

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1010	02220		FLOWABLE FILL	4.00	CUYD		\$	
1020	23386EC		JOINT SEAL REPLACEMENT	236.00	LF		\$	
1030	24094EC		PARTIAL DEPTH PATCHING	1.00	CUYD		\$	
1040	24981EC		BRIDGE CLEANING 047B00133R-HARDIN	1.00	LS		\$	
1050	24983EC		BEARING LUBRICATION	10.00	EACH		\$	

Section: 0007 - TRAFFIC COUNTING LOOPS (ADDED: 8-14-20)

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
------	----------	-----	-------------	----------	------	-----------	----	--------

PROPOSAL BID ITEMS

Report Date 8/14/20

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1051	04793		CONDUIT-1 1/4 IN	60.00	LF		\$	
1052	04795		CONDUIT-2 IN	30.00	LF		\$	
1053	04820		TRENCHING AND BACKFILLING	80.00	LF		\$	
1054	04829		PIEZOELECTRIC SENSOR	6.00	EACH		\$	
1055	04830		LOOP WIRE	2,900.00	LF		\$	
1056	04895		LOOP SAW SLOT AND FILL	540.00	LF		\$	
1057	20359NN		GALVANIZED STEEL CABINET	2.00	EACH		\$	
1058	20360ES818		WOOD POST	4.00	EACH		\$	
1059	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	2.00	EACH		\$	

Section: 0008 - MOBILIZATION/DEMobilIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1060	02568		MOBILIZATION	1.00	LS		\$	
1070	02569		DEMobilIZATION	1.00	LS		\$	