



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

January 22, 2020

CALL NO. 200
CONTRACT ID NO. 201004
ADDENDUM # 2

Subject: HARDIN-NELSON COUNTIES, 121GR20D004-STP BRZ
Letting January 24, 2020

(1) Revised - Proposal Bid Items - Pages 139 of 141

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

PROPOSAL BID ITEMS

Report Date 1/22/20

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00003		CRUSHED STONE BASE	974.00	TON		\$	
0020	00100		ASPHALT SEAL AGGREGATE	4.54	TON		\$	
0030	00103		ASPHALT SEAL COAT	.54	TON		\$	
0040	00212		CL2 ASPH BASE 1.00D PG64-22	716.00	TON		\$	
0050	00301		CL2 ASPH SURF 0.38D PG64-22	138.00	TON		\$	
0060	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	.84	TON		\$	

Section: 0002 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0070	00078		CRUSHED AGGREGATE SIZE NO 2	100.00	TON		\$	
0080	01984		DELINEATOR FOR BARRIER - WHITE	16.00	EACH		\$	
0090	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	11.00	EACH		\$	
0100	02014		BARRICADE-TYPE III	4.00	EACH		\$	
0110	02159		TEMP DITCH	200.00	LF		\$	
0120	02223		GRANULAR EMBANKMENT	248.00	CUYD		\$	
0130	02230		EMBANKMENT IN PLACE	9,323.00	CUYD		\$	
0140	02351		GUARDRAIL-STEEL W BEAM-S FACE	925.00	LF		\$	
0150	02360		GUARDRAIL TERMINAL SECTION NO 1	2.00	EACH		\$	
0160	02381		REMOVE GUARDRAIL	700.00	LF		\$	
0170	02545		CLEARING AND GRUBBING 1.54 ACRES	1.00	LS		\$	
0180	02545		CLEARING AND GRUBBING 1.9 ACRES	1.00	LS		\$	
0190	02562		TEMPORARY SIGNS	390.00	SQFT		\$	
0200	02585		EDGE KEY	40.00	LF		\$	
0210	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0220	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0230	02697		EDGE LINE RUMBLE STRIPS	1,016.00	LF		\$	
0240	02726		STAKING	1.00	LS		\$	
0250	05985		SEEDING AND PROTECTION	11,550.00	SQYD		\$	
0260	06514		PAVE STRIPING-PERM PAINT-4 IN	4,600.00	LF		\$	
0270	25078ED		THRIE BEAM GUARDRAIL TRANSITION TL-3	4.00	EACH		\$	

Section: 0003 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0280	01691		FLUME INLET TYPE 2	4.00	EACH		\$	
0290	02159		TEMP DITCH	200.00	LF		\$	
0300	02160		CLEAN TEMP DITCH	100.00	LF		\$	
0310	02484		CHANNEL LINING CLASS III	69.00	TON		\$	
0320	02701		TEMP SILT FENCE	2,400.00	LF		\$	
0330	02704		SILT TRAP TYPE B	8.00	EACH		\$	
0340	02707		CLEAN SILT TRAP TYPE B	8.00	EACH		\$	

PROPOSAL BID ITEMS

Report Date 1/22/20

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0350	05952		TEMP MULCH	12,400.00	SQYD		\$	
0360	05953		TEMP SEEDING AND PROTECTION	9,325.00	SQYD		\$	
0370	05989		SPECIAL SEEDING CROWN VETCH	2,650.00	SQYD		\$	

Section: 0004 - BRIDGE-28082 HARDIN

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0380	00021		DRAINAGE BLANKET-EMBANKMENT	737.20	CUYD		\$	
0390	01643		JUNCTION BOX-24 IN	2.00	EACH		\$	
0400	02231		STRUCTURE GRANULAR BACKFILL	93.60	CUYD		\$	
0410	02774		PREFABRICATED WICK DRAIN	10,656.00	LF		\$	
0420	03299		ARMORED EDGE FOR CONCRETE	26.00	LF		\$	
0430	03340		STEEL PIPE-2 1/2 IN	10.50	LF		\$	
0440	03343		STEEL PIPE-4 IN	10.00	LF		\$	
0450	04797		CONDUIT-3 IN	248.00	LF		\$	
0460	08001		STRUCTURE EXCAVATION-COMMON	172.40	CUYD		\$	
0470	08019		CYCLOPEAN STONE RIP RAP	792.80	TON		\$	
0480	08033		TEST PILES	60.00	LF		\$	
0490	08051		PILES-STEEL HP14X89	285.20	LF		\$	
0500	08095		PILE POINTS-14 IN	5.00	EACH		\$	
0510	08100		CONCRETE-CLASS A	159.80	CUYD		\$	
0520	08104		CONCRETE-CLASS AA	259.20	CUYD		\$	
0530	08150		STEEL REINFORCEMENT	24,744.00	LB		\$	
0540	08160		STRUCTURAL STEEL 101,009.2 LBS	1.00	LS		\$	
0550	08170		SHEAR CONNECTORS 1128 EACH	1.00	LS		\$	
0560	08301		REMOVE SUPERSTRUCTURE	1.00	LS		\$	
0570	08474		EXPANSION DAM-5 IN NEOPRENE	26.00	LF		\$	
0580	08633		PRECAST PC I BEAM TYPE 3	522.70	LF		\$	
0590	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	1.00	EACH		\$	
0600	20746ED		ROCK CORINGS	104.00	LF		\$	
0610	23378EC		CONCRETE SEALING	13,656.80	SQFT		\$	
0620	23813EC		DECK DRAIN	6.00	EACH		\$	
0630	24732EC		DRILLED SHAFT-84 IN-COMMON	164.80	LF		\$	
0640	24733EC		DRILLED SHAFT-78 IN-ROCK	41.60	LF		\$	
0650	25069EC		DRILLED SHAFT - 84 IN - SOLID ROCK	4.80	LF		\$	
0660	24590ED	AA1	STEEL REINFORCEMENT-GALVANIZED	79,337.20	LB		\$	
0670	25028ED	AA1	RAIL SYSTEM SINGLE SLOPE - 40 IN GALV. REINFORCEMENT (REVISED: 1-22-20)	483.20	LF		\$	
0680	08151	AA2	STEEL REINFORCEMENT-EPOXY COATED	79,337.20	LB		\$	
0690	10100NS	AA2	STEEL PRICE ADJUSTMENT	198,360.00	DOLL	\$1.00	\$	\$198,360.00
0700	25028ED	AA2	RAIL SYSTEM SINGLE SLOPE - 40 IN EPOXY REINFORCEMENT (REVISED: 1-22-20)	483.20	LF		\$	

PROPOSAL BID ITEMS

Report Date 1/22/20

Section: 0005 - BRIDGE-NELSON

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0710	00021		DRAINAGE BLANKET-EMBANKMENT	1,105.80	CUYD		\$	
0720	01643		JUNCTION BOX-24 IN	2.00	EACH		\$	
0730	02231		STRUCTURE GRANULAR BACKFILL	140.40	CUYD		\$	
0740	02692		SETTLEMENT PLATFORM	1.00	EACH		\$	
0750	02774		PREFABRICATED WICK DRAIN	15,984.00	LF		\$	
0760	03299		ARMORED EDGE FOR CONCRETE	39.00	LF		\$	
0770	03340		STEEL PIPE-2 1/2 IN	15.80	LF		\$	
0780	03343		STEEL PIPE-4 IN	15.00	LF		\$	
0790	04797		CONDUIT-3 IN	372.00	LF		\$	
0800	08001		STRUCTURE EXCAVATION-COMMON	258.60	CUYD		\$	
0810	08019		CYCLOPEAN STONE RIP RAP	1,189.20	TON		\$	
0820	08033		TEST PILES	90.00	LF		\$	
0830	08051		PILES-STEEL HP14X89	427.80	LF		\$	
0840	08095		PILE POINTS-14 IN	7.20	EACH		\$	
0850	08100		CONCRETE-CLASS A	239.60	CUYD		\$	
0860	08104		CONCRETE-CLASS AA	388.90	CUYD		\$	
0870	08150		STEEL REINFORCEMENT	37,116.00	LB		\$	
0880	08160		STRUCTURAL STEEL 151,513.8 LB	1.00	LS		\$	
0890	08170		SHEAR CONNECTORS 1,692 LB	1.00	LS		\$	
0900	08301		REMOVE SUPERSTRUCTURE	1.00	LS		\$	
0910	08474		EXPANSION DAM-5 IN NEOPRENE	39.00	LF		\$	
0920	08633		PRECAST PC I BEAM TYPE 3	784.00	LF		\$	
0930	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	1.00	EACH		\$	
0940	20745ED		ROCK SOUNDINGS	256.80	LF		\$	
0950	20746ED		ROCK CORINGS	156.00	LF		\$	
0960	23378EC		CONCRETE SEALING	20,485.20	SQFT		\$	
0970	23813EC		DECK DRAIN	8.40	EACH		\$	
0980	24732EC		DRILLED SHAFT-84 IN-COMMON	247.20	LF		\$	
0990	24733EC		DRILLED SHAFT-78 IN-ROCK	62.40	LF		\$	
1000	25069EC		DRILLED SHAFT - 84 IN - SOLID ROCK	7.20	LF		\$	
1010	24590ED	AB1	STEEL REINFORCEMENT-GALVANIZED	119,005.80	LB		\$	
1020	25028ED	AB1	RAIL SYSTEM SINGLE SLOPE - 40 IN GALV. REINF	724.80	LF		\$	
1030	08151	AB2	STEEL REINFORCEMENT-EPOXY COATED	119,005.80	LB		\$	
1040	10100NS	AB2	STEEL PRICE ADJUSTMENT	297,540.00	DOLL	\$1.00	\$	\$297,540.00
1050	25028ED	AB2	RAIL SYSTEM SINGLE SLOPE - 40 IN EPOXY REINFORCEMENT	724.80	LF		\$	

Section: 0006 - DEMOBILIZATION &/OR MOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
1060	02568		MOBILIZATION	1.00	LS		\$	
1070	02569		DEMOBILIZATION	1.00	LS		\$	