



**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

November 27, 2017

CALL NO. 200
CONTRACT ID NO. 171053
ADDENDUM # 1

Subject: Hopkins County, 054GR17D053-NHPP IM
Letting December 8, 2017

(1) Revised - Notes - Pages 19-20 of 148

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:ks
Enclosures



An Equal Opportunity Employer M/F/D

PAVEMENT SUMMARY
I-69 HOPKINS COUNTY
M.P. 118.150 TO M.P. 124.946
BOTH DIRECTIONS
ITEM NO. 2-2097
PAVING AREAS
ITEM

MAINLINE	TOTAL SQ YD
SURFACE DRIVING LANES AND INSIDE SHOULDERS 2.0" CL4 ASPH SURF 0.50A PG76-22	223,403
 RAMPS AT KY 260	
SURFACE DRIVING LANES 2.0" CL4 ASPH SURF 0.50A PG76-22	5,200
 ASPHALT PAVE MILLING & TEXTURING	SQ YD
MAINLINE TOTAL (2.0")	223,403
RAMPS AT KY 260 (2.0")	5,200

PAVING AREAS

CODE	ITEM	UNITS	TOTAL
1	DGA BASE (1)	TON	300
100	ASPHALT SEAL AGGREGATE (1) (3)	TON	100
103	ASPHALT SEAL COAT (1) (4)	TON	12
219	CL4 ASPH BASE 1.0D PG76-22 (1) (2)	TON	1,000
335	CL4 ASPH SURF 0.50A PG76-22 (2)	TON	25,146
2677	ASPHALT PAVE MILLING & TEXTURING	TON	25,596
2007IEC	JOINT ADHESIVE	LIN FT	153,716
20362ES403	SHOULDER RUMBLE STRIPS - SAWED	LIN FT	71,808

- (1) TO BE USED AS DIRECTED BY THE ENGINEER
- (2) INCLUDES 1000 TONS TO BE USED AS DIRECTED BY THE ENGINEER FOR BASE FAILURE AREAS
- (3) ESTIMATED AT 20 LBS/S.Y.
- (4) ESTIMATED AT 2.4 LBS/S.Y.

I69 - MP 118.15 - MP 124.95 HOPKINS COUNTY Item No. 2-2097.00 GENERAL SUMMARY			
ITEM NUMBER	ITEM	QUANTITY	UNIT
1982	DELINEATOR FOR GUARDRAIL MONO DIR-W	40	EACH
2562	TEMPORARY SIGNS	2,400	SQ FT
2568	MOBILIZATION	1	LP SUM
2569	DEMOBILIZATION	1	LP SUM
2650	MAINTAIN AND CONTROL TRAFFIC	1	LP SUM
2671	PORTABLE CHANGEABLE MESSAGE SIGN	4	EACH
2676	MOBILIZATION FOR MILL & TEXT	1	LP SUM
6549	PAVE STRIPING-TEMP REM TAPE-B	1,000	LIN FT
6550	PAVE STRIPING-TEMP REM TAPE-W	3,600	LIN FT
6551	PAVE STRIPING-TEMP REM TAPE-Y	3,600	LIN FT
10020NS	FUEL ADJUSTMENT	\$40,673	DOLLAR
10030NS	ASPHALT ADJUSTMENT	\$102,158	DOLLAR
24189ER	DURABLE WATERBORNE MARKING-6 IN W	89,760	LIN FT
24190ER	DURABLE WATERBORNE MARKING-6 IN Y	71,808	LIN FT
24191ER	DURABLE WATERBORNE MARKING-12 IN W	1,750	LIN FT
24489EC	INLAID PAVEMENT MARKER	898	EACH
24781EC	INTELLIGENT COMPACTION FOR ASPHALT	26,168	TON
24891EC	PAVE MOUNT INFRARED TEMP EQUIPMENT	2,010,624	SQ FT