



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Secretary

October 11, 2011

CALL NO. 201  
CONTRACT ID NO. 111345  
ADDENDUM # 1

Subject: Clinton County, 121GR11D045-HPSTP AND NH  
Letting October 21, 2011

- (1) Revised - Material Summary - Pages 35-41 of 140
- (2) Revised - Bid Items - Pages 129-140 of 140

Proposal revisions are available at <http://transportation.ky.gov/contract/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith  
Director  
Division of Construction Procurement

RG:ks  
Enclosures



An Equal Opportunity Employer M/F/D

MATERIAL SUMMARY

CONTRACT ID: 111345

HPSTP 0139 (003)

PES NO: DE02701271145

ALBANY BY-PASS (US 127) BEGINNING JUST NORTH OF SPRING CREEK EXTENDING NORTH TO KY  
1590 , A DISTANCE OF 4.220000 MILES.

LINE NO	BID CODE	DESCRIPTION	QUANTITY	UNIT
1078	00071	CRUSHED AGGREGATE SIZE NO 57	1,500.00	TON
1011	00078	CRUSHED AGGREGATE SIZE NO 2	1,515.00	TON
1005	01000	PERFORATED PIPE-4 IN	2,557.00	LF
1006	01010	NON-PERFORATED PIPE-4 IN	280.00	LF
1007	01020	PERF PIPE HEADWALL TY 1-4 IN	3.00	EACH
1008	01024	PERF PIPE HEADWALL TY 2-4 IN	2.00	EACH
1009	01028	PERF PIPE HEADWALL TY 3-4 IN	8.00	EACH
1010	01032	PERF PIPE HEADWALL TY 4-4 IN	2.00	EACH
1050	01310	REMOVE PIPE	211.00	LF
1075	01825	ISLAND CURB AND GUTTER	75.00	LF
1076	01845	ISLAND INTEGRAL CURB	59.50	LF
1077	01946	MOUNTABLE MEDIAN TYPE 2A	79.00	SQYD
1025	01982	DELINEATOR FOR GUARDRAIL-WHITE	191.00	EACH
1052	02014	BARRICADE-TYPE III	8.00	EACH
1049	02091	REMOVE PAVEMENT	1,187.00	SQYD
1056	02223	GRANULAR EMBANKMENT	26,466.00	CUYD
1003	02242	WATER	3,541.00	MGAL
1013	02262	FENCE-WOVEN WIRE TYPE 1	31,667.00	LF
1016	02351	GUARDRAIL-STEEL W BEAM-S FACE	29,245.00	LF
1021	02360	GUARDRAIL TERMINAL SECTION NO 1	47.00	EACH
1017	02363	GUARDRAIL CONNECTOR TO BRIDGE END TY A	14.00	EACH
1022	02367	GUARDRAIL END TREATMENT TYPE 1	3.00	EACH
1018	02369	GUARDRAIL END TREATMENT TYPE 2A	3.00	EACH
1019	02373	GUARDRAIL END TREATMENT TYPE 3	5.00	EACH
1020	02391	GUARDRAIL END TREATMENT TYPE 4A	26.00	EACH
1065	02404	SEPTIC TANK TREATMENT	9.00	EACH
1014	02429	RIGHT-OF-WAY MONUMENT TYPE 1	354.00	EACH
1027	02432	WITNESS POST	354.00	EACH
1066	02475	PLUG WATER WELL	2.00	EACH
1023	02483	CHANNEL LINING CLASS II	10,099.00	TON
1024	02484	CHANNEL LINING CLASS III	16,257.00	TON
1001	02545	CLEARING AND GRUBBING (8-260.02 - 180 ACRES)	1.00	LS
1031	02555	CONCRETE-CLASS B	78.00	CUYD
1051	02562	SIGNS	786.00	SQFT
1015	02585	EDGE KEY	232.00	LF
1057	02596	FABRIC-GEOTEXTILE TYPE I	2,135.00	SQYD
1058	02598	FABRIC-GEOTEXTILE TYPE III	35,130.00	SQYD
1059	02599	FABRIC-GEOTEXTILE TYPE IV	32,922.00	SQYD
1060	02600	FABRIC GEOTEXTILE TY IV FOR PIPE	8,297.00	SQYD
1061	02650	MAINTAIN & CONTROL TRAFFIC (8-260.02)	1.00	LS
1063	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.02 - NO 2 OLD US127)	1.00	LS
1062	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.02 - NO 1 US127)	1.00	LS
1064	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.02 - NO 3 KY553)	1.00	LS
1053	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
1071	02692	SETTLEMENT PLATFORM	6.00	EACH
1069	02696	SHOULDER RUMBLE STRIPS-SAWED	56,880.00	LF
1002	02726	STAKING	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 111345

		(8-260.02)		
1072	03340	STEEL PIPE-2 1/2 IN	31.50	LF
1073	03343	STEEL PIPE-4 IN	147.00	LF
1026	05950	EROSION CONTROL BLANKET	35,601.00	SQYD
1028	05966	TOPDRESSING FERTILIZER	63.00	TON
1029	05985	SEEDING AND PROTECTION	1,212,383.00	SQYD
1034	06510	PAVE STRIPING-TEMP PAINT-4 IN	20,000.00	LF
1035	06514	PAVE STRIPING-PERM PAINT-4 IN	153,635.00	LF
1036	06517	PAVE STRIPING-PERM PAINT-12 IN	960.00	LF
1047	06554	PAVE STRIPING-DUR TY 1-4 IN W	2,954.00	LF
1048	06555	PAVE STRIPING-DUR TY 1-4 IN Y	2,954.00	LF
1042	06568	PAVE MARKING-THERMO STOP BAR-24IN	373.00	LF
1043	06570	PAVE MARKING-PAINT CROSS-HATCH	39,940.00	SQFT
1045	06573	PAVE MARKING-THERMO STR ARROW	11.00	EACH
1039	06574	PAVE MARKING-THERMO CURV ARROW	49.00	EACH
1044	06575	PAVE MARKING-THERMO COMB ARROW	6.00	EACH
1046	06588	PAVEMENT MARKER TY IVA-BY TEMP	28.00	EACH
1040	06589	PAVEMENT MARKER TYPE V-MW	146.00	EACH
1037	06591	PAVEMENT MARKER TYPE V-BY	913.00	EACH
1041	06592	PAVEMENT MARKER TYPE V-B W/R	56.00	EACH
1038	06593	PAVEMENT MARKER TYPE V-B Y/R	56.00	EACH
1074	08019	CYCLOPEAN STONE RIP RAP	2,895.00	TON
		(REVISED: 10-11-11)		
1032	08100	CONCRETE-CLASS A	101.85	CUYD
1033	08150	STEEL REINFORCEMENT	6,434.00	LB
1054	20209EP69	GRANULAR PILE CORE	175.00	CUYD
1055	20210EP69	COHESIVE PILE CORE	1,396.00	CUYD
1070	23131ER701	PIPELINE VIDEO INSPECTION	3,031.00	LF
1030	23143ED	KPDES PERMIT AND TEMP EROSION CONTROL	1.00	LS
		(8-260.02)		
1004	23237EN10W	WATERBLAST STRIPE REMOVAL	4,178.00	LF
1067	24005EC	FILL AND CAP GAS WELL	4.00	EACH
1068	24266EC	FILL AND CAP OIL WELL	1.00	EACH
2010	00439	ENTRANCE PIPE-12 IN	374.00	LF
2011	00440	ENTRANCE PIPE-15 IN	564.00	LF
2012	00441	ENTRANCE PIPE-18 IN	192.00	LF
2013	00445	ENTRANCE PIPE-30 IN	237.00	LF
2001	00461	CULVERT PIPE-15 IN	55.00	LF
2002	00462	CULVERT PIPE-18 IN	1,544.00	LF
2003	00464	CULVERT PIPE-24 IN	1,076.00	LF
2004	00466	CULVERT PIPE-30 IN	511.00	LF
2005	00468	CULVERT PIPE-36 IN	459.00	LF
2006	00469	CULVERT PIPE-42 IN	124.00	LF
2007	00470	CULVERT PIPE-48 IN	512.00	LF
2008	00475	CULVERT PIPE-78 IN	236.00	LF
2009	00521	STORM SEWER PIPE-15 IN	178.00	LF
2021	01371	METAL END SECTION TY 1-18 IN	2.00	EACH
2022	01391	METAL END SECTION TY 3-18 IN	4.00	EACH
2018	01433	SLOPED BOX OUTLET TYPE 1-18 IN	4.00	EACH
2019	01434	SLOPED BOX OUTLET TYPE 1-24 IN	4.00	EACH
2020	01450	S & F BOX INLET-OUTLET-18 IN	3.00	EACH
2023	01451	S & F BOX INLET-OUTLET-24 IN	4.00	EACH
2024	01452	S & F BOX INLET-OUTLET-30 IN	2.00	EACH
2017	01480	CURB BOX INLET TYPE B	2.00	EACH
2014	01490	DROP BOX INLET TYPE 1	5.00	EACH
2015	01505	DROP BOX INLET TYPE 5B	1.00	EACH
2016	01511	DROP BOX INLET TYPE 5D	1.00	EACH
3007	00003	CRUSHED STONE BASE	90,117.00	TON
3008	00013	LIME STABILIZED ROADBED	173,846.00	SQYD
3009	00014	LIME	3,221.00	TON
3013	00100	ASPHALT SEAL AGGREGATE	552.00	TON
3005	00212	CL2 ASPH BASE 1.00D PG64-22	9,617.00	TON
3003	00214	CL3 ASPH BASE 1.00D PG64-22	51,602.00	TON
3004	00221	CL2 ASPH BASE 0.75D PG64-22	7,062.00	TON
3012	00291	EMULSIFIED ASPHALT RS-2	65.90	TON
3002	00301	CL2 ASPH SURF 0.38D PG64-22	6,342.00	TON
3001	00339	CL3 ASPH SURF 0.38D PG64-22	7,647.00	TON
3010	00358	ASPHALT CURING SEAL	173.70	TON
3006	02078	JPC PAVEMENT-6 IN SHLD	79.00	SQYD
3011	02702	SAND FOR BLOTTER	434.90	TON
3017	10203ND	PAVEMENT ADJUSTMENT	1.00	LS
		(8-260.02 - ASPHALT)		

3015	21553EN	EMBANKMENT	1,168,674.00	CUYD
3016	21554EN	EXCAVATION	1,247,921.00	CUYD
4008	00003	CRUSHED STONE BASE	90,117.00	TON
4009	00013	LIME STABILIZED ROADBED	173,846.00	SQYD
4010	00014	LIME	3,221.00	TON
4014	00100	ASPHALT SEAL AGGREGATE	552.00	TON
4005	00212	CL2 ASPH BASE 1.00D PG64-22	9,617.00	TON
4003	00214	CL3 ASPH BASE 1.00D PG64-22	8,082.00	TON
4004	00221	CL2 ASPH BASE 0.75D PG64-22	7,062.00	TON
4013	00291	EMULSIFIED ASPHALT RS-2	65.90	TON
4002	00301	CL2 ASPH SURF 0.38D PG64-22	6,342.00	TON
4001	00339	CL3 ASPH SURF 0.38D PG64-22	1,636.00	TON
4011	00358	ASPHALT CURING SEAL	173.70	TON
4006	02073	JPC PAVEMENT-9 IN	87,434.00	SQYD
4007	02078	JPC PAVEMENT-6 IN SHLD	79.00	SQYD
4012	02702	SAND FOR BLOTTER	434.90	TON
4017	10203ND	PAVEMENT ADJUSTMENT (8-260.02 - CONCRETE)	1.00	LS
4015	21553EN	EMBANKMENT	1,168,674.00	CUYD
4016	21554EN	EXCAVATION	1,247,921.00	CUYD
5008	00003	CRUSHED STONE BASE	81,990.00	TON
5009	00013	LIME STABILIZED ROADBED	173,846.00	SQYD
5010	00014	LIME	3,221.00	TON
5014	00100	ASPHALT SEAL AGGREGATE	552.00	TON
5005	00212	CL2 ASPH BASE 1.00D PG64-22	692.00	TON
5003	00214	CL3 ASPH BASE 1.00D PG64-22	8,082.00	TON
5004	00221	CL2 ASPH BASE 0.75D PG64-22	7,062.00	TON
5013	00291	EMULSIFIED ASPHALT RS-2	65.90	TON
5002	00301	CL2 ASPH SURF 0.38D PG64-22	2,623.00	TON
5001	00339	CL3 ASPH SURF 0.38D PG64-22	1,636.00	TON
5011	00358	ASPHALT CURING SEAL	173.70	TON
5006	02073	JPC PAVEMENT-9 IN	87,434.00	SQYD
5007	02078	JPC PAVEMENT-6 IN SHLD	54,171.00	SQYD
5012	02702	SAND FOR BLOTTER	434.90	TON
5017	10203ND	PAVEMENT ADJUSTMENT (8-260.02 - CONCRETE)	1.00	LS
5015	21553EN	EMBANKMENT	1,168,674.00	CUYD
5016	21554EN	EXCAVATION	1,247,921.00	CUYD
6104	08002	STRUCTURE EXCAV-SOLID ROCK	727.00	CUYD
6103	08003	FOUNDATION PREPARATION (8-260.02 - 26115)	1.00	LS
6101	08100	CONCRETE-CLASS A	1,545.80	CUYD
6102	08150	STEEL REINFORCEMENT	158,405.00	LB
6206	02231	STRUCTURE GRANULAR BACKFILL	282.00	CUYD
6207	02998	MASONRY COATING	1,307.00	SQYD
6211	03299	ARMORED EDGE FOR CONCRETE	68.00	LF
6214	08001	STRUCTURE EXCAVATION-COMMON	146.00	CUYD
6205	08020	CRUSHED AGGREGATE SLOPE PROT	123.00	TON
6209	08033	TEST PILES	308.00	LF
6208	08046	PILES-STEEL HP12X53	2,064.00	LF
6210	08094	PILE POINTS-12 IN	46.00	EACH
6201	08100	CONCRETE-CLASS A	190.90	CUYD
6202	08104	CONCRETE-CLASS AA	319.70	CUYD
6203	08150	STEEL REINFORCEMENT	32,905.00	LB
6204	08151	STEEL REINFORCEMENT-EPOXY COATED	93,658.00	LB
6215	08160	STRUCTURAL STEEL (8-260.02 - 26116 - 432 LBS)	1.00	LS
6212	08634	PRECAST PC I BEAM TYPE 4	1,006.00	LF
6213	21532ED	RAIL SYSTEM TYPE III	510.00	LF
6303	08003	FOUNDATION PREPARATION (8-260.02 - 26119)	1.00	LS
6301	08100	CONCRETE-CLASS A	159.10	CUYD
6302	08150	STEEL REINFORCEMENT	18,278.00	LB
6406	02231	STRUCTURE GRANULAR BACKFILL	334.00	CUYD
6407	02998	MASONRY COATING	916.00	SQYD
6411	03299	ARMORED EDGE FOR CONCRETE	98.00	LF
6414	08001	STRUCTURE EXCAVATION-COMMON	238.00	CUYD
6405	08020	CRUSHED AGGREGATE SLOPE PROT	256.00	TON
6409	08033	TEST PILES	212.00	LF
6408	08046	PILES-STEEL HP12X53	2,342.00	LF
6410	08094	PILE POINTS-12 IN	54.00	EACH

6401	08100	CONCRETE-CLASS A	191.10	CUYD
6402	08104	CONCRETE-CLASS AA	283.60	CUYD
6403	08150	STEEL REINFORCEMENT	25,608.00	LB
6404	08151	STEEL REINFORCEMENT-EPOXY COATED	82,860.00	LB
6412	08633	PRECAST PC I BEAM TYPE 3	776.40	LF
6413	21532ED	RAIL SYSTEM TYPE III	316.00	LF
7901	02568	MOBILIZATION	1.00	LS
7902	02569	DEMobilIZATION	1.00	LS
7904	02742	TRAINEE PAYMENT REIMBURSEMENT 2 ARTICULATING TRUCK (OFF ROAD) DRIVERS	3,200.00	HOUR
7903	02742	TRAINEE PAYMENT REIMBURSEMENT 1 CLASS A/B OPERATOR	1,600.00	HOUR

NH 1271 (105) PES NO: DE02701271146  
ALBANY-TENNESSEE STATE LINE ROAD (US 127) RECONSTRUCT US 127 FROM THE KENTUCKY STATE  
LINE EXTENDING NORTH TO THE ALBANY BYPASS , A DISTANCE OF 2.510000 MILES.

LINE NO	BID CODE	DESCRIPTION	QUANTITY	UNIT
1001	00020	TRAFFIC BOUND BASE	1,150.00	TON
1002	00078	CRUSHED AGGREGATE SIZE NO 2	9.00	TON
1003	01000	PERFORATED PIPE-4 IN	406.00	LF
1004	01010	NON-PERFORATED PIPE-4 IN	90.00	LF
1005	01028	PERF PIPE HEADWALL TY 3-4 IN	5.00	EACH
1006	01032	PERF PIPE HEADWALL TY 4-4 IN	4.00	EACH
1007	01845	ISLAND INTEGRAL CURB	50.00	LF
1008	01982	DELINEATOR FOR GUARDRAIL-WHITE	73.00	EACH
1009	02014	BARRICADE-TYPE III	20.00	EACH
1010	02091	REMOVE PAVEMENT	12,610.00	SQYD
1011	02223	GRANULAR EMBANKMENT	7,290.00	CUYD
1012	02242	WATER	2,100.00	MGAL
1013	02262	FENCE-WOVEN WIRE TYPE 1	25,283.00	LF
1014	02265	REMOVE FENCE	4,315.00	LF
1015	02351	GUARDRAIL-STEEL W BEAM-S FACE	6,962.50	LF
1018	02360	GUARDRAIL TERMINAL SECTION NO 1	6.00	EACH
1019	02363	GUARDRAIL CONNECTOR TO BRIDGE END TY A	2.00	EACH
1020	02373	GUARDRAIL END TREATMENT TYPE 3	2.00	EACH
1022	02391	GUARDRAIL END TREATMENT TYPE 4A	7.00	EACH
1023	02429	RIGHT-OF-WAY MONUMENT TYPE 1	90.00	EACH
1024	02432	WITNESS POST	45.00	EACH
1026	02483	CHANNEL LINING CLASS II	1,554.00	TON
1027	02484	CHANNEL LINING CLASS III	5,290.00	TON
1028	02545	CLEARING AND GRUBBING (8-260.10 - CLINTON CO KY - 56 ACRES)	1.00	LS
1029	02562	SIGNS	300.00	SQFT
1030	02585	EDGE KEY	140.00	LF
1031	02599	FABRIC-GEOTEXTILE TYPE IV	25,051.00	SQYD
1032	02600	FABRIC GEOTEXTILE TY IV FOR PIPE	10,945.00	SQYD
1033	02650	MAINTAIN & CONTROL TRAFFIC (8-260.10 - CLINTON CO KY)	1.00	LS
1034	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.10 - CLINTON CO KY - DIVERSION 1)	1.00	LS
1035	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.10 - CLINTON CO KY - DIVERSION 2)	1.00	LS
1036	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.10 - CLINTON CO KY - DIVERSION 5)	1.00	LS
1037	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
1038	02696	SHOULDER RUMBLE STRIPS-SAWED	25,164.00	LF
1039	02726	STAKING (8-260.10 - CLINTON CO KY)	1.00	LS
1040	05950	EROSION CONTROL BLANKET	31,933.00	SQYD
1041	05966	TOPDRESSING FERTILIZER	20.00	TON
1059	05985	SEEDING AND PROTECTION	125,674.00	SQYD
1042	06510	PAVE STRIPING-TEMP PAINT-4 IN	35,600.00	LF
1045	06514	PAVE STRIPING-PERM PAINT-4 IN	60,904.00	LF
1052	06568	PAVE MARKING-THERMO STOP BAR-24IN	36.00	LF
1046	06570	PAVE MARKING-PAINT CROSS-HATCH	20,794.00	SQFT
1047	06574	PAVE MARKING-THERMO CURV ARROW	17.00	EACH
1049	06588	PAVEMENT MARKER TY IVA-BY TEMP	63.00	EACH
1050	06589	PAVEMENT MARKER TYPE V-MW	41.00	EACH
1048	06591	PAVEMENT MARKER TYPE V-BY	420.00	EACH
1053	08100	CONCRETE-CLASS A	37.81	CUYD
1054	08150	STEEL REINFORCEMENT	1,478.00	LB
1055	20210EP69	COHESIVE PILE CORE	407.00	CUYD
1056	20315ED	CLAY SOIL CAP	32.00	CUYD
1057	23131ER701	PIPELINE VIDEO INSPECTION	3,488.00	LF
1058	23143ED	KPDES PERMIT AND TEMP EROSION CONTROL (8-260.10 - CLINTON CO KY)	1.00	LS

2010	00003	CRUSHED STONE BASE	48,090.00	TON
2013	00013	LIME STABILIZED ROADBED	79,156.00	SQYD
2014	00014	LIME	1,460.00	TON
2009	00100	ASPHALT SEAL AGGREGATE	479.00	TON
2004	00212	CL2 ASPH BASE 1.00D PG64-22	6,884.00	TON
2003	00214	CL3 ASPH BASE 1.00D PG64-22	22,402.00	TON
2005	00221	CL2 ASPH BASE 0.75D PG64-22	838.00	TON
2008	00291	EMULSIFIED ASPHALT RS-2	57.40	TON
2002	00301	CL2 ASPH SURF 0.38D PG64-22	3,224.00	TON
2001	00339	CL3 ASPH SURF 0.38D PG64-22	3,088.00	TON
2015	00358	ASPHALT CURING SEAL	79.20	TON
2007	02082	JPC PAVEMENT-9 IN SHLD	67.00	SQYD
2016	02702	SAND FOR BLOTTER	198.00	TON
2021	10203ND	PAVEMENT ADJUSTMENT (8-260.10 - ASPHALT FOR CLINTON CO)	1.00	LS
2017	21553EN	EMBANKMENT	297,145.00	CUYD
2018	21554EN	EXCAVATION	385,578.00	CUYD
3011	00003	CRUSHED STONE BASE	43,828.00	TON
3014	00013	LIME STABILIZED ROADBED	77,371.00	SQYD
3015	00014	LIME	1,427.00	TON
3010	00100	ASPHALT SEAL AGGREGATE	450.00	TON
3004	00212	CL2 ASPH BASE 1.00D PG64-22	6,884.00	TON
3003	00214	CL3 ASPH BASE 1.00D PG64-22	733.00	TON
3005	00221	CL2 ASPH BASE 0.75D PG64-22	838.00	TON
3009	00291	EMULSIFIED ASPHALT RS-2	53.90	TON
3002	00301	CL2 ASPH SURF 0.38D PG64-22	3,224.00	TON
3001	00339	CL3 ASPH SURF 0.38D PG64-22	150.00	TON
3016	00358	ASPHALT CURING SEAL	77.40	TON
3007	02073	JPC PAVEMENT-9 IN	42,729.00	SQYD
3008	02082	JPC PAVEMENT-9 IN SHLD	67.00	SQYD
3017	02702	SAND FOR BLOTTER	193.60	TON
3020	10203ND	PAVEMENT ADJUSTMENT (8-260.10 - CONCRETE FOR CLINTON CO)	1.00	LS
3018	21553EN	EMBANKMENT	297,145.00	CUYD
3019	21554EN	EXCAVATION	385,578.00	CUYD
4012	00003	CRUSHED STONE BASE	40,410.00	TON
4015	00013	LIME STABILIZED ROADBED	76,756.00	SQYD
4016	00014	LIME	1,416.00	TON
4011	00100	ASPHALT SEAL AGGREGATE	450.00	TON
4004	00212	CL2 ASPH BASE 1.00D PG64-22	1,686.00	TON
4003	00214	CL3 ASPH BASE 1.00D PG64-22	733.00	TON
4005	00221	CL2 ASPH BASE 0.75D PG64-22	838.00	TON
4010	00291	EMULSIFIED ASPHALT RS-2	53.90	TON
4002	00301	CL2 ASPH SURF 0.38D PG64-22	1,100.00	TON
4001	00339	CL3 ASPH SURF 0.38D PG64-22	150.00	TON
4017	00358	ASPHALT CURING SEAL	76.80	TON
4007	02073	JPC PAVEMENT-9 IN	42,729.00	SQYD
4008	02078	JPC PAVEMENT-6 IN SHLD	30,889.00	SQYD
4009	02082	JPC PAVEMENT-9 IN SHLD	67.00	SQYD
4018	02702	SAND FOR BLOTTER	192.00	TON
4021	10203ND	PAVEMENT ADJUSTMENT (8-260.10 - CONCRETE FOR CLINTON CO)	1.00	LS
4019	21553EN	EMBANKMENT	297,145.00	CUYD
4020	21554EN	EXCAVATION	385,578.00	CUYD
5001	00440	ENTRANCE PIPE-15 IN	432.00	LF
5002	00441	ENTRANCE PIPE-18 IN	68.00	LF
5003	00461	CULVERT PIPE-15 IN	78.00	LF
5004	00462	CULVERT PIPE-18 IN	1,374.00	LF
5005	00464	CULVERT PIPE-24 IN	393.00	LF
5006	00466	CULVERT PIPE-30 IN	288.00	LF
5007	00468	CULVERT PIPE-36 IN	92.00	LF
5008	00469	CULVERT PIPE-42 IN	79.00	LF
5009	00470	CULVERT PIPE-48 IN	87.00	LF
5010	00471	CULVERT PIPE-54 IN	50.00	LF
5011	00494	CULVERT PIPE-30 IN EQUIV	42.00	LF
5012	00524	STORM SEWER PIPE-24 IN	505.00	LF
5013	01381	METAL END SECTION TY 2-18 IN	1.00	EACH
5014	01390	METAL END SECTION TY 3-15 IN	2.00	EACH
5015	01391	METAL END SECTION TY 3-18 IN	2.00	EACH
5016	01394	METAL END SECTION TY 3-30 IN	2.00	EACH
5017	01396	METAL END SECTION TY 3-42 IN	2.00	EACH

5018	01397	METAL END SECTION TY 3-48 IN	2.00	EACH
5019	01433	SLOPED BOX OUTLET TYPE 1-18 IN	2.00	EACH
5020	01450	S & F BOX INLET-OUTLET-18 IN	4.00	EACH
5021	01452	S & F BOX INLET-OUTLET-30 IN	2.00	EACH
5022	01453	S & F BOX INLET-OUTLET-36 IN	1.00	EACH
5023	01490	DROP BOX INLET TYPE 1	2.00	EACH
5024	01643	JUNCTION BOX-24 IN	1.00	EACH
5026	01756	MANHOLE TYPE A	1.00	EACH
6001	02231	STRUCTURE GRANULAR BACKFILL	350.00	CUYD
6002	02998	MASONRY COATING	2,220.00	SQYD
6003	03299	ARMORED EDGE FOR CONCRETE	106.00	LF
6004	08001	STRUCTURE EXCAVATION-COMMON	100.00	CUYD
6005	08002	STRUCTURE EXCAV-SOLID ROCK	100.00	CUYD
6007	08019	CYCLOPEAN STONE RIP RAP	960.00	TON
6008	08020	CRUSHED AGGREGATE SLOPE PROT	590.00	TON
6009	08033	TEST PILES	64.00	LF
6010	08039	PRE-DRILLING FOR PILES	150.00	LF
6011	08051	PILES-STEEL HP14X89	219.00	LF
6012	08095	PILE POINTS-14 IN	10.00	EACH
6013	08100	CONCRETE-CLASS A	652.20	CUYD
6014	08104	CONCRETE-CLASS AA	700.10	CUYD
6015	08150	STEEL REINFORCEMENT	135,756.00	LB
6016	08151	STEEL REINFORCEMENT-EPOXY COATED	209,463.00	LB
6017	08160	STRUCTURAL STEEL	1.00	LS
		(8-260.10 - CLINTON CO - 1978 LBS)		
6019	21532ED	RAIL SYSTEM TYPE III	757.00	LF
6006	24375EC	STRUCTURE EXCAVATION-SPECIAL SOLID ROC	210.00	CUYD
6018	24376EC	PRECAST PC I-BEAM-78 IN(MOD)	1,872.00	LF
7001	02568	MOBILIZATION	1.00	LS
7002	02569	DEMOBILIZATION	1.00	LS

NH 1271 (105)

PES NO: DE12201271146

ALBANY-TENNESSEE STATE LINE ROAD (US 127) RECONSTRUCT US 127 FROM 0.6 MILE SOUTH OF THE KENTUCKY STATE LINE EXTENDING NORTH TO THE KENTUCKY STATE LINE , A DISTANCE OF 0.600000 MILES.

LINE NO	BID CODE	DESCRIPTION	QUANTITY	UNIT
1001	00020	TRAFFIC BOUND BASE	600.00	TON
1002	00078	CRUSHED AGGREGATE SIZE NO 2	4.00	TON
1003	01000	PERFORATED PIPE-4 IN	159.00	LF
1004	01010	NON-PERFORATED PIPE-4 IN	40.00	LF
1005	01028	PERF PIPE HEADWALL TY 3-4 IN	1.00	EACH
1006	01032	PERF PIPE HEADWALL TY 4-4 IN	3.00	EACH
1008	01982	DELINEATOR FOR GUARDRAIL-WHITE	19.00	EACH
1009	02014	BARRICADE-TYPE III	10.00	EACH
1010	02091	REMOVE PAVEMENT	5,070.00	SQYD
1011	02223	GRANULAR EMBANKMENT	8,364.00	CUYD
1012	02242	WATER	600.00	MGAL
1013	02262	FENCE-WOVEN WIRE TYPE 1	6,249.00	LF
1015	02351	GUARDRAIL-STEEL W BEAM-S FACE	1,775.00	LF
1021	02381	REMOVE GUARDRAIL	2,278.00	LF
1023	02429	RIGHT-OF-WAY MONUMENT TYPE 1	2.00	EACH
1028	02483	CHANNEL LINING CLASS II	562.00	TON
1030	02545	CLEARING AND GRUBBING	1.00	LS
		(8-260.10 - PICKETT CO TN - 16 ACRES)		
1031	02562	SIGNS	200.00	SQFT
1032	02585	EDGE KEY	128.00	LF
1033	02599	FABRIC-GEOTEXTILE TYPE IV	51,263.00	SQYD
1034	02600	FABRIC GEOTEXTILE TY IV FOR PIPE	2,157.00	SQYD
1035	02650	MAINTAIN & CONTROL TRAFFIC	1.00	LS
		(8-260.10 - PICKETT CO TN)		
1037	02651	DIVERSIONS (BY-PASS DETOURS)	1.00	LS
		(8-260.10 - PICKETT CO TN - DIVERSION 4)		
1036	02651	DIVERSIONS (BY-PASS DETOURS)	1.00	LS
		(8-260.10 - PICKETT CO TN - DIVERSION 3)		
1038	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
1039	02696	SHOULDER RUMBLE STRIPS-SAWED	8,673.00	LF
1040	02726	STAKING	1.00	LS
		(8-260.10 - PICKETT CO TN)		
1041	05950	EROSION CONTROL BLANKET	5,927.00	SQYD
1042	05966	TOPDRESSING FERTILIZER	5.00	TON
1059	05985	SEEDING AND PROTECTION	30,687.00	SQYD
1043	06510	PAVE STRIPING-TEMP PAINT-4 IN	6,500.00	LF
1045	06514	PAVE STRIPING-PERM PAINT-4 IN	21,494.00	LF
1052	06568	PAVE MARKING-THERMO STOP BAR-24IN	26.00	LF
1046	06570	PAVE MARKING-PAINT CROSS-HATCH	4,887.00	SQFT
1047	06574	PAVE MARKING-THERMO CURV ARROW	17.00	EACH

1049	06588	PAVEMENT MARKER TY IVA-BY TEMP	39.00	EACH
1050	06589	PAVEMENT MARKER TYPE V-MW	33.00	EACH
1048	06591	PAVEMENT MARKER TYPE V-BY	157.00	EACH
1051	06600	REMOVE PAVEMENT MARKER TYPE V	40.00	EACH
1053	08100	CONCRETE-CLASS A	9.18	CUYD
1054	08150	STEEL REINFORCEMENT	330.00	LB
1057	23131ER701	PIPELINE VIDEO INSPECTION	745.00	LF
1058	23143ED	KPDES PERMIT AND TEMP EROSION CONTROL (8-260.10 - PICKETT CO TN)	1.00	LS
1016	24366EC	GUARDRAIL TERMINAL (TN)	8.00	EACH
1017	24367EC	GUARDRAIL END ANCHOR TY 38(TN)	3.00	EACH
1025	24368EC	RIGHT OF WAY MONUMENT TY A(TN)	10.00	EACH
1026	24369EC	RIGHT OF WAY MONUMENT TY B(TN)	5.00	EACH
1027	24370EC	RIGHT OF WAY MONUMENT TY C(TN)	6.00	EACH
2010	00003	CRUSHED STONE BASE (REVISED: 10-11-11)	25,848.00	TON
2009	00100	ASPHALT SEAL AGGREGATE	216.00	TON
2006	00190	LEVELING & WEDGING PG64-22	321.00	TON
2004	00212	CL2 ASPH BASE 1.00D PG64-22	3,177.00	TON
2003	00214	CL3 ASPH BASE 1.00D PG64-22	6,563.00	TON
2005	00221	CL2 ASPH BASE 0.75D PG64-22 (REVISED: 10-11-11)	310.00	TON
2008	00291	EMULSIFIED ASPHALT RS-2	25.80	TON
2002	00301	CL2 ASPH SURF 0.38D PG64-22 (REVISED: 10-11-11)	1,077.00	TON
2001	00339	CL3 ASPH SURF 0.38D PG64-22	1,145.00	TON
2019	02676	MOBILIZATION FOR MILL & TEXT (8-260.10 - PICKETT CO TN)	1.00	LS
2020	02677	ASPHALT PAVE MILLING & TEXTURING	575.00	TON
2017	21553EN	EMBANKMENT	89,420.00	CUYD
2018	21554EN	EXCAVATION	35,901.00	CUYD
3011	00003	CRUSHED STONE BASE (REVISED: 10-11-11)	25,848.00	TON
3010	00100	ASPHALT SEAL AGGREGATE	216.00	TON
3006	00190	LEVELING & WEDGING PG64-22	321.00	TON
3004	00212	CL2 ASPH BASE 1.00D PG64-22	3,177.00	TON
3003	00214	CL3 ASPH BASE 1.00D PG64-22	6,563.00	TON
3005	00221	CL2 ASPH BASE 0.75D PG64-22 (REVISED: 10-11-11)	310.00	TON
3009	00291	EMULSIFIED ASPHALT RS-2	25.80	TON
3002	00301	CL2 ASPH SURF 0.38D PG64-22 (REVISED: 10-11-11)	1,077.00	TON
3001	00339	CL3 ASPH SURF 0.38D PG64-22	1,145.00	TON
3020	02676	MOBILIZATION FOR MILL & TEXT (8-260.10 - PICKETT CO TN)	1.00	LS
3022	02677	ASPHALT PAVE MILLING & TEXTURING	575.00	TON
3018	21553EN	EMBANKMENT	89,420.00	CUYD
3019	21554EN	EXCAVATION	35,901.00	CUYD
4012	00003	CRUSHED STONE BASE (REVISED: 10-11-11)	25,848.00	TON
4011	00100	ASPHALT SEAL AGGREGATE	216.00	TON
4006	00190	LEVELING & WEDGING PG64-22	321.00	TON
4004	00212	CL2 ASPH BASE 1.00D PG64-22	3,177.00	TON
4003	00214	CL3 ASPH BASE 1.00D PG64-22	6,563.00	TON
4005	00221	CL2 ASPH BASE 0.75D PG64-22 (REVISED: 10-11-11)	310.00	TON
4010	00291	EMULSIFIED ASPHALT RS-2	25.80	TON
4002	00301	CL2 ASPH SURF 0.38D PG64-22 (REVISED: 10-11-11)	1,077.00	TON
4001	00339	CL3 ASPH SURF 0.38D PG64-22	1,145.00	TON
4021	02676	MOBILIZATION FOR MILL & TEXT (8-260.10 - PICKETT CO TN)	1.00	LS
4022	02677	ASPHALT PAVE MILLING & TEXTURING	575.00	TON
4019	21553EN	EMBANKMENT	89,420.00	CUYD
4020	21554EN	EXCAVATION	35,901.00	CUYD
5001	00440	ENTRANCE PIPE-15 IN	171.00	LF
5004	00462	CULVERT PIPE-18 IN	539.00	LF
5005	00464	CULVERT PIPE-24 IN	47.00	LF
5006	00466	CULVERT PIPE-30 IN	86.00	LF
5019	01433	SLOPED BOX OUTLET TYPE 1-18 IN	4.00	EACH
5025	01645	JUNCTION BOX-36 IN	1.00	EACH
7001	02568	MOBILIZATION	1.00	LS
7002	02569	DEMOBILIZATION	1.00	LS



CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 1  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
SECTION 0001 PAVING ALT GROUP AA1 (ALTERNATE 1 - ASPHALT W/ ASPHALT SHOULDERS)						
0010	00003	CRUSHED STONE BASE (REVISED: 10-11-11)	164,055.000	TON		
0020	00013	LIME STABILIZED ROADBED	253,002.000	SQYD		
0030	00014	LIME	4,681.000	TON		
0040	00100	ASPHALT SEAL AGGREGATE	1,247.000	TON		
0050	00190	LEVELING & WEDGING PG64-22	321.000	TON		
0060	00212	CL2 ASPH BASE 1.00D PG64-22	19,678.000	TON		
0070	00214	CL3 ASPH BASE 1.00D PG64-22	80,567.000	TON		
0080	00221	CL2 ASPH BASE 0.75D PG64-22 (REVISED: 10-11-11)	8,210.000	TON		
0090	00291	EMULSIFIED ASPHALT RS-2	149.100	TON		
0100	00301	CL2 ASPH SURF 0.38D PG64-22 (REVISED: 10-11-11)	10,643.000	TON		
0110	00339	CL3 ASPH SURF 0.38D PG64-22	11,880.000	TON		
0120	00358	ASPHALT CURING SEAL	252.900	TON		
0130	02078	JPC PAVEMENT-6 IN SHLD	79.000	SQYD		
0140	02082	JPC PAVEMENT-9 IN SHLD	67.000	SQYD		
0150	02676	MOBILIZATION FOR MILL & TEXT (8-260.10 - PICKETT CO TN)	( 1.00)	LS		
0160	02677	ASPHALT PAVE MILLING & TEXTURING	575.000	TON		
0170	02702	SAND FOR BLOTTER	632.900	TON		
0180	10203ND	PAVEMENT ADJUSTMENT (8-260.02 - ASPHALT)	( 1.00)	LS	459,382.00	459,382.00
0190	10203ND	PAVEMENT ADJUSTMENT (8-260.10 - ASPHALT FOR CLINTON C )	( 1.00)	LS	273,169.00	273,169.00
0200	21553EN	EMBANKMENT	1,555,239.000	CUYD		

CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 2  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0210	21554EN	EXCAVATION	1,669,400.000	CUYD		
SECTION 0002 PAVING ALT GROUP AA2 (ALTERNATE 2 - CONCRETE W/ ASPHALT SHOULDERS)						
0220	00003	CRUSHED STONE BASE (REVISED: 10-11-11)	159,793.000	TON		
0230	00013	LIME STABILIZED ROADBED	251,217.000	SQYD		
0240	00014	LIME	4,648.000	TON		
0250	00100	ASPHALT SEAL AGGREGATE	1,218.000	TON		
0260	00190	LEVELING & WEDGING PG64-22	321.000	TON		
0270	00212	CL2 ASPH BASE 1.00D PG64-22	19,678.000	TON		
0280	00214	CL3 ASPH BASE 1.00D PG64-22	15,378.000	TON		
0290	00221	CL2 ASPH BASE 0.75D PG64-22 (REVISED: 10-11-11)	8,210.000	TON		
0300	00291	EMULSIFIED ASPHALT RS-2	145.600	TON		
0310	00301	CL2 ASPH SURF 0.38D PG64-22 (REVISED: 10-11-11)	10,643.000	TON		
0320	00339	CL3 ASPH SURF 0.38D PG64-22	2,931.000	TON		
0330	00358	ASPHALT CURING SEAL	251.100	TON		
0340	02073	JPC PAVEMENT-9 IN	130,163.000	SQYD		
0350	02078	JPC PAVEMENT-6 IN SHLD	79.000	SQYD		
0360	02082	JPC PAVEMENT-9 IN SHLD	67.000	SQYD		
0370	02676	MOBILIZATION FOR MILL & TEXT (8-260.10 - PICKETT CO TN)	( 1.00)	LS		
0380	02677	ASPHALT PAVE MILLING & TEXTURING	575.000	TON		
0390	02702	SAND FOR BLOTTER	628.500	TON		
0400	10203ND	PAVEMENT ADJUSTMENT (8-260.02 - CONCRETE)	( 1.00)	LS	231,686.00	231,686.00

CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 3  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0410	10203ND	PAVEMENT ADJUSTMENT (8-260.10 - CONCRETE FOR CLINTON	( 1.00)	LS	134,589.00	134,589.00
0420	21553EN	EMBANKMENT	1,555,239.000	CUYD		
0430	21554EN	EXCAVATION	1,669,400.000	CUYD		
SECTION 0003 PAVING ALT GROUP AA3 (ALTERNATE 3 - CONCRETE W/ CONCRETE SHOULDERS						
0440	00003	CRUSHED STONE BASE (REVISED: 10-11-11)	148,248.000	TON		
0450	00013	LIME STABILIZED ROADBED	250,602.000	SQYD		
0460	00014	LIME	4,637.000	TON		
0470	00100	ASPHALT SEAL AGGREGATE	1,218.000	TON		
0480	00190	LEVELING & WEDGING PG64-22	321.000	TON		
0490	00212	CL2 ASPH BASE 1.00D PG64-22	5,555.000	TON		
0500	00214	CL3 ASPH BASE 1.00D PG64-22	15,378.000	TON		
0510	00221	CL2 ASPH BASE 0.75D PG64-22 (REVISED: 10-11-11)	8,210.000	TON		
0520	00291	EMULSIFIED ASPHALT RS-2	145.600	TON		
0530	00301	CL2 ASPH SURF 0.38D PG64-22 (REVISED: 10-11-11)	4,800.000	TON		
0540	00339	CL3 ASPH SURF 0.38D PG64-22	2,931.000	TON		
0550	00358	ASPHALT CURING SEAL	250.500	TON		
0560	02073	JPC PAVEMENT-9 IN	130,163.000	SQYD		
0570	02078	JPC PAVEMENT-6 IN SHLD	85,060.000	SQYD		
0580	02082	JPC PAVEMENT-9 IN SHLD	67.000	SQYD		
0590	02676	MOBILIZATION FOR MILL & TEXT (8-260.10 - PICKETT CO TN)	( 1.00)	LS		
0600	02677	ASPHALT PAVE MILLING & TEXTURING	575.000	TON		

CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 4  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0610	02702	SAND FOR BLOTTER	626.900	TON		
0620	10203ND	PAVEMENT ADJUSTMENT (8-260.02 - CONCRETE)	( 1.00)	LS	231,686.00	231,686.00
0630	10203ND	PAVEMENT ADJUSTMENT (8-260.10 - CONCRETE FOR CLINTON	( 1.00)	LS	134,589.00	134,589.00
0640	21553EN	EMBANKMENT	1,555,239.000	CUYD		
0650	21554EN	EXCAVATION	1,669,400.000	CUYD		
SECTION 0004 ROADWAY						
0660	00020	TRAFFIC BOUND BASE	1,750.000	TON		
0670	00071	CRUSHED AGGREGATE SIZE NO 57	1,500.000	TON		
0680	00078	CRUSHED AGGREGATE SIZE NO 2	1,528.000	TON		
0690	01000	PERFORATED PIPE-4 IN	3,122.000	LF		
0700	01010	NON-PERFORATED PIPE-4 IN	410.000	LF		
0710	01020	PERF PIPE HEADWALL TY 1-4 IN	3.000	EACH		
0720	01024	PERF PIPE HEADWALL TY 2-4 IN	2.000	EACH		
0730	01028	PERF PIPE HEADWALL TY 3-4 IN	14.000	EACH		
0740	01032	PERF PIPE HEADWALL TY 4-4 IN	9.000	EACH		
0750	01310	REMOVE PIPE	211.000	LF		
0760	01825	ISLAND CURB AND GUTTER	75.000	LF		
0770	01845	ISLAND INTEGRAL CURB	109.500	LF		
0780	01946	MOUNTABLE MEDIAN TYPE 2A	79.000	SQYD		
0790	01982	DELINEATOR FOR GUARDRAIL-WHITE	283.000	EACH		
0800	02014	BARRICADE-TYPE III	38.000	EACH		

CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 5  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0810	02091	REMOVE PAVEMENT	18,867.000	SQYD		
0820	02223	GRANULAR EMBANKMENT	42,120.000	CUYD		
0830	02242	WATER	6,241.000	MGAL		
0840	02262	FENCE-WOVEN WIRE TYPE 1	63,199.000	LF		
0850	02265	REMOVE FENCE	4,315.000	LF		
0860	02351	GUARDRAIL-STEEL W BEAM-S FACE	37,982.500	LF		
0870	02360	GUARDRAIL TERMINAL SECTION NO 1	53.000	EACH		
0880	02363	GUARDRAIL CONNECTOR TO BRIDGE END TY A	16.000	EACH		
0890	02367	GUARDRAIL END TREATMENT TYPE 1	3.000	EACH		
0900	02369	GUARDRAIL END TREATMENT TYPE 2A	3.000	EACH		
0910	02373	GUARDRAIL END TREATMENT TYPE 3	7.000	EACH		
0920	02381	REMOVE GUARDRAIL	2,278.000	LF		
0930	02391	GUARDRAIL END TREATMENT TYPE 4A	33.000	EACH		
0940	02404	SEPTIC TANK TREATMENT	9.000	EACH		
0950	02429	RIGHT-OF-WAY MONUMENT TYPE 1	446.000	EACH		
0960	02432	WITNESS POST	399.000	EACH		
0970	02475	PLUG WATER WELL	2.000	EACH		
0980	02483	CHANNEL LINING CLASS II	12,215.000	TON		
0990	02484	CHANNEL LINING CLASS III	21,547.000	TON		
1000	02545	CLEARING AND GRUBBING (8-260.02 - 180 ACRES)	( 1.00)	LS		
1010	02545	CLEARING AND GRUBBING (8-260.10 - CLINTON CO KY - 56 ACRES)	( 1.00)	LS		

CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 6  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
1020	02545	CLEARING AND GRUBBING (8-260.10 - PICKETT CO TN - 16 AC)	( 1.00)	LS		
1030	02555	CONCRETE-CLASS B	78.000	CUYD		
1040	02562	SIGNS	1,286.000	SQFT		
1050	02585	EDGE KEY	500.000	LF		
1060	02596	FABRIC-GEOTEXTILE TYPE I	2,135.000	SQYD		
1070	02598	FABRIC-GEOTEXTILE TYPE III	35,130.000	SQYD		
1080	02599	FABRIC-GEOTEXTILE TYPE IV	109,236.000	SQYD		
1090	02600	FABRIC GEOTEXTILE TY IV FOR PIPE	21,399.000	SQYD	2.00	42,798.00
1100	02650	MAINTAIN & CONTROL TRAFFIC (8-260.02)	( 1.00)	LS		
1110	02650	MAINTAIN & CONTROL TRAFFIC (8-260.10 - CLINTON CO KY)	( 1.00)	LS		
1120	02650	MAINTAIN & CONTROL TRAFFIC (8-260.10 - PICKETT CO TN)	( 1.00)	LS		
1130	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.02 - NO 1 US127)	( 1.00)	LS		
1140	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.02 - NO 2 OLD US127)	( 1.00)	LS		
1150	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.02 - NO 3 KY553)	( 1.00)	LS		
1160	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.10 - CLINTON CO KY - DIVER	( 1.00)	LS		
1170	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.10 - CLINTON CO KY - DIVER	( 1.00)	LS		
1180	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.10 - CLINTON CO KY - DIVER	( 1.00)	LS		
1190	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.10 - PICKETT CO TN - DIVER	( 1.00)	LS		
1200	02651	DIVERSIONS (BY-PASS DETOURS) (8-260.10 - PICKETT CO TN - DIVER	( 1.00)	LS		
1210	02671	PORTABLE CHANGEABLE MESSAGE SIGN	6.000	EACH		
1220	02692	SETTLEMENT PLATFORM	6.000	EACH		

CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 7  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
1230	02696	SHOULDER RUMBLE STRIPS-SAWED	90,717.000	LF		
1240	02726	STAKING (8-260.02)	( 1.00)	LS		
1250	02726	STAKING (8-260.10 - CLINTON CO KY)	( 1.00)	LS		
1260	02726	STAKING (8-260.10 - PICKETT CO TN)	( 1.00)	LS		
1270	03340	STEEL PIPE-2 1/2 IN	31.500	LF		
1280	03343	STEEL PIPE-4 IN	147.000	LF		
1290	05950	EROSION CONTROL BLANKET	73,461.000	SQYD		
1300	05966	TOPDRESSING FERTILIZER	88.000	TON		
1310	05985	SEEDING AND PROTECTION	1,368,744.000	SQYD		
1320	06510	PAVE STRIPING-TEMP PAINT-4 IN	62,100.000	LF		
1330	06514	PAVE STRIPING-PERM PAINT-4 IN	236,033.000	LF		
1340	06517	PAVE STRIPING-PERM PAINT-12 IN	960.000	LF		
1350	06554	PAVE STRIPING-DUR TY 1-4 IN W	2,954.000	LF		
1360	06555	PAVE STRIPING-DUR TY 1-4 IN Y	2,954.000	LF		
1370	06568	PAVE MARKING-THERMO STOP BAR-24IN	435.000	LF		
1380	06570	PAVE MARKING-PAINT CROSS-HATCH	65,621.000	SQFT		
1390	06573	PAVE MARKING-THERMO STR ARROW	11.000	EACH		
1400	06574	PAVE MARKING-THERMO CURV ARROW	83.000	EACH		
1410	06575	PAVE MARKING-THERMO COMB ARROW	6.000	EACH		
1420	06588	PAVEMENT MARKER TY IVA-BY TEMP	130.000	EACH		
1430	06589	PAVEMENT MARKER TYPE V-MW	220.000	EACH		

CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 8  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
1440	06591	PAVEMENT MARKER TYPE V-BY	1,490.000	EACH		
1450	06592	PAVEMENT MARKER TYPE V-B W/R	56.000	EACH		
1460	06593	PAVEMENT MARKER TYPE V-B Y/R	56.000	EACH		
1470	06600	REMOVE PAVEMENT MARKER TYPE V	40.000	EACH		
1480	08019	CYCLOPEAN STONE RIP RAP (REVISED: 10-11-11)	2,895.000	TON		
1490	08100	CONCRETE-CLASS A	148.840	CUYD		
1500	08150	STEEL REINFORCEMENT	8,242.000	LB		
1510	20209EP69	GRANULAR PILE CORE	175.000	CUYD		
1520	20210EP69	COHESIVE PILE CORE	1,803.000	CUYD		
1530	20315ED	CLAY SOIL CAP	32.000	CUYD		
1540	23131ER701	PIPELINE VIDEO INSPECTION	7,264.000	LF		
1550	23143ED	KPDES PERMIT AND TEMP EROSION CONTROL (8-260.02)	( 1.00)	LS		
1560	23143ED	KPDES PERMIT AND TEMP EROSION CONTROL (8-260.10 - CLINTON CO KY)	( 1.00)	LS		
1570	23143ED	KPDES PERMIT AND TEMP EROSION CONTROL (8-260.10 - PICKETT CO TN)	( 1.00)	LS		
1580	23237EN10W	WATERBLAST STRIPE REMOVAL	4,178.000	LF		
1590	24005EC	FILL AND CAP GAS WELL	4.000	EACH		
1600	24266EC	FILL AND CAP OIL WELL	1.000	EACH		
1610	24366EC	GUARDRAIL TERMINAL (TN)	8.000	EACH		
1620	24367EC	GUARDRAIL END ANCHOR TY 38(TN)	3.000	EACH		
1630	24368EC	RIGHT OF WAY MONUMENT TY A(TN)	10.000	EACH		
1640	24369EC	RIGHT OF WAY MONUMENT TY B(TN)	5.000	EACH		



CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 9  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE UNIT QUANTITY	UNIT PRICE	AMOUNT
1650	24370EC	RIGHT OF WAY MONUMENT TY C(TN)	6.000 EACH		
SECTION 0005 DRAINAGE					
1660	00439	ENTRANCE PIPE-12 IN	374.000 LF		
1670	00440	ENTRANCE PIPE-15 IN	1,167.000 LF		
1680	00441	ENTRANCE PIPE-18 IN	260.000 LF		
1690	00445	ENTRANCE PIPE-30 IN	237.000 LF		
1700	00461	CULVERT PIPE-15 IN	133.000 LF		
1710	00462	CULVERT PIPE-18 IN	3,457.000 LF		
1720	00464	CULVERT PIPE-24 IN	1,516.000 LF		
1730	00466	CULVERT PIPE-30 IN	885.000 LF		
1740	00468	CULVERT PIPE-36 IN	551.000 LF		
1750	00469	CULVERT PIPE-42 IN	203.000 LF		
1760	00470	CULVERT PIPE-48 IN	599.000 LF		
1770	00471	CULVERT PIPE-54 IN	50.000 LF		
1780	00475	CULVERT PIPE-78 IN	236.000 LF		
1790	00494	CULVERT PIPE-30 IN EQUIV	42.000 LF		
1800	00521	STORM SEWER PIPE-15 IN	178.000 LF		
1810	00524	STORM SEWER PIPE-24 IN	505.000 LF		
1820	01371	METAL END SECTION TY 1-18 IN	2.000 EACH		
1830	01381	METAL END SECTION TY 2-18 IN	1.000 EACH		
1840	01390	METAL END SECTION TY 3-15 IN	2.000 EACH		

CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 10  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE UNIT QUANTITY	UNIT PRICE	AMOUNT
1850	01391	METAL END SECTION TY 3-18 IN	6.000 EACH		
1860	01394	METAL END SECTION TY 3-30 IN	2.000 EACH		
1870	01396	METAL END SECTION TY 3-42 IN	2.000 EACH		
1880	01397	METAL END SECTION TY 3-48 IN	2.000 EACH		
1890	01433	SLOPED BOX OUTLET TYPE 1-18 IN	10.000 EACH		
1900	01434	SLOPED BOX OUTLET TYPE 1-24 IN	4.000 EACH		
1910	01450	S & F BOX INLET-OUTLET-18 IN	7.000 EACH		
1920	01451	S & F BOX INLET-OUTLET-24 IN	4.000 EACH		
1930	01452	S & F BOX INLET-OUTLET-30 IN	4.000 EACH		
1940	01453	S & F BOX INLET-OUTLET-36 IN	1.000 EACH		
1950	01480	CURB BOX INLET TYPE B	2.000 EACH		
1960	01490	DROP BOX INLET TYPE 1	7.000 EACH		
1970	01505	DROP BOX INLET TYPE 5B	1.000 EACH		
1980	01511	DROP BOX INLET TYPE 5D	1.000 EACH		
1990	01643	JUNCTION BOX-24 IN	1.000 EACH		
2000	01645	JUNCTION BOX-36 IN	1.000 EACH		
2010	01756	MANHOLE TYPE A	1.000 EACH		
SECTION 0006 BRIDGE					
2020	02231	STRUCTURE GRANULAR BACKFILL	966.000 CUYD		
2030	02998	MASONRY COATING	4,443.000 SQYD		
2040	03299	ARMORED EDGE FOR CONCRETE	272.000 LF		

CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 11  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
2050	08001	STRUCTURE EXCAVATION-COMMON	484.000	CUYD		
2060	08002	STRUCTURE EXCAV-SOLID ROCK	827.000	CUYD		
2070	08003	FOUNDATION PREPARATION (8-260.02 - 26115)	( 1.00)	LS		
2080	08003	FOUNDATION PREPARATION (8-260.02 - 26119)	( 1.00)	LS		
2090	08019	CYCLOPEAN STONE RIP RAP	960.000	TON		
2100	08020	CRUSHED AGGREGATE SLOPE PROT	969.000	TON		
2110	08033	TEST PILES	584.000	LF		
2120	08039	PRE-DRILLING FOR PILES	150.000	LF		
2130	08046	PILES-STEEL HP12X53	4,406.000	LF		
2140	08051	PILES-STEEL HP14X89	219.000	LF		
2150	08094	PILE POINTS-12 IN	100.000	EACH		
2160	08095	PILE POINTS-14 IN	10.000	EACH		
2170	08100	CONCRETE-CLASS A	2,739.100	CUYD		
2180	08104	CONCRETE-CLASS AA	1,303.400	CUYD		
2190	08150	STEEL REINFORCEMENT	370,952.000	LB		
2200	08151	STEEL REINFORCEMENT-EPOXY COATED	385,981.000	LB		
2210	08160	STRUCTURAL STEEL (8-260.02 - 26116 - 432 LBS)	( 1.00)	LS		
2220	08160	STRUCTURAL STEEL (8-260.10 - CLINTON CO - 1978 LBS)	( 1.00)	LS		
2230	08633	PRECAST PC I BEAM TYPE 3	776.400	LF		
2240	08634	PRECAST PC I BEAM TYPE 4	1,006.000	LF		
2250	21532ED	RAIL SYSTEM TYPE III	1,583.000	LF		

CONTRACT ID: 111345  
COUNTY: CLINTON, OTHER STATE - PICKETT COUNTY, TN  
PROPOSAL: 121GR11D045-HPSTP AND NH

PAGE: 12  
LETTING: 10/21/11  
CALL NO: 201

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
2260	24375EC	STRUCTURE EXCAVATION-SPECIAL SOLID ROCK	210.000	CUYD		
2270	24376EC	PRECAST PC I-BEAM-78 IN(MOD)	1,872.000	LF		
SECTION 0007 TRAINEES						
2280	02742	TRAINEE PAYMENT REIMBURSEMENT 1 CLASS A/B OPERATOR	1,600.000	HOUR		
2290	02742	TRAINEE PAYMENT REIMBURSEMENT 2 ARTICULATING TRUCK (OFF ROAD) DRIVERS	3,200.000	HOUR		
SECTION 0008 MOBILIZATION / DEMOBILIZATION						
2300	02568	MOBILIZATION (NO MORE THAN 5%)		LUMP		
2310	02569	DEMOBILIZATION (AT LEAST 1.5%)		LUMP		
		TOTAL BID				