



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Secretary

December 10, 2012

CALL NO. 206  
CONTRACT ID NO. 121380  
ADDENDUM # 2

Subject: Fayette-Woodford Counties, 121GR12D080-NH  
Letting December 14, 2012

- (1) Revised - Plan Sheets - All plan revisions were included in addendum # 1
- (2) Added - Note - Page 24 (b) of 131
- (3) Revised - Material Summary - Pages 72-81 of 131
- (4) Revised - Bid Items - Pages 122-131 (a) of 131

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

Plan revisions are available at <http://www.lynnimaging.com/kytransportation/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith  
Director  
Division of Construction Procurement

RG:ks  
Enclosures



An Equal Opportunity Employer M/F/D

7-2033.00  
Fayette/Woodford County  
US 60

#### SPECIAL NOTE FOR LOAD TRANSFER ASSEMBLY ANCHOR HOOKS

The anchor hooks to be used for all full-depth replacement areas should be per Standard Drawing RPS-020-013. Anchor hooks used for load transfer assemblies in the 7" unbonded overlay portion of the project may be less than 18" in length. The minimum number of hooks and the spacing shown in the Standard Drawings should still be used. The hooks should extend a minimum of 1" into the existing concrete pavement and should be placed using a power-actuated nailing device. Any alternate hook(s) will require approval of the Engineer. The Engineer may require additional hooks to securely hold the assembly in place.

# MATERIAL SUMMARY

**CONTRACT ID: 121380**

**121GR12D080-NH**

**DE03400601280**

LEXINGTON-VERSAILLES ROAD (US 60) PAVEMENT REHABILITATION ON US 60 FROM WOODFORD COUNTY LINE TO KY 4 IN LEXINGTON GRADE & DRAIN AND PAVEMENT ALTERNATES, A DISTANCE OF 4.36 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0010	06550	PAVE STRIPING-TEMP REM TAPE-W	7,000.00	LF
0020	06549	PAVE STRIPING-TEMP REM TAPE-B	7,000.00	LF
0030	06510	PAVE STRIPING-TEMP PAINT-4 IN	342,870.00	LF
0040	05990	SODDING	1,312.00	SQYD
0050	05950	EROSION CONTROL BLANKET	81,704.00	SQYD
0060	03225	TUBULAR MARKERS	1,056.00	EACH
0070	02775	ARROW PANEL	2.00	EACH
0080	02726	STAKING - (FAYETTE COUNTY)	1.00	LS
0090	02720	SIDEWALK-4 IN CONCRETE	37.00	SQYD
0100	02690	SAFELOADING	27.10	CUYD
0110	02671	PORTABLE CHANGEABLE MESSAGE SIGN	7.00	EACH
0120	02651	DIVERSIONS (BY-PASS DETOURS) - (FAYETTE COUNTY - #7)	1.00	LS
0130	02651	DIVERSIONS (BY-PASS DETOURS) - (FAYETTE COUNTY - #6)	1.00	LS
0140	02651	DIVERSIONS (BY-PASS DETOURS) - (FAYETTE COUNTY - #5)	1.00	LS
0150	02651	DIVERSIONS (BY-PASS DETOURS) - (FAYETTE COUNTY - #4)	1.00	LS
0160	02650	MAINTAIN & CONTROL TRAFFIC - (FAYETTE COUNTY)	1.00	LS
0170	02599	FABRIC-GEOTEXTILE TYPE IV	270.00	SQYD
0180	02562	SIGNS	1,400.00	SQFT
0190	02469	CLEAN SINKHOLE	3.00	EACH
0200	02237	DITCHING	32,636.00	LF
0210	02223	GRANULAR EMBANKMENT	156.00	CUYD
0220	02014	BARRICADE-TYPE III	28.00	EACH
0230	01984	DELINEATOR FOR BARRIER - WHITE	10.00	EACH
0240	01982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	127.00	EACH
0250	08151	STEEL REINFORCEMENT-EPOXY COATED	5,755.00	LB
0260	08104	CONCRETE-CLASS AA	34.60	CUYD
0270	08001	STRUCTURE EXCAVATION-COMMON	57.50	CUYD
0280	02998	MASONRY COATING	200.00	SQYD
0290	02555	CONCRETE-CLASS B	34.50	CUYD
0300	02403	REMOVE CONCRETE MASONRY	23.90	CUYD
0310	23274EN11F	TURF REINFORCEMENT MAT 1	1,533.00	SQYD
0320	23143ED	KPDES PERMIT AND TEMP EROSION CONTROL - (FAYETTE COUNTY)	1.00	LS
0330	22664EN	WATER BLASTING EXISTING STRIPE	212,814.00	LF
0340	20467NS112	RELOCATE TUBULAR MARKER	1,056.00	EACH
0350	20418ED	REMOVE & RELOCATE SIGNS	1.00	EACH
0360	20411ED	LAW ENFORCEMENT OFFICER	2,100.00	HOUR
0370	06591	PAVEMENT MARKER TYPE V-BY	187.00	EACH
0380	06590	PAVEMENT MARKER TYPE V-MY	966.00	EACH

## MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0390	06589	PAVEMENT MARKER TYPE V-MW	577.00	EACH
0400	06586	PAVEMENT MARKER TY IVA-MY TEMP	577.00	EACH
0410	06585	PAVEMENT MARKER TY IVA-MW TEMP	2,305.00	EACH
0420	06578	PAVE MARKING-THERMO MERGE ARROW	5.00	EACH
0430	06574	PAVE MARKING-THERMO CURV ARROW	83.00	EACH
0440	06572	PAVE MARKING-DOTTED LANE EXTEN	640.00	LF
0450	06568	PAVE MARKING-THERMO STOP BAR-24IN	287.00	LF
0460	06565	PAVE MARKING-THERMO X-WALK-6 IN	540.00	LF
0470	06551	PAVE STRIPING-TEMP REM TAPE-Y	7,000.00	LF
0480	02676	MOBILIZATION FOR MILL & TEXT - (FAYETTE COUNTY)	1.00	LS
0490	02585	EDGE KEY	776.00	LF
0500	02200	ROADWAY EXCAVATION	14,990.00	CUYD
0510	02107	BREAKING AND SEATING PAVEMENT	112,704.00	SQYD
0520	02091	REMOVE PAVEMENT	8,502.00	SQYD
0530	02058	REMOVE PCC PAVEMENT	38,513.00	SQYD
0540	00358	ASPHALT CURING SEAL	48.00	TON
0550	00342	CL4 ASPH SURF 0.38A PG76-22	10,689.00	TON
0560	00339	CL3 ASPH SURF 0.38D PG64-22	4,205.00	TON
0570	00219	CL4 ASPH BASE 1.00D PG76-22	36,276.00	TON
0580	00217	CL4 ASPH BASE 1.00D PG64-22	46,221.00	TON
0590	00214	CL3 ASPH BASE 1.00D PG64-22	58,134.00	TON
0600	00190	LEVELING & WEDGING PG64-22	2,864.00	TON
0610	00103	ASPHALT SEAL COAT	20.00	TON
0620	00100	ASPHALT SEAL AGGREGATE	167.00	TON
0630	00020	TRAFFIC BOUND BASE	128.00	TON
0640	00018	DRAINAGE BLANKET-TYPE II-ASPH	10,083.00	TON
0650	00001	DGA BASE	17,395.00	TON
0660	02677	ASPHALT PAVE MILLING & TEXTURING	15,777.00	TON
0670	02696	SHOULDER RUMBLE STRIPS-SAWED	37,593.00	LF
0680	23385EC	CONCRETE MEDIAN	1,132.00	SQYD
0690	10203ND	PAVEMENT ADJUSTMENT - (FAYETTE COUNTY); (REVISED: 12-6-12)	1.00	LS
0700	03247	REPAIR BLOWUP	200.00	SQYD
0710	02702	SAND FOR BLOTTER	127.00	TON
0720	00001	DGA BASE	16,504.00	TON
0730	00339	CL3 ASPH SURF 0.38D PG64-22	3,500.00	TON
0740	00269	MOD OPEN-GRADED DRAINAGE COURSE - (REVISED: 12-10-12)	11,844.00	TON
0750	00219	CL4 ASPH BASE 1.00D PG76-22	46.00	TON
0760	00214	CL3 ASPH BASE 1.00D PG64-22	30,679.00	TON
0770	00190	LEVELING & WEDGING PG64-22	2,301.00	TON
0780	00103	ASPHALT SEAL COAT	20.00	TON
0790	00100	ASPHALT SEAL AGGREGATE	167.00	TON
0800	00022	JPC PAVEMENT DRAINAGE BLANKET	10,366.00	TON
0810	00020	TRAFFIC BOUND BASE	28.00	TON
0820	06514	PAVE STRIPING-PERM PAINT-4 IN	113,607.00	LF
0830	00342	CL4 ASPH SURF 0.38A PG76-22	46.00	TON
0840	02079	JPC PAVEMENT-7 IN SHLD	37,643.00	SQYD
0850	02076	JPC PAVEMENT-7 IN	117,347.00	SQYD
0860	02072	JPC PAVEMENT-11 IN SHLD	8,478.00	SQYD
0870	02071	JPC PAVEMENT-11 IN	37,574.00	SQYD

## MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0880	02058	REMOVE PCC PAVEMENT	38,513.00	SQYD
0890	00358	ASPHALT CURING SEAL	40.00	TON
0900	23385EC	CONCRETE MEDIAN	1,132.00	SQYD
0910	10203ND	PAVEMENT ADJUSTMENT - (FAYETTE-CONCRETE); (REVISED: 12-6-12)	1.00	LS
0920	03247	REPAIR BLOWUP	200.00	SQYD
0930	02702	SAND FOR BLOTTER	123.00	TON
0940	02695	RUMBLE STRIPS TYPE 3	4,177.00	LF
0950	02677	ASPHALT PAVE MILLING & TEXTURING	15,777.00	TON
0960	02676	MOBILIZATION FOR MILL & TEXT - (FAYETTE COUNTY)	1.00	LS
0970	02585	EDGE KEY	776.00	LF
0980	02200	ROADWAY EXCAVATION	6,768.00	CUYD
0990	02091	REMOVE PAVEMENT	8,502.00	SQYD
1000	20366NN	REPLACE GRATE	4.00	EACH
1010	23131ER701	PIPELINE VIDEO INSPECTION	790.00	LF
1020	20166ES810	TEMPORARY PIPE	260.00	LF
1030	02600	FABRIC GEOTEXTILE TY IV FOR PIPE	1,290.00	SQYD
1040	01720	RECONSTRUCT INLET	16.00	EACH
1050	01719	ADJUST INLET	60.00	EACH
1060	01641	JUNCTION BOX-15 IN	7.00	EACH
1070	01587	DROP BOX INLET TYPE 16S	1.00	EACH
1080	01584	CAP DROP BOX INLET	1.00	EACH
1090	01581	DROP BOX INLET TYPE 16G	4.00	EACH
1100	01559	DROP BOX INLET TYPE 13G	29.00	EACH
1110	01490	DROP BOX INLET TYPE 1	1.00	EACH
1120	01432	SLOPED BOX OUTLET TYPE 1-15 IN	1.00	EACH
1130	00980	SLOTTED DRAIN PIPE-12 IN	75.00	LF
1140	00521	STORM SEWER PIPE-15 IN	836.00	LF
1150	00464	CULVERT PIPE-24 IN	8.00	LF
1160	00450	ENTRANCE PIPE-15 IN EQUIV	115.00	LF
1170	00440	ENTRANCE PIPE-15 IN	206.00	LF
1180	02397	TEMP GUARDRAIL	525.00	LF
1190	02360	GUARDRAIL TERMINAL SECTION NO 1	3.00	EACH
1200	02363	GUARDRAIL CONNECTOR TO BRIDGE END TY A	4.00	EACH
1210	02369	GUARDRAIL END TREATMENT TYPE 2A	5.00	EACH
1220	02367	GUARDRAIL END TREATMENT TYPE 1	5.00	EACH
1230	21802EN	G/R STEEL W BEAM-S FACE (7 FT POST)	6,160.00	LF
1240	02381	REMOVE GUARDRAIL	6,055.00	LF
1250	01015	INSPECT & CERTIFY EDGE DRAIN SYSTEM - (FAYETTE COUNTY)	1.00	LS
1260	01741	CORED HOLE DRAINAGE BOX CON-6 IN	88.00	EACH
1270	01029	PERF PIPE HEADWALL TY 3-6 IN	28.00	EACH
1280	01025	PERF PIPE HEADWALL TY 2-6 IN	2.00	EACH
1290	01021	PERF PIPE HEADWALL TY 1-6 IN	7.00	EACH
1300	01011	NON-PERFORATED PIPE-6 IN	1,109.00	LF
1310	01001	PERFORATED PIPE-6 IN	42,900.00	LF
1320	00078	CRUSHED AGGREGATE SIZE NO 2	37.00	TON
1330	01904	REMOVE CURB	44,017.70	LF
1340	01890	ISLAND HEADER CURB TYPE 1	170.00	LF
1350	01845	ISLAND INTEGRAL CURB	44.50	LF
1360	01820	LIP CURB AND GUTTER	43,532.10	LF

## MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
1370	01810	STANDARD CURB AND GUTTER	271.10	LF
1380	01904	REMOVE CURB	44,017.70	LF
1390	01890	ISLAND HEADER CURB TYPE 1	214.50	LF
1400	01820	LIP CURB AND GUTTER	43,532.10	LF
1410	01810	STANDARD CURB AND GUTTER	271.10	LF
1420	20391NS835	ELECTRICAL JUNCTION BOX TYPE A	2.00	EACH
1430	20360ES818	WOOD POST	4.00	EACH
1440	20359NN	GALVANIZED STEEL CABINET	2.00	EACH
1450	04895	LOOP SAW SLOT AND FILL	308.00	LF
1460	04830	LOOP WIRE	1,500.00	LF
1470	04820	TRENCHING AND BACKFILLING	60.00	LF
1480	04795	CONDUIT-2 IN	20.00	LF
1490	04793	CONDUIT-1 1/4 IN	50.00	LF
1500	02569	DEMOBILIZATION	1.00	LS
1510	02568	MOBILIZATION	1.00	LS
1520	06411	STEEL POST TYPE 2	1,428.00	LF
1530	06407	SBM ALUM SHEET SIGNS .125 IN	810.00	SQFT
1540	06406	SBM ALUM SHEET SIGNS .080 IN	264.00	SQFT
1550	04740	POLE BASE	4.00	EACH
1560	04740	POLE BASE	4.00	EACH
1570	04792	CONDUIT-1 IN - (REVISED: 12-6-12)	145.00	LF
1580	04792	CONDUIT-1 IN - (REVISED: 12-6-12)	85.00	LF
1590	04793	CONDUIT-1 1/4 IN	4,185.00	LF
1600	04793	CONDUIT-1 1/4 IN	4,185.00	LF
1610	04795	CONDUIT-2 IN - (REVISED: 12-6-12)	1,040.00	LF
1620	04795	CONDUIT-2 IN - (REVISED: 12-6-12)	1,040.00	LF
1630	04811	ELECTRICAL JUNCTION BOX TYPE B	12.00	EACH
1640	04811	ELECTRICAL JUNCTION BOX TYPE B	12.00	EACH
1650	04820	TRENCHING AND BACKFILLING - (REVISED: 12-6-12)	3,535.00	LF
1660	04820	TRENCHING AND BACKFILLING - (REVISED: 12-6-12)	3,535.00	LF
1670	04821	OPEN CUT ROADWAY	60.00	LF
1680	04821	OPEN CUT ROADWAY	60.00	LF
1690	04830	LOOP WIRE - (REVISED: 12-6-12)	1,670.00	LF
1700	04844	CABLE-NO. 14/5C - (REVISED: 12-6-12)	4,625.00	LF
1710	04844	CABLE-NO. 14/5C - (REVISED: 12-6-12)	4,625.00	LF
1720	04845	CABLE-NO. 14/7C	965.00	LF
1730	04845	CABLE-NO. 14/7C	965.00	LF
1740	04850	CABLE-NO. 14/1 PAIR - (REVISED: 12-6-12)	5,205.00	LF
1750	04850	CABLE-NO. 14/1 PAIR - (REVISED: 12-6-12)	5,205.00	LF
1760	04886	MESSENGER-15400 LB - (REVISED: 12-6-12)	220.00	LF
1770	04886	MESSENGER-15400 LB - (REVISED: 12-6-12)	220.00	LF
1780	04895	LOOP SAW SLOT AND FILL - (REVISED: 12-6-12)	575.00	LF
1790	04932	INSTALL STEEL STRAIN POLE	6.00	EACH
1800	04932	INSTALL STEEL STRAIN POLE	6.00	EACH
1810	04950	REMOVE SIGNAL EQUIPMENT	2.00	EACH
1820	04950	REMOVE SIGNAL EQUIPMENT	2.00	EACH
1830	06472	INSTALL SPAN MOUNTED SIGN	1.00	EACH
1840	06472	INSTALL SPAN MOUNTED SIGN	1.00	EACH
1850	20094ES835	TEMP RELOCATION OF SIGNAL HEAD	32.00	EACH
1860	20094ES835	TEMP RELOCATION OF SIGNAL HEAD	32.00	EACH

## MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
1870	20188NS835	INSTALL LED SIGNAL-3 SECTION	9.00	EACH
1880	20188NS835	INSTALL LED SIGNAL-3 SECTION	9.00	EACH
1890	20391NS835	ELECTRICAL JUNCTION BOX TYPE A - (REVISED: 12-6-12)	11.00	EACH
1900	20391NS835	ELECTRICAL JUNCTION BOX TYPE A - (REVISED: 12-6-12)	11.00	EACH
1910	20408ES835	INSTALL LED BEACON-12 IN	8.00	EACH
1920	20408ES835	INSTALL LED BEACON-12 IN	8.00	EACH
1930	20455NS835	VIDEO CAMERA	3.00	EACH
1940	20455NS835	VIDEO CAMERA	3.00	EACH
1950	21543EN	BORE AND JACK CONDUIT - (REVISED: 12-6-12)	470.00	LF
1960	21543EN	BORE AND JACK CONDUIT - (REVISED: 12-6-12)	470.00	LF
1970	21659NN	RELOCATE SIGNAL HEAD	1.00	EACH
1980	21659NN	RELOCATE SIGNAL HEAD	1.00	EACH
1990	22939ND	INSTALL LUMINAIRE POLE	4.00	EACH
2000	22939ND	INSTALL LUMINAIRE POLE	4.00	EACH
2010	23157EN	TRAFFIC SIGNAL POLE BASE - (REVISED: 12-6-12)	30.90	CUYD
2020	23157EN	TRAFFIC SIGNAL POLE BASE - (REVISED: 12-6-12)	30.90	CUYD
2030	23206EC	INSTALL CONTROLLER CABINET	2.00	EACH
2040	23206EC	INSTALL CONTROLLER CABINET	2.00	EACH
2050	24526ED	INSTALL-BEACON CONTROLLER-2 CIRCUIT	1.00	EACH
2060	24526ED	INSTALL-BEACON CONTROLLER-2 CIRCUIT	1.00	EACH
2070	24555ED	SIGNAL CONTROLLER	1.00	EACH
2080	24555ED	SIGNAL CONTROLLER	1.00	EACH
2090	24568ED	ELECTRONIC SIGN	2.00	EACH
2100	24568ED	ELECTRONIC SIGN	2.00	EACH
2110	04894	PREFORMED LOOP/LEAD-IN - (REVISED: 12-6-12)	390.00	LF
2120	20452ES835	PREFORMED LOOPS	240.00	LF
2130	20453ES835	PREFORMED QUADRAPOLE LOOPS	102.00	LF
2140	04740	POLE BASE	10.00	EACH
2150	04797	CONDUIT-3 IN	20.00	LF
2160	04797	CONDUIT-3 IN	20.00	LF
2170	02742	TRAINEE PAYMENT REIMBURSEMENT - 1 CLASS A OPERATOR TRAINEE	1,600.00	HOURL
2180	02742	TRAINEE PAYMENT REIMBURSEMENT - 1 TRUCK DRIVER TRAINEE	1,400.00	HOURL
2190	04885	MESSENGER-10800 LB - (REVISED: 12-6-12)	530.00	LF
2200	04885	MESSENGER-10800 LB - (REVISED: 12-6-12)	530.00	LF

**CONTRACT ID: 121380**

**121GR12D080-NH**

**DE12000601280**

LEXINGTON-VERSAILLES ROAD (US 60) PAVEMENT REHABILITATION ON US 60 FROM THE BLUEGRASS PARKWAY TO THE FAYETTE COUNTY LINE GRADE & DRAIN AND PAVEMENT ALTERNATES, A DISTANCE OF 2.03 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
2210	20391NS835	ELECTRICAL JUNCTION BOX TYPE A	2.00	EACH
2220	20360ES818	WOOD POST	4.00	EACH
2230	20359NN	GALVANIZED STEEL CABINET	2.00	EACH

## MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
2240	04895	LOOP SAW SLOT AND FILL	365.00	LF
2250	04830	LOOP WIRE	1,900.00	LF
2260	04829	PIEZOELECTRIC SENSOR	4.00	EACH
2270	04820	TRENCHING AND BACKFILLING	110.00	LF
2280	04795	CONDUIT-2 IN	50.00	LF
2290	04793	CONDUIT-1 1/4 IN	70.00	LF
2300	06551	PAVE STRIPING-TEMP REM TAPE-Y	3,000.00	LF
2310	06550	PAVE STRIPING-TEMP REM TAPE-W	3,000.00	LF
2320	06549	PAVE STRIPING-TEMP REM TAPE-B	3,000.00	LF
2330	06513	PAVE STRIPING-TEMP PAINT-12 IN	1,100.00	LF
2340	06510	PAVE STRIPING-TEMP PAINT-4 IN	151,156.00	LF
2350	06418	FLEXIBLE DELINEATOR POST-Y	45.00	EACH
2360	06417	FLEXIBLE DELINEATOR POST-W	30.00	EACH
2370	05990	SODDING	350.00	SQYD
2380	05950	EROSION CONTROL BLANKET	39,305.00	SQYD
2390	03225	TUBULAR MARKERS	386.00	EACH
2400	02775	ARROW PANEL	2.00	EACH
2410	02726	STAKING - (WOODFORD COUNTY)	1.00	LS
2420	02690	SAFELOADING	10.40	CUYD
2430	02671	PORTABLE CHANGEABLE MESSAGE SIGN	5.00	EACH
2440	02651	DIVERSIONS (BY-PASS DETOURS) - (WOODFORD COUNTY - #8)	1.00	LS
2450	02651	DIVERSIONS (BY-PASS DETOURS) - (WOODFORD COUNTY - #3)	1.00	LS
2460	02651	DIVERSIONS (BY-PASS DETOURS) - (WOODFORD COUNTY - #2)	1.00	LS
2470	02651	DIVERSIONS (BY-PASS DETOURS) - (WOODFORD COUNTY - #1)	1.00	LS
2480	02650	MAINTAIN & CONTROL TRAFFIC - (WOODFORD COUNTY)	1.00	LS
2490	02562	SIGNS	600.00	SQFT
2500	02237	DITCHING	12,838.00	LF
2510	02014	BARRICADE-TYPE III	12.00	EACH
2520	01982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	53.00	EACH
2530	06514	PAVE STRIPING-PERM PAINT-4 IN	50,064.00	LF
2540	24191ER	DURABLE WATERBORNE MARKING-12 IN W	800.00	LF
2550	24190ER	DURABLE WATERBORNE MARKING-6 IN Y	2,110.00	LF
2560	24189ER	DURABLE WATERBORNE MARKING-6 IN W	3,855.00	LF
2570	23274EN11F	TURF REINFORCEMENT MAT 1	700.00	SQYD
2580	23143ED	KPDES PERMIT AND TEMP EROSION CONTROL - (WOODFORD COUNTY)	1.00	LS
2590	22664EN	WATER BLASTING EXISTING STRIPE	76,776.00	LF
2600	20467NS112	RELOCATE TUBULAR MARKER	386.00	EACH
2610	20411ED	LAW ENFORCEMENT OFFICER	900.00	HOURL
2620	20410ED	MAINTAIN LIGHTING - (WOODFORD COUNTY)	1.00	LS
2630	06593	PAVEMENT MARKER TYPE V-B Y/R	21.00	EACH
2640	06592	PAVEMENT MARKER TYPE V-B W/R	68.00	EACH
2650	06591	PAVEMENT MARKER TYPE V-BY	70.00	EACH
2660	06590	PAVEMENT MARKER TYPE V-MY	466.00	EACH
2670	06589	PAVEMENT MARKER TYPE V-MW	268.00	EACH
2680	06586	PAVEMENT MARKER TY IVA-MY TEMP	268.00	EACH



## MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
2690	06585	PAVEMENT MARKER TY IVA-MW TEMP	1,071.00	EACH
2700	06574	PAVE MARKING-THERMO CURV ARROW	35.00	EACH
2710	06568	PAVE MARKING-THERMO STOP BAR-24IN	261.00	LF
2720	06565	PAVE MARKING-THERMO X-WALK-6 IN	230.00	LF
2730	03247	REPAIR BLOWUP	200.00	SQYD
2740	02702	SAND FOR BLOTTER	86.00	TON
2750	02696	SHOULDER RUMBLE STRIPS-SAWED	19,138.00	LF
2760	02677	ASPHALT PAVE MILLING & TEXTURING	9,708.00	TON
2770	02676	MOBILIZATION FOR MILL & TEXT - (WOODFORD COUNTY)	1.00	LS
2780	02585	EDGE KEY	586.00	LF
2790	02200	ROADWAY EXCAVATION	8,752.00	CUYD
2800	02107	BREAKING AND SEATING PAVEMENT	23,513.00	SQYD
2810	02091	REMOVE PAVEMENT	4,074.00	SQYD
2820	02058	REMOVE PCC PAVEMENT	22,529.00	SQYD
2830	00358	ASPHALT CURING SEAL	27.00	TON
2840	00342	CL4 ASPH SURF 0.38A PG76-22	6,040.00	TON
2850	00339	CL3 ASPH SURF 0.38D PG64-22	1,287.00	TON
2860	00219	CL4 ASPH BASE 1.00D PG76-22	11,103.00	TON
2870	00217	CL4 ASPH BASE 1.00D PG64-22	17,603.00	TON
2880	00214	CL3 ASPH BASE 1.00D PG64-22	19,008.00	TON
2890	00194	LEVELING & WEDGING PG76-22	168.00	TON
2900	00190	LEVELING & WEDGING PG64-22	1,355.00	TON
2910	00103	ASPHALT SEAL COAT	7.00	TON
2920	00100	ASPHALT SEAL AGGREGATE	56.00	TON
2930	00018	DRAINAGE BLANKET-TYPE II-ASPH	6,793.00	TON
2940	00001	DGA BASE	10,657.00	TON
2950	23385EC	CONCRETE MEDIAN	709.00	SQYD
2960	10203ND	PAVEMENT ADJUSTMENT - (WOODFORD COUNTY - ASPHALT)	1.00	LS
2970	00358	ASPHALT CURING SEAL	27.00	TON
2980	00342	CL4 ASPH SURF 0.38A PG76-22	2,742.00	TON
2990	00339	CL3 ASPH SURF 0.38D PG64-22	902.00	TON
3000	00269	MOD OPEN-GRADED DRAINAGE COURSE - (REVISED: 12-10-12)	2,677.00	TON
3010	00219	CL4 ASPH BASE 1.00D PG76-22	485.00	TON
3020	00217	CL4 ASPH BASE 1.00D PG64-22	1,027.00	TON
3030	00214	CL3 ASPH BASE 1.00D PG64-22	9,766.00	TON
3040	00194	LEVELING & WEDGING PG76-22	168.00	TON
3050	00190	LEVELING & WEDGING PG64-22	1,082.00	TON
3060	00103	ASPHALT SEAL COAT	7.00	TON
3070	00100	ASPHALT SEAL AGGREGATE	56.00	TON
3080	00022	JPC PAVEMENT DRAINAGE BLANKET	6,973.00	TON
3090	00001	DGA BASE	9,947.00	TON
3100	02071	JPC PAVEMENT-11 IN	22,529.00	SQYD
3110	02058	REMOVE PCC PAVEMENT	22,529.00	SQYD
3120	02076	JPC PAVEMENT-7 IN	25,522.00	SQYD
3130	02072	JPC PAVEMENT-11 IN SHLD	6,212.00	SQYD
3140	23385EC	CONCRETE MEDIAN	709.00	SQYD
3150	10203ND	PAVEMENT ADJUSTMENT - (WOODFORD COUNTY - CONCRETE)	1.00	LS

## MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
3160	03247	REPAIR BLOWUP	200.00	SQYD
3170	02702	SAND FOR BLOTTER	83.00	TON
3180	02696	SHOULDER RUMBLE STRIPS-SAWED	8,630.00	LF
3190	02695	RUMBLE STRIPS TYPE 3	1,393.00	LF
3200	02677	ASPHALT PAVE MILLING & TEXTURING	9,708.00	TON
3210	02676	MOBILIZATION FOR MILL & TEXT - (WOODFORD COUNTY)	1.00	LS
3220	02585	EDGE KEY	586.00	LF
3230	02200	ROADWAY EXCAVATION	3,975.00	CUYD
3240	02091	REMOVE PAVEMENT	4,074.00	SQYD
3250	02079	JPC PAVEMENT-7 IN SHLD	9,044.00	SQYD
3260	01015	INSPECT & CERTIFY EDGE DRAIN SYSTEM - (WOODFORD COUNTY)	1.00	LS
3270	01741	CORED HOLE DRAINAGE BOX CON-6 IN	17.00	EACH
3280	01029	PERF PIPE HEADWALL TY 3-6 IN	14.00	EACH
3290	01025	PERF PIPE HEADWALL TY 2-6 IN	1.00	EACH
3300	01021	PERF PIPE HEADWALL TY 1-6 IN	1.00	EACH
3310	01011	NON-PERFORATED PIPE-6 IN	303.00	LF
3320	01001	PERFORATED PIPE-6 IN	15,252.00	LF
3330	00078	CRUSHED AGGREGATE SIZE NO 2	16.00	TON
3340	20366NN	REPLACE GRATE	1.00	EACH
3350	23131ER701	PIPELINE VIDEO INSPECTION	51.00	LF
3360	20166ES810	TEMPORARY PIPE	143.00	LF
3370	02600	FABRIC GEOTEXTILE TY IV FOR PIPE	83.00	SQYD
3380	01720	RECONSTRUCT INLET	2.00	EACH
3390	01719	ADJUST INLET	10.00	EACH
3400	01568	DROP BOX INLET TYPE 13S	2.00	EACH
3410	01559	DROP BOX INLET TYPE 13G	12.00	EACH
3420	01493	DROP BOX INLET TYPE 2	1.00	EACH
3430	01452	S & F BOX INLET-OUTLET-30 IN	1.00	EACH
3440	01432	SLOPED BOX OUTLET TYPE 1-15 IN	1.00	EACH
3450	00521	STORM SEWER PIPE-15 IN	51.00	LF
3460	00466	CULVERT PIPE-30 IN	15.00	LF
3470	00462	CULVERT PIPE-18 IN	84.00	LF
3480	00440	ENTRANCE PIPE-15 IN	106.00	LF
3490	02360	GUARDRAIL TERMINAL SECTION NO 1	4.00	EACH
3500	02369	GUARDRAIL END TREATMENT TYPE 2A	2.00	EACH
3510	02367	GUARDRAIL END TREATMENT TYPE 1	2.00	EACH
3520	21802EN	G/R STEEL W BEAM-S FACE (7 FT POST)	2,625.00	LF
3530	02381	REMOVE GUARDRAIL	2,610.00	LF
3540	23839EC	REMOVE CONCRETE MEDIAN	68.50	SQYD
3550	01946	MOUNTABLE MEDIAN TYPE 2A	68.50	SQYD
3560	01904	REMOVE CURB	12,675.40	LF
3570	01875	STANDARD HEADER CURB	133.00	LF
3580	01820	LIP CURB AND GUTTER	12,675.40	LF
3590	23839EC	REMOVE CONCRETE MEDIAN	68.50	SQYD
3600	01946	MOUNTABLE MEDIAN TYPE 2A	6.40	SQYD
3610	01945	MOUNTABLE MEDIAN TYPE 1A	62.10	SQYD
3620	01904	REMOVE CURB	12,675.40	LF
3630	01875	STANDARD HEADER CURB	133.00	LF
3640	01820	LIP CURB AND GUTTER	12,675.40	LF

## MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
3650	02569	DEMOBILIZATION	1.00	LS
3660	02568	MOBILIZATION	1.00	LS
3670	06411	STEEL POST TYPE 2	770.00	LF
3680	06407	SBM ALUM SHEET SIGNS .125 IN	361.00	SQFT
3690	06406	SBM ALUM SHEET SIGNS .080 IN	269.00	SQFT
3700	04701	POLE 40 FT MTG HT	10.00	EACH
3710	04714	POLE 120 FT MTG HT HIGH MAST	6.00	EACH
3720	04740	POLE BASE	10.00	EACH
3730	04750	TRANSFORMER BASE	10.00	EACH
3740	04760	POLE W/SECONDARY CONTROL EQUIP	2.00	EACH
3750	04761	LIGHTING CONTROL EQUIPMENT	1.00	EACH
3760	04770	HPS LUMINAIRE	10.00	EACH
3770	04773	HPS LUMINAIRE HIGH MAST	32.00	EACH
3780	04780	FUSED CONNECTOR KIT	20.00	EACH
3790	04793	CONDUIT-1 1/4 IN	1,130.00	LF
3800	04795	CONDUIT-2 IN	190.00	LF
3810	04797	CONDUIT-3 IN	595.00	LF
3820	04800	MARKER	17.00	EACH
3830	04820	TRENCHING AND BACKFILLING	5,360.00	LF
3840	04860	CABLE-NO. 8/3C DUCTED	740.00	LF
3850	04861	CABLE-NO. 6/3C DUCTED	5,315.00	LF
3860	04940	REMOVE LIGHTING	1.00	LS
3870	20391NS835	ELECTRICAL JUNCTION BOX TYPE A	13.00	EACH
3880	21543EN	BORE AND JACK CONDUIT	785.00	LF
3890	23161EN	POLE BASE-HIGH MAST	56.00	CUYD
3900	23675EC	WIRE-NO. 12-INSTALL	1,440.00	LF
3910	24474ED	WIRE-NO.8-INSTALL	3,660.00	LF
3920	04740	POLE BASE	2.00	EACH
3930	04740	POLE BASE	2.00	EACH
3940	04792	CONDUIT-1 IN - (REVISED: 12-6-12)	90.00	LF
3950	04792	CONDUIT-1 IN - (REVISED: 12-6-12)	80.00	LF
3960	04793	CONDUIT-1 1/4 IN	2,100.00	LF
3970	04793	CONDUIT-1 1/4 IN	2,100.00	LF
3980	04795	CONDUIT-2 IN - (REVISED: 12-6-12)	80.00	LF
3990	04795	CONDUIT-2 IN - (REVISED: 12-6-12)	80.00	LF
4000	04811	ELECTRICAL JUNCTION BOX TYPE B	16.00	EACH
4010	04811	ELECTRICAL JUNCTION BOX TYPE B	16.00	EACH
4020	04820	TRENCHING AND BACKFILLING - (REVISED: 12-6-12)	2,260.00	LF
4030	04820	TRENCHING AND BACKFILLING - (REVISED: 12-6-12)	2,260.00	LF
4040	04821	OPEN CUT ROADWAY	35.00	LF
4050	04821	OPEN CUT ROADWAY	35.00	LF
4060	04830	LOOP WIRE - (REVISED: 12-6-12)	3,115.00	LF
4070	04844	CABLE-NO. 14/5C - (REVISED: 12-6-12)	6,700.00	LF
4080	04844	CABLE-NO. 14/5C - (REVISED: 12-6-12)	6,700.00	LF
4090	04850	CABLE-NO. 14/1 PAIR - (REVISED: 12-6-12)	1,535.00	LF
4100	04850	CABLE-NO. 14/1 PAIR - (REVISED: 12-6-12)	1,535.00	LF
4110	04885	MESSENGER-10800 LB - (REVISED: 12-6-12)	552.00	LF
4120	04885	MESSENGER-10800 LB - (REVISED: 12-6-12)	552.00	LF
4130	04886	MESSENGER-15400 LB - (REVISED: 12-6-12)	1,060.00	LF
4140	04886	MESSENGER-15400 LB - (REVISED: 12-6-12)	1,060.00	LF

## MATERIAL SUMMARY

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
4150	04895	LOOP SAW SLOT AND FILL - (REVISED: 12-6-12)	1,225.00	LF
4160	04931	INSTALL CONTROLLER TYPE 170	2.00	EACH
4170	04931	INSTALL CONTROLLER TYPE 170	2.00	EACH
4180	04932	INSTALL STEEL STRAIN POLE	12.00	EACH
4190	04932	INSTALL STEEL STRAIN POLE	12.00	EACH
4200	04950	REMOVE SIGNAL EQUIPMENT	2.00	EACH
4210	04950	REMOVE SIGNAL EQUIPMENT	2.00	EACH
4220	20093NS835	INSTALL PEDESTRIAN HEAD-LED	2.00	EACH
4230	20093NS835	INSTALL PEDESTRIAN HEAD-LED	2.00	EACH
4240	20094ES835	TEMP RELOCATION OF SIGNAL HEAD	24.00	EACH
4250	20094ES835	TEMP RELOCATION OF SIGNAL HEAD	24.00	EACH
4260	20188NS835	INSTALL LED SIGNAL-3 SECTION	12.00	EACH
4270	20188NS835	INSTALL LED SIGNAL-3 SECTION	12.00	EACH
4280	20266ES835	INSTALL LED SIGNAL- 4 SECTION	8.00	EACH
4290	20266ES835	INSTALL LED SIGNAL- 4 SECTION	8.00	EACH
4300	20408ES835	INSTALL LED BEACON-12 IN	8.00	EACH
4310	20408ES835	INSTALL LED BEACON-12 IN	8.00	EACH
4320	21743NN	INSTALL PEDESTRIAN DETECTOR	2.00	EACH
4330	21743NN	INSTALL PEDESTRIAN DETECTOR	2.00	EACH
4340	22939ND	INSTALL LUMINAIRE POLE	2.00	EACH
4350	22939ND	INSTALL LUMINAIRE POLE	2.00	EACH
4360	23068NN	REMOVE & REINSTALL COORDINATING UNIT	2.00	EACH
4370	23068NN	REMOVE & REINSTALL COORDINATING UNIT	2.00	EACH
4380	23157EN	TRAFFIC SIGNAL POLE BASE - (REVISED: 12-6-12)	59.10	CUYD
4390	23157EN	TRAFFIC SIGNAL POLE BASE - (REVISED: 12-6-12)	59.10	CUYD
4400	23235EC	INSTALL PEDESTAL POST	2.00	EACH
4410	23235EC	INSTALL PEDESTAL POST	2.00	EACH
4420	24525EC	ADVANCE WARNING FLASHER	2.00	EACH
4430	24525EC	ADVANCE WARNING FLASHER	2.00	EACH
4440	04894	PREFORMED LOOP/LEAD-IN - (REVISED: 12-6-12)	325.00	LF
4450	20453ES835	PREFORMED QUADRAPOLE LOOPS	918.00	LF

**PROPOSAL BID ITEMS**

Report Date 12/10/12

**Section: 0001 - PAVING (ASPHALT ALTERNATE)**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0010	00001		DGA BASE	28,052.00	TON		\$	
0020	00018		DRAINAGE BLANKET-TYPE II-ASPH	16,876.00	TON		\$	
0030	00020		TRAFFIC BOUND BASE	128.00	TON		\$	
0040	00100		ASPHALT SEAL AGGREGATE	223.00	TON		\$	
0050	00103		ASPHALT SEAL COAT	27.00	TON		\$	
0060	00190		LEVELING & WEDGING PG64-22	4,219.00	TON		\$	
0070	00194		LEVELING & WEDGING PG76-22	168.00	TON		\$	
0080	00214		CL3 ASPH BASE 1.00D PG64-22	77,142.00	TON		\$	
0090	00217		CL4 ASPH BASE 1.00D PG64-22	63,824.00	TON		\$	
0100	00219		CL4 ASPH BASE 1.00D PG76-22	47,379.00	TON		\$	
0110	00339		CL3 ASPH SURF 0.38D PG64-22	5,492.00	TON		\$	
0120	00342		CL4 ASPH SURF 0.38A PG76-22	16,729.00	TON		\$	
0130	00358		ASPHALT CURING SEAL	75.00	TON		\$	
0140	02058		REMOVE PCC PAVEMENT	61,042.00	SQYD		\$	
0150	02091		REMOVE PAVEMENT	12,576.00	SQYD		\$	
0160	02107		BREAKING AND SEATING PAVEMENT	136,217.00	SQYD		\$	
0170	02200		ROADWAY EXCAVATION	23,742.00	CUYD		\$	
0180	02585		EDGE KEY	1,362.00	LF		\$	
0190	02676		MOBILIZATION FOR MILL & TEXT(FAYETTE COUNTY)	1.00	LS		\$	
0200	02676		MOBILIZATION FOR MILL & TEXT (WOODFORD COUNTY)	1.00	LS		\$	
0210	02677		ASPHALT PAVE MILLING & TEXTURING	25,485.00	TON		\$	
0220	02696		SHOULDER RUMBLE STRIPS-SAWED	56,731.00	LF		\$	
0230	02702		SAND FOR BLOTTER	213.00	TON		\$	
0240	03247		REPAIR BLOWUP	400.00	SQYD		\$	
0250	10203ND		PAVEMENT ADJUSTMENT(FAYETTE COUNTY); (REVISED: 12-6-12)	1.00	LS	375,534.00	\$	\$1,375,534.00
0260	10203ND		PAVEMENT ADJUSTMENT(WOODFORD COUNTY - ASPHALT)	1.00	LS	639,541.00	\$	\$639,541.00
0270	23385EC		CONCRETE MEDIAN	1,841.00	SQYD		\$	

**PROPOSAL BID ITEMS**

Report Date 12/10/12

**Section: 0002 - PAVING (CONCRETE ALTERNATE)**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0640	00001		DGA BASE	26,451.00	TON		\$	
0650	00020		TRAFFIC BOUND BASE	28.00	TON		\$	
0660	00022		JPC PAVEMENT DRAINAGE BLANKET	17,339.00	TON		\$	
0670	00100		ASPHALT SEAL AGGREGATE	223.00	TON		\$	
0680	00103		ASPHALT SEAL COAT	27.00	TON		\$	
0690	00190		LEVELING & WEDGING PG64-22	3,383.00	TON		\$	
0700	00194		LEVELING & WEDGING PG76-22	168.00	TON		\$	
0710	00214		CL3 ASPH BASE 1.00D PG64-22	40,445.00	TON		\$	
0720	00217		CL4 ASPH BASE 1.00D PG64-22	1,027.00	TON		\$	
0730	00219		CL4 ASPH BASE 1.00D PG76-22	531.00	TON		\$	
0740	00269		MOD OPEN-GRADED DRAINAGE COURSE (REVISED: 12-10-12)	14,521.00	TON		\$	
0750	00339		CL3 ASPH SURF 0.38D PG64-22	4,402.00	TON		\$	
0760	00342		CL4 ASPH SURF 0.38A PG76-22	2,788.00	TON		\$	
0770	00358		ASPHALT CURING SEAL	67.00	TON		\$	
0780	02058		REMOVE PCC PAVEMENT	61,042.00	SQYD		\$	
0790	02071		JPC PAVEMENT-11 IN	60,103.00	SQYD		\$	
0800	02072		JPC PAVEMENT-11 IN SHLD	14,690.00	SQYD		\$	
0810	02076		JPC PAVEMENT-7 IN	142,869.00	SQYD		\$	
0820	02079		JPC PAVEMENT-7 IN SHLD	46,687.00	SQYD		\$	
0830	02091		REMOVE PAVEMENT	12,576.00	SQYD		\$	
0840	02200		ROADWAY EXCAVATION	10,743.00	CUYD		\$	
0850	02585		EDGE KEY	1,362.00	LF		\$	
0860	02676		MOBILIZATION FOR MILL & TEXT(FAYETTE COUNTY)	1.00	LS		\$	
0870	02676		MOBILIZATION FOR MILL & TEXT (WOODFORD COUNTY)	1.00	LS		\$	
0880	02677		ASPHALT PAVE MILLING & TEXTURING	25,485.00	TON		\$	
0890	02695		RUMBLE STRIPS TYPE 3	5,570.00	LF		\$	
0900	02696		SHOULDER RUMBLE STRIPS-SAWED	8,630.00	LF		\$	
0910	02702		SAND FOR BLOTTER	206.00	TON		\$	
0920	03247		REPAIR BLOWUP	400.00	SQYD		\$	
0930	10203ND		PAVEMENT ADJUSTMENT(FAYETTE- CONCRETE); (REVISED: 12-6-12)	1.00	LS	558,358.00	\$	558,358.00
0940	10203ND		PAVEMENT ADJUSTMENT(WOODFORD COUNTY - CONCRETE)	1.00	LS	259,603.00	\$	259,603.00
0950	23385EC		CONCRETE MEDIAN	1,841.00	SQYD		\$	

**Section: 0003 - ROADWAY**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0960	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	180.00	EACH		\$	
0970	01984		DELINEATOR FOR BARRIER - WHITE	10.00	EACH		\$	
0980	02014		BARRICADE-TYPE III	40.00	EACH		\$	
0990	02223		GRANULAR EMBANKMENT	156.00	CUYD		\$	
1000	02237		DITCHING	45,474.00	LF		\$	
1010	02469		CLEAN SINKHOLE	3.00	EACH		\$	

**PROPOSAL BID ITEMS**

Report Date 12/10/12

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1020	02562		SIGNS	2,000.00	SQFT		\$	
1030	02599		FABRIC-GEOTEXTILE TYPE IV	270.00	SQYD		\$	
1040	02650		MAINTAIN & CONTROL TRAFFIC(FAYETTE COUNTY)	1.00	LS		\$	
1050	02650		MAINTAIN & CONTROL TRAFFIC (WOODFORD COUNTY)	1.00	LS		\$	
1060	02651		DIVERSIONS (BY-PASS DETOURS)(FAYETTE COUNTY - #7)	1.00	LS		\$	
1070	02651		DIVERSIONS (BY-PASS DETOURS)(FAYETTE COUNTY - #6)	1.00	LS		\$	
1080	02651		DIVERSIONS (BY-PASS DETOURS)(FAYETTE COUNTY - #5)	1.00	LS		\$	
1090	02651		DIVERSIONS (BY-PASS DETOURS)(FAYETTE COUNTY - #4)	1.00	LS		\$	
1100	02651		DIVERSIONS (BY-PASS DETOURS) (WOODFORD COUNTY - #8)	1.00	LS		\$	
1110	02651		DIVERSIONS (BY-PASS DETOURS) (WOODFORD COUNTY - #3)	1.00	LS		\$	
1120	02651		DIVERSIONS (BY-PASS DETOURS) (WOODFORD COUNTY - #2)	1.00	LS		\$	
1130	02651		DIVERSIONS (BY-PASS DETOURS) (WOODFORD COUNTY - #1)	1.00	LS		\$	
1140	02671		PORTABLE CHANGEABLE MESSAGE SIGN	12.00	EACH		\$	
1150	02690		SAFELoading	37.50	CUYD		\$	
1160	02720		SIDEWALK-4 IN CONCRETE	37.00	SQYD		\$	
1170	02726		STAKING(FAYETTE COUNTY)	1.00	LS		\$	
1180	02726		STAKING(WOODFORD COUNTY)	1.00	LS		\$	
1190	02775		ARROW PANEL	4.00	EACH		\$	
1200	03225		TUBULAR MARKERS	1,442.00	EACH		\$	
1210	05950		EROSION CONTROL BLANKET	121,009.00	SQYD		\$	
1220	05990		SODDING	1,662.00	SQYD		\$	
1230	06417		FLEXIBLE DELINEATOR POST-W	30.00	EACH		\$	
1240	06418		FLEXIBLE DELINEATOR POST-Y	45.00	EACH		\$	
1250	06510		PAVE STRIPING-TEMP PAINT-4 IN	494,026.00	LF		\$	
1260	06513		PAVE STRIPING-TEMP PAINT-12 IN	1,100.00	LF		\$	
1270	06514		PAVE STRIPING-PERM PAINT-4 IN	163,671.00	LF		\$	
1280	06549		PAVE STRIPING-TEMP REM TAPE-B	10,000.00	LF		\$	
1290	06550		PAVE STRIPING-TEMP REM TAPE-W	10,000.00	LF		\$	
1300	06551		PAVE STRIPING-TEMP REM TAPE-Y	10,000.00	LF		\$	
1310	06565		PAVE MARKING-THERMO X-WALK-6 IN	770.00	LF		\$	
1320	06568		PAVE MARKING-THERMO STOP BAR-24IN	548.00	LF		\$	
1330	06572		PAVE MARKING-DOTTED LANE EXTEN	640.00	LF		\$	
1340	06574		PAVE MARKING-THERMO CURV ARROW	118.00	EACH		\$	
1350	06578		PAVE MARKING-THERMO MERGE ARROW	5.00	EACH		\$	
1360	06585		PAVEMENT MARKER TY IVA-MW TEMP	3,376.00	EACH		\$	
1370	06586		PAVEMENT MARKER TY IVA-MY TEMP	845.00	EACH		\$	
1380	06589		PAVEMENT MARKER TYPE V-MW	845.00	EACH		\$	
1390	06590		PAVEMENT MARKER TYPE V-MY	1,432.00	EACH		\$	
1400	06591		PAVEMENT MARKER TYPE V-BY	257.00	EACH		\$	
1410	06592		PAVEMENT MARKER TYPE V-B W/R	68.00	EACH		\$	
1420	06593		PAVEMENT MARKER TYPE V-B Y/R	21.00	EACH		\$	
1430	20410ED		MAINTAIN LIGHTING(WOODFORD COUNTY)	1.00	LS		\$	
1440	20411ED		LAW ENFORCEMENT OFFICER	3,000.00	HOURL		\$	

**PROPOSAL BID ITEMS**

Report Date 12/10/12

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1450	20418ED		REMOVE & RELOCATE SIGNS	1.00	EACH		\$	
1460	20467NS112		RELOCATE TUBULAR MARKER	1,442.00	EACH		\$	
1470	22664EN		WATER BLASTING EXISTING STRIPE	289,590.00	LF		\$	
1480	23143ED		KPDES PERMIT AND TEMP EROSION CONTROL(FAYETTE COUNTY)	1.00	LS		\$	
1490	23143ED		KPDES PERMIT AND TEMP EROSION CONTROL(WOODFORD COUNTY)	1.00	LS		\$	
1500	23274EN11F		TURF REINFORCEMENT MAT 1	2,233.00	SQYD		\$	
1510	24189ER		DURABLE WATERBORNE MARKING-6 IN W	3,855.00	LF		\$	
1520	24190ER		DURABLE WATERBORNE MARKING-6 IN Y	2,110.00	LF		\$	
1530	24191ER		DURABLE WATERBORNE MARKING-12 IN W	800.00	LF		\$	



**PROPOSAL BID ITEMS**

Report Date 12/10/12

**Section: 0004 - DRAINAGE**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1540	00078		CRUSHED AGGREGATE SIZE NO 2	53.00	TON		\$	
1550	00440		ENTRANCE PIPE-15 IN	312.00	LF		\$	
1560	00450		ENTRANCE PIPE-15 IN EQUIV	115.00	LF		\$	
1570	00462		CULVERT PIPE-18 IN	84.00	LF		\$	
1580	00464		CULVERT PIPE-24 IN	8.00	LF		\$	
1590	00466		CULVERT PIPE-30 IN	15.00	LF		\$	
1600	00521		STORM SEWER PIPE-15 IN	887.00	LF		\$	
1610	00980		SLOTTED DRAIN PIPE-12 IN	75.00	LF		\$	
1620	01001		PERFORATED PIPE-6 IN	58,152.00	LF		\$	
1630	01011		NON-PERFORATED PIPE-6 IN	1,412.00	LF		\$	
1640	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM (FAYETTE COUNTY)	1.00	LS		\$	
1650	01015		INSPECT & CERTIFY EDGE DRAIN SYSTEM (WOODFORD COUNTY)	1.00	LS		\$	
1660	01021		PERF PIPE HEADWALL TY 1-6 IN	8.00	EACH		\$	
1670	01025		PERF PIPE HEADWALL TY 2-6 IN	3.00	EACH		\$	
1680	01029		PERF PIPE HEADWALL TY 3-6 IN	42.00	EACH		\$	
1690	01432		SLOPED BOX OUTLET TYPE 1-15 IN	2.00	EACH		\$	
1700	01452		S & F BOX INLET-OUTLET-30 IN	1.00	EACH		\$	
1710	01490		DROP BOX INLET TYPE 1	1.00	EACH		\$	
1720	01493		DROP BOX INLET TYPE 2	1.00	EACH		\$	
1730	01559		DROP BOX INLET TYPE 13G	41.00	EACH		\$	
1740	01568		DROP BOX INLET TYPE 13S	2.00	EACH		\$	
1750	01581		DROP BOX INLET TYPE 16G	4.00	EACH		\$	
1760	01584		CAP DROP BOX INLET	1.00	EACH		\$	
1770	01587		DROP BOX INLET TYPE 16S	1.00	EACH		\$	
1780	01641		JUNCTION BOX-15 IN	7.00	EACH		\$	
1790	01719		ADJUST INLET	70.00	EACH		\$	
1800	01720		RECONSTRUCT INLET	18.00	EACH		\$	
1810	01741		CORED HOLE DRAINAGE BOX CON-6 IN	105.00	EACH		\$	
1820	02600		FABRIC GEOTEXTILE TY IV FOR PIPE	1,373.00	SQYD	\$2.00	\$	\$2,746.00
1830	20166ES810		TEMPORARY PIPE	403.00	LF		\$	
1840	20366NN		REPLACE GRATE	5.00	EACH		\$	
1850	23131ER701		PIPELINE VIDEO INSPECTION	841.00	LF		\$	

**Section: 0005 - BRIDGE**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1860	02403		REMOVE CONCRETE MASONRY	23.90	CUYD		\$	
1870	02555		CONCRETE-CLASS B	34.50	CUYD		\$	
1880	02998		MASONRY COATING	200.00	SQYD		\$	
1890	08001		STRUCTURE EXCAVATION-COMMON	57.50	CUYD		\$	
1900	08104		CONCRETE-CLASS AA	34.60	CUYD		\$	
1910	08151		STEEL REINFORCEMENT-EPOXY COATED	5,755.00	LB		\$	

# PROPOSAL BID ITEMS

Report Date 12/10/12

## Section: 0006 - SIGNING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1920	06406		SBM ALUM SHEET SIGNS .080 IN	533.00	SQFT		\$	
1930	06407		SBM ALUM SHEET SIGNS .125 IN	1,171.00	SQFT		\$	
1940	06411		STEEL POST TYPE 2	2,198.00	LF		\$	

**PROPOSAL BID ITEMS**

Report Date 12/10/12

**Section: 0007 - SIGNALIZATION (ASPHALT ALTERNATE)**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
1950	04740		POLE BASE	6.00	EACH		\$	
1960	04792		CONDUIT-1 IN(REVISED: 12-6-12)	165.00	LF		\$	
1970	04793		CONDUIT-1 1/4 IN	6,285.00	LF		\$	
1980	04795		CONDUIT-2 IN(REVISED: 12-6-12)	1,120.00	LF		\$	
1990	04797		CONDUIT-3 IN	20.00	LF		\$	
2000	04811		ELECTRICAL JUNCTION BOX TYPE B	28.00	EACH		\$	
2010	04820		TRENCHING AND BACKFILLING(REVISED: 12-6-12)	5,795.00	LF		\$	
2020	04821		OPEN CUT ROADWAY	95.00	LF		\$	
2030	04830		LOOP WIRE(REVISED: 12-6-12)	4,785.00	LF		\$	
2040	04844		CABLE-NO. 14/5C(REVISED: 12-6-12)	11,325.00	LF		\$	
2050	04845		CABLE-NO. 14/7C	965.00	LF		\$	
2060	04850		CABLE-NO. 14/1 PAIR(REVISED: 12-6-12)	6,740.00	LF		\$	
2070	04885		MESSENGER-10800 LB(REVISED: 12-6-12)	1,082.00	LF		\$	
2080	04886		MESSENGER-15400 LB(REVISED: 12-6-12)	1,280.00	LF		\$	
2090	04895		LOOP SAW SLOT AND FILL(REVISED: 12-6-12)	1,800.00	LF		\$	
2100	04931		INSTALL CONTROLLER TYPE 170	2.00	EACH		\$	
2110	04932		INSTALL STEEL STRAIN POLE	18.00	EACH		\$	
2120	04950		REMOVE SIGNAL EQUIPMENT	4.00	EACH		\$	
2130	06472		INSTALL SPAN MOUNTED SIGN	1.00	EACH		\$	
2140	20093NS835		INSTALL PEDESTRIAN HEAD-LED	2.00	EACH		\$	
2150	20094ES835		TEMP RELOCATION OF SIGNAL HEAD	56.00	EACH		\$	
2160	20188NS835		INSTALL LED SIGNAL-3 SECTION	21.00	EACH		\$	
2170	20266ES835		INSTALL LED SIGNAL- 4 SECTION	8.00	EACH		\$	
2180	20391NS835		ELECTRICAL JUNCTION BOX TYPE A (REVISED: 12-6-12)	11.00	EACH		\$	
2190	20408ES835		INSTALL LED BEACON-12 IN	16.00	EACH		\$	
2200	20455NS835		VIDEO CAMERA	3.00	EACH		\$	
2210	21543EN		BORE AND JACK CONDUIT(REVISED: 12-6-12)	470.00	LF		\$	
2220	21659NN		RELOCATE SIGNAL HEAD	1.00	EACH		\$	
2230	21743NN		INSTALL PEDESTRIAN DETECTOR	2.00	EACH		\$	
2240	22939ND		INSTALL LUMINAIRE POLE	6.00	EACH		\$	
2250	23068NN		REMOVE & REINSTALL COORDINATING UNIT	2.00	EACH		\$	
2260	23157EN		TRAFFIC SIGNAL POLE BASE(REVISED: 12-6-12)	90.00	CUYD		\$	
2270	23206EC		INSTALL CONTROLLER CABINET	2.00	EACH		\$	
2280	23235EC		INSTALL PEDESTAL POST	2.00	EACH		\$	
2290	24525EC		ADVANCE WARNING FLASHER	2.00	EACH		\$	
2300	24526ED		INSTALL-BEACON CONTROLLER-2 CIRCUIT	1.00	EACH		\$	
2310	24555ED		SIGNAL CONTROLLER	1.00	EACH		\$	
2320	24568ED		ELECTRONIC SIGN	2.00	EACH		\$	

**PROPOSAL BID ITEMS**

Report Date 12/10/12

**Section: 0008 - SIGNALIZATION (CONCRETE ALTERNATE)**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
2330	04740		POLE BASE	6.00	EACH		\$	
2340	04792		CONDUIT-1 IN(REVISED: 12-6-12)	235.00	LF		\$	
2350	04793		CONDUIT-1 1/4 IN	6,285.00	LF		\$	
2360	04795		CONDUIT-2 IN(REVISED: 12-6-12)	1,120.00	LF		\$	
2370	04797		CONDUIT-3 IN	20.00	LF		\$	
2380	04811		ELECTRICAL JUNCTION BOX TYPE B	28.00	EACH		\$	
2390	04820		TRENCHING AND BACKFILLING(REVISED: 12-6-12)	5,795.00	LF		\$	
2400	04821		OPEN CUT ROADWAY	95.00	LF		\$	
2410	04844		CABLE-NO. 14/5C(REVISED: 12-6-12)	11,325.00	LF		\$	
2420	04845		CABLE-NO. 14/7C	965.00	LF		\$	
2430	04850		CABLE-NO. 14/1 PAIR(REVISED: 12-6-12)	6,740.00	LF		\$	
2440	04885		MESSENGER-10800 LB(REVISED: 12-6-12)	1,082.00	LF		\$	
2450	04886		MESSENGER-15400 LB(REVISED: 12-6-12)	1,280.00	LF		\$	
2460	04894		PREFORMED LOOP/LEAD-IN(REVISED: 12-6-12)	715.00	LF		\$	
2470	04931		INSTALL CONTROLLER TYPE 170	2.00	EACH		\$	
2480	04932		INSTALL STEEL STRAIN POLE	18.00	EACH		\$	
2490	04950		REMOVE SIGNAL EQUIPMENT	4.00	EACH		\$	
2500	06472		INSTALL SPAN MOUNTED SIGN	1.00	EACH		\$	
2510	20093NS835		INSTALL PEDESTRIAN HEAD-LED	2.00	EACH		\$	
2520	20094ES835		TEMP RELOCATION OF SIGNAL HEAD	56.00	EACH		\$	
2530	20188NS835		INSTALL LED SIGNAL-3 SECTION	21.00	EACH		\$	
2540	20266ES835		INSTALL LED SIGNAL- 4 SECTION	8.00	EACH		\$	
2550	20391NS835		ELECTRICAL JUNCTION BOX TYPE A (REVISED: 12-6-12)	11.00	EACH		\$	
2560	20408ES835		INSTALL LED BEACON-12 IN	16.00	EACH		\$	
2570	20452ES835		PREFORMED LOOPS	240.00	LF		\$	
2580	20453ES835		PREFORMED QUADRAPOLE LOOPS	1,020.00	LF		\$	
2590	20455NS835		VIDEO CAMERA	3.00	EACH		\$	
2600	21543EN		BORE AND JACK CONDUIT(REVISED: 12-6-12)	470.00	LF		\$	
2610	21659NN		RELOCATE SIGNAL HEAD	1.00	EACH		\$	
2620	21743NN		INSTALL PEDESTRIAN DETECTOR	2.00	EACH		\$	
2630	22939ND		INSTALL LUMINAIRE POLE	6.00	EACH		\$	
2640	23068NN		REMOVE & REINSTALL COORDINATING UNIT	2.00	EACH		\$	
2650	23157EN		TRAFFIC SIGNAL POLE BASE(REVISED: 12-6-12)	90.00	CUYD		\$	
2660	23206EC		INSTALL CONTROLLER CABINET	2.00	EACH		\$	
2670	23235EC		INSTALL PEDESTAL POST	2.00	EACH		\$	
2680	24525EC		ADVANCE WARNING FLASHER	2.00	EACH		\$	
2690	24526ED		INSTALL-BEACON CONTROLLER-2 CIRCUIT	1.00	EACH		\$	
2700	24555ED		SIGNAL CONTROLLER	1.00	EACH		\$	
2710	24568ED		ELECTRONIC SIGN	2.00	EACH		\$	

**PROPOSAL BID ITEMS**

Report Date 12/10/12

**Section: 0009 - LIGHTING**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
2720	04701		POLE 40 FT MTG HT	10.00	EACH		\$	
2730	04714		POLE 120 FT MTG HT HIGH MAST	6.00	EACH		\$	
2740	04740		POLE BASE	20.00	EACH		\$	
2750	04750		TRANSFORMER BASE	10.00	EACH		\$	
2760	04760		POLE W/SECONDARY CONTROL EQUIP	2.00	EACH		\$	
2770	04761		LIGHTING CONTROL EQUIPMENT	1.00	EACH		\$	
2780	04770		HPS LUMINAIRE	10.00	EACH		\$	
2790	04773		HPS LUMINAIRE HIGH MAST	32.00	EACH		\$	
2800	04780		FUSED CONNECTOR KIT	20.00	EACH		\$	
2810	04793		CONDUIT-1 1/4 IN	1,130.00	LF		\$	
2820	04795		CONDUIT-2 IN	190.00	LF		\$	
2830	04797		CONDUIT-3 IN	595.00	LF		\$	
2840	04800		MARKER	17.00	EACH		\$	
2850	04820		TRENCHING AND BACKFILLING	5,360.00	LF		\$	
2860	04860		CABLE-NO. 8/3C DUCTED	740.00	LF		\$	
2870	04861		CABLE-NO. 6/3C DUCTED	5,315.00	LF		\$	
2880	04940		REMOVE LIGHTING	1.00	LS		\$	
2890	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	13.00	EACH		\$	
2900	21543EN		BORE AND JACK CONDUIT	785.00	LF		\$	
2910	23161EN		POLE BASE-HIGH MAST	56.00	CUYD		\$	
2920	23675EC		WIRE-NO. 12-INSTALL	1,440.00	LF		\$	
2930	24474ED		WIRE-NO.8-INSTALL	3,660.00	LF		\$	

**Section: 0010 - TRAFFIC LOOPS**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0280	04793		CONDUIT-1 1/4 IN	120.00	LF		\$	
0290	04795		CONDUIT-2 IN	70.00	LF		\$	
0300	04820		TRENCHING AND BACKFILLING	170.00	LF		\$	
0310	04829		PIEZOELECTRIC SENSOR	4.00	EACH		\$	
0320	04830		LOOP WIRE	3,400.00	LF		\$	
0330	04895		LOOP SAW SLOT AND FILL	673.00	LF		\$	
0340	20359NN		GALVANIZED STEEL CABINET	4.00	EACH		\$	
0350	20360ES818		WOOD POST	8.00	EACH		\$	
0360	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	4.00	EACH		\$	

**PROPOSAL BID ITEMS**

Report Date 12/10/12

**Section: 0011 - GUARDRAIL**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0370	02360		GUARDRAIL TERMINAL SECTION NO 1	7.00	EACH		\$	
0380	02363		GUARDRAIL CONNECTOR TO BRIDGE END TY A	4.00	EACH		\$	
0390	02367		GUARDRAIL END TREATMENT TYPE 1	7.00	EACH		\$	
0400	02369		GUARDRAIL END TREATMENT TYPE 2A	7.00	EACH		\$	
0410	02381		REMOVE GUARDRAIL	8,665.00	LF		\$	
0420	02397		TEMP GUARDRAIL	525.00	LF		\$	
0430	21802EN		G/R STEEL W BEAM-S FACE (7 FT POST)	8,785.00	LF		\$	

**Section: 0012 - CURB (ASPHALT ALTERNATE)**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0440	01810		STANDARD CURB AND GUTTER	271.10	LF		\$	
0450	01820		LIP CURB AND GUTTER	56,207.50	LF		\$	
0460	01875		STANDARD HEADER CURB	133.00	LF		\$	
0470	01890		ISLAND HEADER CURB TYPE 1	214.50	LF		\$	
0480	01904		REMOVE CURB	56,693.10	LF		\$	
0490	01945		MOUNTABLE MEDIAN TYPE 1A	62.10	SQYD		\$	
0500	01946		MOUNTABLE MEDIAN TYPE 2A	6.40	SQYD		\$	
0510	23839EC		REMOVE CONCRETE MEDIAN	68.50	SQYD		\$	

**Section: 0013 - CURB (CONCRETE ALTERNATE)**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0520	01810		STANDARD CURB AND GUTTER	271.10	LF		\$	
0530	01820		LIP CURB AND GUTTER	56,207.50	LF		\$	
0540	01845		ISLAND INTEGRAL CURB	44.50	LF		\$	
0550	01875		STANDARD HEADER CURB	133.00	LF		\$	
0560	01890		ISLAND HEADER CURB TYPE 1	170.00	LF		\$	
0570	01904		REMOVE CURB	56,693.10	LF		\$	
0580	01946		MOUNTABLE MEDIAN TYPE 2A	68.50	SQYD		\$	
0590	23839EC		REMOVE CONCRETE MEDIAN	68.50	SQYD		\$	

**Section: 0014 - TRAINEES**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0600	02742		TRAINEE PAYMENT REIMBURSEMENT1 CLASS A OPERATOR TRAINEE	1,600.00	HOURL		\$	
0610	02742		TRAINEE PAYMENT REIMBURSEMENT1 TRUCK DRIVER TRAINEE	1,400.00	HOURL		\$	

# PROPOSAL BID ITEMS

Report Date 12/10/12

## Section: 0015 - MOBILIZATION / DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0620	02568		MOBILIZATION	1.00	LS		\$	
0630	02569		DEMOBILIZATION	1.00	LS		\$	