



COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET  
[www.transportation.ky.gov/](http://www.transportation.ky.gov/)

Andy Beshear  
GOVERNOR

Jim Gray  
SECRETARY

October 7, 2020

CALL NO. 208  
CONTRACT ID NO. 202171  
ADDENDUM # 2

**Subject:** FRANKLIN COUNTY, 037GR20P021 - NHPP & STP  
Letting October 9, 2020

- (1) Revised - Material Summary - Pages 84-86 of 139
- (2) Revised - Traffic Loop Summary - Page 92 of 139
- (3) Revised - Proposal Bid Items - Pages 138-139 of 139

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

# MATERIAL SUMMARY

**CONTRACT ID: 202171**

**037GR20P021 - NHPP & STP**

**MP03701272002**

WEST PLAZA CONNECTOR ROAD (US 127) BEGINNING 0.128 MILES NORTH OF US 60 EXTENDING NORTH TO THE SOUTH END OF THE BRIDGE OVER KY 3505. ASPHALT RESURFACING, A DISTANCE OF .87 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0060	00190	LEVELING & WEDGING PG64-22	114.00	TON
0065	00301	CL2 ASPH SURF 0.38D PG64-22	400.00	TON
0070	00307	CL2 ASPH SURF 0.38B PG64-22	2,075.00	TON
0075	00356	ASPHALT MATERIAL FOR TACK	15.00	TON
0080	02562	TEMPORARY SIGNS	290.00	SQFT
0085	02650	MAINTAIN & CONTROL TRAFFIC - (US 127)	1.00	LS
0090	02676	MOBILIZATION FOR MILL & TEXT - (US 127)	1.00	LS
0095	02677	ASPHALT PAVE MILLING & TEXTURING	2,510.00	TON
0100	02720	SIDEWALK-4 IN CONCRETE	65.00	SQYD
0105	02775	ARROW PANEL	1.00	EACH
0110	04811	ELECTRICAL JUNCTION BOX TYPE B - (REVISED: 10-7-20)	8.00	EACH
0115	04820	TRENCHING AND BACKFILLING - (REVISED: 10-7-20)	230.00	LF
0120	04830	LOOP WIRE - (REVISED: 10-7-20)	5,550.00	LF
0125	04850	CABLE-NO. 14/1 PAIR - (REVISED: 10-7-20)	3,380.00	LF
0130	04895	LOOP SAW SLOT AND FILL - (REVISED: 10-7-20)	2,745.00	LF
0135	06510	PAVE STRIPING-TEMP PAINT-4 IN	20,700.00	LF
0140	06542	PAVE STRIPING-THERMO-6 IN W	12,500.00	LF
0145	06543	PAVE STRIPING-THERMO-6 IN Y	9,275.00	LF
0150	06547	PAVE STRIPING-THERMO-12 IN Y	160.00	LF
0155	06565	PAVE MARKING-THERMO X-WALK-6 IN	1,180.00	LF
0160	06568	PAVE MARKING-THERMO STOP BAR-24IN	220.00	LF
0165	06574	PAVE MARKING-THERMO CURV ARROW	18.00	EACH
0170	06575	PAVE MARKING-THERMO COMB ARROW	2.00	EACH
0175	20071EC	JOINT ADHESIVE	10,000.00	LF
0180	23158ES505	DETECTABLE WARNINGS - (NEW)	40.00	SQFT
0185	24880EC	REMOVE PAVEMENT MARKER	120.00	EACH
0190	02569	DEMOBILIZATION	1.00	LS
0195	24123EC	PVC CONDUIT-1 1/4 IN-SCHEDULE 40 - (ADDED: 10-7-20)	230.00	LF
0200	04792	CONDUIT-1 IN - (ADDED: 10-7-20)	80.00	LF
0205	24963ED	LOOP TEST - (ADDED: 10-7-20)	17.00	EACH

# MATERIAL SUMMARY

**CONTRACT ID: 202171**

**037GR20P021 - NHPP & STP**

**MP03722612001**

HOLMES STREET (KY 2261) BEGINNING AT MEAGHER AVENUE EXTENDING NORTH TO US 127. ASPHALT RESURFACING, A DISTANCE OF 1.03 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0210	00190	LEVELING & WEDGING PG64-22	112.00	TON
0215	00301	CL2 ASPH SURF 0.38D PG64-22	790.00	TON
0220	00307	CL2 ASPH SURF 0.38B PG64-22	1,360.00	TON
0225	01792	ADJUST MANHOLE	8.00	EACH
0230	01987	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	15.00	EACH
0235	02351	GUARDRAIL-STEEL W BEAM-S FACE	750.00	LF
0240	02360	GUARDRAIL TERMINAL SECTION NO 1	2.00	EACH
0245	02367	GUARDRAIL END TREATMENT TYPE 1	3.00	EACH
0250	02369	GUARDRAIL END TREATMENT TYPE 2A	1.00	EACH
0255	02381	REMOVE GUARDRAIL	687.50	LF
0260	02396	REMOVE GUARDRAIL END TREATMENT	4.00	EACH
0265	02562	TEMPORARY SIGNS	510.00	SQFT
0270	02650	MAINTAIN & CONTROL TRAFFIC - (KY 2261)	1.00	LS
0275	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0280	02676	MOBILIZATION FOR MILL & TEXT - (KY 2261)	1.00	LS
0285	02677	ASPHALT PAVE MILLING & TEXTURING	2,150.00	TON
0290	06510	PAVE STRIPING-TEMP PAINT-4 IN	24,276.00	LF
0295	06514	PAVE STRIPING-PERM PAINT-4 IN	24,276.00	LF
0300	06547	PAVE STRIPING-THERMO-12 IN Y	70.00	LF
0305	06568	PAVE MARKING-THERMO STOP BAR-24IN	40.00	LF
0310	06569	PAVE MARKING-THERMO CROSS-HATCH	175.00	SQFT
0315	06574	PAVE MARKING-THERMO CURV ARROW	12.00	EACH
0320	08805	GUARDRAIL-BRIDGE CASE I	50.00	LF
0325	23607EC	PAVE MARK THERMO-LANE REDUCTION ARROW	3.00	EACH
0330	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	9.00	TON
0335	02569	DEMOBILIZATION	1.00	LS

# MATERIAL SUMMARY

**CONTRACT ID: 202171**

**037GR20P021 - NHPP & STP**

**MP03735052001**

DEVILS HOLLOW ROAD (KY 3505) BEGINNING AT KY 1005 EXTENDING EAST TO PARKSIDE DRIVE. ASPHALT RESURFACING, A DISTANCE OF .17 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00190	LEVELING & WEDGING PG64-22	13.00	TON
0010	00301	CL2 ASPH SURF 0.38D PG64-22	220.00	TON
0015	00356	ASPHALT MATERIAL FOR TACK	2.00	TON
0020	02562	TEMPORARY SIGNS	270.00	SQFT
0025	02650	MAINTAIN & CONTROL TRAFFIC - (KY 3505)	1.00	LS
0030	02676	MOBILIZATION FOR MILL & TEXT - (KY 3505)	1.00	LS
0035	02677	ASPHALT PAVE MILLING & TEXTURING	220.00	TON
0040	06510	PAVE STRIPING-TEMP PAINT-4 IN	3,200.00	LF
0045	06514	PAVE STRIPING-PERM PAINT-4 IN	3,200.00	LF
0050	06568	PAVE MARKING-THERMO STOP BAR-24IN	12.00	LF
0055	02569	DEMOBILIZATION	1.00	LS

**FRANKLIN COUNTY  
TRAFFIC LOOP SUMMARY  
FD05-037-0127-006-008**

US 127

INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT 1 INCH LF		CONDUIT 1 1/4 INCH LF		CONDUIT 2 INCH LF		CABLE NO. 14 LF	JUNCTION TYPE B EA	CONDUIT ROADWAY LF		REMOVE AND REPLACE SIDEWALK SQ YD	Trenching and Backfilling LF	Loop Test EA	NOTES
			LF	EA	LF	EA	LF	EA								
MINUTEMAN																
127 SOUTH	505	990	10	30	0	705	1	0	0	0	0	0	0	30	3	3 6X30 STOP BAR LOOPS
127 NORTH	505	990	10	30	0	660	1	0	0	0	0	0	0	30	3	3 6X30 STOP BAR LOOPS
MINUTEMAN	245	600	10	30	0	650	1	0	0	0	0	0	0	30	2	2 6X30 STOP BAR LOOPS
PARKSIDE DR	165	330	10	20	0	40	1	0	0	0	0	0	0	20	1	6X30 STOP BAR LOOP
<b>Total</b>	<b>1420</b>	<b>2910</b>	<b>40</b>	<b>110</b>	<b>0</b>	<b>2055</b>	<b>4</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>110</b>	<b>9</b>	

INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT 1 INCH LF		CONDUIT 1 1/4 INCH LF		CONDUIT 2 INCH LF		CABLE NO. 14 LF	JUNCTION TYPE B EA	CONDUIT ROADWAY LF		REMOVE AND REPLACE SIDEWALK SQ YD	Trenching and Backfilling LF	Loop Test EA	NOTES
			LF	EA	LF	EA	LF	EA								
HOLLY HILL																
127 SOUTH	505	990	10	30	0	900	1	0	0	0	0	0	0	30	3	3 6X30 STOP BAR LOOPS
127 NORTH	505	990	10	30	0	150	1	0	0	0	0	0	0	30	3	3 6X30 STOP BAR LOOPS
HOLLY HILL	150	330	10	30	0	225	1	0	0	0	0	0	0	30	1	6X30 STOP BAR LOOP
PARKSIDE DR	165	330	10	30	0	50	1	0	0	0	0	0	0	30	1	6X30 STOP BAR LOOP
<b>Total</b>	<b>1325</b>	<b>2640</b>	<b>40</b>	<b>120</b>	<b>0</b>	<b>1325</b>	<b>4</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>120</b>	<b>8</b>	
<b>Grand Total</b>	<b>2745</b>	<b>5550</b>	<b>80</b>	<b>230</b>	<b>0</b>	<b>3380</b>	<b>8</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>230</b>	<b>17</b>	

- Quantities are for estimating purposes only. The Contractor shall field measure and inspect items to verify quantities.
- 2 - 1/4 inch conduits may be used in place of 2" conduit. Field verify conduit to match existing facilities/te-in to poles/cabinets. specifications. Only replace existing conduit if damaged.

**PROPOSAL BID ITEMS**

Report Date 10/7/20

**Section: 0001 - PAVING**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	239.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	1,410.00	TON		\$	
0030	00307		CL2 ASPH SURF 0.38B PG64-22	3,435.00	TON		\$	
0040	00356		ASPHALT MATERIAL FOR TACK	17.00	TON		\$	
0050	01792		ADJUST MANHOLE	8.00	EACH		\$	
0060	01987		DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	15.00	EACH		\$	
0070	02351		GUARDRAIL-STEEL W BEAM-S FACE	750.00	LF		\$	
0080	02360		GUARDRAIL TERMINAL SECTION NO 1	2.00	EACH		\$	
0090	02367		GUARDRAIL END TREATMENT TYPE 1	3.00	EACH		\$	
0100	02369		GUARDRAIL END TREATMENT TYPE 2A	1.00	EACH		\$	
0110	02381		REMOVE GUARDRAIL	687.50	LF		\$	
0120	02396		REMOVE GUARDRAIL END TREATMENT	4.00	EACH		\$	
0130	02562		TEMPORARY SIGNS	1,070.00	SQFT		\$	
0140	02650		MAINTAIN & CONTROL TRAFFIC (KY 2261)	1.00	LS		\$	
0150	02650		MAINTAIN & CONTROL TRAFFIC (KY 3505)	1.00	LS		\$	
0160	02650		MAINTAIN & CONTROL TRAFFIC (US 127)	1.00	LS		\$	
0170	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0180	02676		MOBILIZATION FOR MILL & TEXT (KY 2261)	1.00	LS		\$	
0190	02676		MOBILIZATION FOR MILL & TEXT (KY 3505)	1.00	LS		\$	
0200	02676		MOBILIZATION FOR MILL & TEXT (US 127)	1.00	LS		\$	
0210	02677		ASPHALT PAVE MILLING & TEXTURING	4,880.00	TON		\$	
0220	02720		SIDEWALK-4 IN CONCRETE	65.00	SQYD		\$	
0230	02775		ARROW PANEL	1.00	EACH		\$	
0238	04792		CONDUIT-1 IN (ADDED: 10-7-20)	80.00	LF		\$	
0250	04811		ELECTRICAL JUNCTION BOX TYPE B (REVISED: 10-7-20)	8.00	EACH		\$	
0260	04820		TRENCHING AND BACKFILLING (REVISED: 10-7-20)	230.00	LF		\$	
0270	04830		LOOP WIRE (REVISED: 10-7-20)	5,550.00	LF		\$	
0280	04850		CABLE-NO. 14/1 PAIR (REVISED: 10-7-20)	3,380.00	LF		\$	
0290	04895		LOOP SAW SLOT AND FILL (REVISED: 10-7-20)	2,745.00	LF		\$	
0300	06510		PAVE STRIPING-TEMP PAINT-4 IN	48,176.00	LF		\$	
0310	06514		PAVE STRIPING-PERM PAINT-4 IN	27,476.00	LF		\$	
0320	06542		PAVE STRIPING-THERMO-6 IN W	12,500.00	LF		\$	
0330	06543		PAVE STRIPING-THERMO-6 IN Y	9,275.00	LF		\$	
0340	06547		PAVE STRIPING-THERMO-12 IN Y	230.00	LF		\$	
0350	06565		PAVE MARKING-THERMO X-WALK-6 IN	1,180.00	LF		\$	
0360	06568		PAVE MARKING-THERMO STOP BAR-24IN	272.00	LF		\$	
0370	06569		PAVE MARKING-THERMO CROSS-HATCH	175.00	SQFT		\$	

**PROPOSAL BID ITEMS**

Report Date 10/7/20

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0380	06574		PAVE MARKING-THERMO CURV ARROW	30.00	EACH		\$	
0390	06575		PAVE MARKING-THERMO COMB ARROW	2.00	EACH		\$	
0400	08805		GUARDRAIL-BRIDGE CASE I	50.00	LF		\$	
0410	20071EC		JOINT ADHESIVE	10,000.00	LF		\$	
0420	23158ES505		DETECTABLE WARNINGS (NEW)	40.00	SQFT		\$	
0430	23607EC		PAVE MARK THERMO-LANE REDUCTION ARROW	3.00	EACH		\$	
0435	24123EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 40 (ADDED: 10-7-20)	230.00	LF		\$	
0440	24880EC		REMOVE PAVEMENT MARKER	120.00	EACH		\$	
0445	24963ED		LOOP TEST (ADDED: 10-7-20)	17.00	EACH		\$	
0450	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING	9.00	TON		\$	

**Section: 0002 - DEMOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0460	02569		DEMOBILIZATION	1.00	LS		\$	