



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Secretary

May 14, 2012

CALL NO. 301  
CONTRACT ID NO. 121319  
ADDENDUM # 1

Subject: Rockcastle County, JL04 102 1249 000-016  
Letting May 18, 2012

(1) Revised - Special Notes - Page 12 of 76

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith  
Director  
Division of Construction Procurement

RG:ks  
Enclosures



An Equal Opportunity Employer M/F/D

**SPECIAL NOTES FOR GUARDRAIL AND CRIBBING**  
**KY 1249**  
**ROCKCASTLE COUNTY**

**I. DESCRIPTION**

Except as specified herein, perform all work in accordance with the Department's Standard and Supplemental Specifications and Standard and Sepia Drawings, 2008 edition. Article references are to the Standard Specifications.

Furnish all equipment, labor, materials, and incidentals for the following work items:

(1) Site preparation; (2) Guardrail, Guardrail with Extra Length Posts, End Treatments, and Terminal Sections, as applicable; (3) Wall Cribbing and Backfill; (4) Delineators for Guardrail; (5) Maintain and Control Traffic; and (6) all other work specified as part of this contract.

**II. MATERIALS**

Except as specified herein, provide for all materials to be sampled and tested in accordance with the Department's Sampling Manual and make the materials available for sampling a sufficient time in advance of the use of the materials to allow for the necessary time for testing.

**A. Maintain and Control Traffic.** See Traffic Control Plan.

**B. Guardrail.** Furnish Guardrail system components according to section 814 and the Standard Drawings; except use steel posts only, no alternates. Furnish approximately 5,730 Extra Length Posts (9 foot length, steel-no alternates).

**C. Delineators for Guardrail.** Furnish white Delineators for Guardrail according to the Delineators for Guardrail Sepia Drawing (See Figure 2).

**D. Wall Cribbing.** Acceptable cribbing materials include new or like new used steel beam guardrail or steel or aluminum structural plates. Used steel beam guardrail is considered as structurally sound and in generally good condition and shall be subject to the inspection and approval of the Engineer prior to its installation. Used guardrail for cribbing purposes must perform like new guardrail that would be used for cribbing. This includes a galvanized coating, uniform thickness, and straight sections so as to prevent the backfill from escaping between installed sections. Contractor shall obtain the Engineer's approval of the type material prior to installation. Certifications and/or mill test reports are not required to be furnished for guardrail used for cribbing purposes. Use uniform material at each site; however, the Engineer will allow the Contractor to vary materials at different sites within the project.