



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

September 22, 2011

CALL NO. 303
CONTRACT ID NO. 112977
ADDENDUM # 1

Subject: Clay County, FE02 026 9006 B00062N
Letting September 23, 2011

- (1) Revised - Traffic Control - Pages 24-25 of 71
- (2) Revised - Bid Items - Pages 70-71 of 71

Proposal revisions are available at <http://transportation.ky.gov/contract/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

SPECIAL NOTE FOR TRAFFIC CONTROL ON BRIDGE REPAIR CONTRACTS

I. TRAFFIC CONTROL GENERAL

Except as provided herein, traffic shall be maintained in accordance with the 2008 Standard Specifications, Section 112. Except for the roadway and traffic control bid items listed, all items of work necessary to maintain and control traffic will be paid at the lump sum bid price to "Maintain and Control Traffic".

Contrary to Section 106.01, traffic control devices used on this project may be new or used in new condition, at the beginning of the work and maintained in like new condition until completion of the work.

II. TRAFFIC COORDINATOR

Furnish a Traffic Coordinator as per Section 112. The Traffic Coordinator shall inspect the project maintenance of traffic, at least three times daily, or as directed by the Engineer, during the Contractor's operations and at any time a lane closure is in place. The personnel shall have access on the project to a radio or telephone to be used in case of emergencies or accidents.

The Traffic Coordinator shall report all incidents throughout the work zone to the Engineer on the project. The Contractor shall furnish the name and telephone number where the Traffic Coordinator can be contacted at all times.

III. SIGNS

Contrary to Section 112.04.02, only long term signs (sign intended to be continuously in place for more than 3 days) will be measured for payment; short term signs (signs intended to be left in place for 3 days or less) will not be measured for payment but will be incidental to Maintain and Control Traffic.

The contractor is to install warning signs for wide loads in advance of the bridge under the direction of the Engineer. The Department will not measure installation, maintenance, or removal for payment, and will consider these incidentals to Maintain and Control Traffic.

IV. TEMPORARY PAVEMENT STRIPING

Skip lines and/or solid lines through the length of the tapers for lane closures and other striping as directed by the Engineer shall be temporarily covered with 6" black removable tape. Permanent removal of all other pavement striping for traffic control shall be considered incidental to Maintain and Control Traffic. Temporary pavement striping shall be paid only once per course in accordance with Section 112.04.07. The Contractor shall replace any temporary striping that becomes damaged or fails to adhere to the pavement before dark on the day of the notification. Liquidated damages shall be assessed to the Contractor at a rate of \$500 per day for failing to replace temporary striping within this time limit.

V. PROJECT PHASING & CONSTRUCTION PROCEDURES

Maintain one lane of traffic during construction in accordance with Standard Drawing No. TTC-110 for lane closures, and the attached detail drawing. The minimum clear lane width required is 13'-0".

Parkway lane closures will not be permitted on these days:

Easter Weekend (Thursday-Sunday)

Memorial Day Weekend (Friday-Monday)

Independence Day, when July 4th is on Tuesday, Wednesday, or Thursday; or

Independence Day Weekend, when July 4th is on Monday (Saturday-Monday) or Friday (Friday-Sunday)

Labor Day Weekend (Friday-Monday)

VI. TEMPORARY SIGNAL

Provide, install, and maintain a temporary 2 phase traffic signal. The Contractor must provide a 24-hour contact person and number available to maintain the temporary signals as needed.

CONTRACT ID: 112977
COUNTY: CLAY
PROPOSAL: FE02 026 9006 B00062N

PAGE: 1
LETTING: 09/23/11
CALL NO: 303

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
SECTION 0001 BRIDGE						
0020	02562	SIGNS	149.000	SQFT		
0030	02650	MAINTAIN & CONTROL TRAFFIC APPLIES TO B00062	(1.00)	LS		
0040	02653	LANE CLOSURE	2.000	EACH		
0050	02775	ARROW PANEL	1.000	EACH		
0070	03299	ARMORED EDGE FOR CONCRETE	88.000	LF		
0080	03300	ELIMINATE TRANSVERSE JOINT	135.750	LF		
0090	03304	BRIDGE OVERLAY APPROACH PAVEMENT	489.000	SQYD		
0091	04933	TEMP SIGNAL 2 PHASE (ADDED: 9-22-11)	1.000	EACH		
0100	06514	PAVE STRIPING-PERM PAINT-4 IN	671.000	LF		
0110	06549	PAVE STRIPING-TEMP REM TAPE-B (REVISED: 9-22-11)	500.000	LF		
0120	06550	PAVE STRIPING-TEMP REM TAPE-W (REVSIED: 9-22-11)	1,000.000	LF		
0121	06551	PAVE STRIPING-TEMP REM TAPE-Y (ADDED: 9-22-11)	2,000.000	LF		
0130	08150	STEEL REINFORCEMENT	1,169.000	LB		
0140	08504	EPOXY SAND SLURRY	99.000	SQYD		
0150	08510	REM EPOXY BIT FOREIGN OVERLAY	919.000	SQYD		
0160	08526	CONC CLASS M FULL DEPTH PATCH	5.000	CUYD		
0170	08534	CONCRETE OVERLAY-LATEX	38.300	CUYD		
0180	08549	BLAST CLEANING	1,018.000	SQYD		
0190	23428EC	CONCRETE PATCHING REPAIR PIER CAP ENDS (REVISED: 9-22-11)	20.000	CUFT		
0200	24094EC	PARTIAL DEPTH PATCHING	25.500	CUYD		
SECTION 0002 DEMOBILIZATION						

CONTRACT ID: 112977
COUNTY: CLAY
PROPOSAL: FE02 026 9006 B00062N

PAGE: 2
LETTING: 09/23/11
CALL NO: 303

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0210	02569	DEMOBILIZATION (AT LEAST 1.5%)	LUMP			
		TOTAL BID				