



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

February 19, 2020

CALL NO. 304
CONTRACT ID NO. 202058
ADDENDUM # 1

Subject: JEFFERSON COUNTY, FD05 056 0146 006-009
Letting February 21, 2020

- (1) Revised - Loop Summary - Page 29 of 44
- (2) Revised - Proposal Bid Items- Page 44 of 44

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

Jefferson County
 TRAFFIC LOOP SUMMARY
 FD05-0560146-006-009
 LOOP SUMMARY FOR ASPHALT PAVEMENT BID ALTERNATE

INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT 1 INCH LF		CONDUIT 1 1/4 INCH LF		CABLE NO. 14 LF	JUNCTION TYPE B EA		Trenching and Backfilling LF	Loop Test EA	NOTES
			LF	EA	LF	EA						
1265 North Leg	150	350	10	50	275	1	60	1				(1) 6 ft x 30 ft Loop @ Stop Bar (Left Turn)
Total	150	350	10	50	275	1	60	1				

INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT 1 INCH LF		CONDUIT 1 1/4 INCH LF		CABLE NO. 14 LF	JUNCTION TYPE B EA		Trenching and Backfilling LF	Loop Test EA	NOTES
			LF	EA	LF	EA						
Factory Ln./Chamberlin Ln North Leg	150	375	10	10	20	1	20	1				(1) 6 ft x 30 ft Loop @ Stop Bar (Left Turn)
South Leg	155	375	10	35	375	1	45	1				(1) 6 ft x 30 ft Loop @ Stop Bar (Left Turn)
Total	305	750	20	45	395	2	65	2				

INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT 1 INCH LF		CONDUIT 1 1/4 INCH LF		CABLE NO. 14 LF	JUNCTION TYPE B EA		Trenching and Backfilling LF	Loop Test EA	NOTES
			LF	EA	LF	EA						
Springs Station Rd. North Leg	150	375	10	45	225	1	55	1				(1) 6 ft x 30 ft Loop @ Stop Bar (Left Turn)
Total	150	375	10	45	225	1	55	1				

INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT 1 INCH LF		CONDUIT 1 1/4 INCH LF		CABLE NO. 14 LF	JUNCTION TYPE B EA		Trenching and Backfilling LF	Loop Test EA	NOTES
			LF	EA	LF	EA						
Reamers Rd./KY 1447 North Leg	150	375	10	25	25	1	35	1				(1) 6 ft x 30 ft Loop @ Stop Bar (Left Turn)
South Leg	150	500	10	100	350	1	110	1				(1) 6 ft x 30 ft Loop @ Stop Bar (Left Turn)
Total	300	875	20	125	375	2	145	2				

NOTES:
 1. Quantities are for estimating purposes only. The Contractor shall field measure and inspect items to verify quantities.
 2. 2 - 1/4 inch conduits may be used in place of 2" conduit. Field verify conduit to match existing facilities/ite-in to poles/cabinets. specifications. Only replace existing conduit if damaged.

Grand Total 905 2350 60 265 1270 6 325 6

PROPOSAL BID ITEMS

Report Date 2/19/20

Page 1 of 1

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	243.00	TON		\$	
0020	02562		TEMPORARY SIGNS	390.00	SQFT		\$	
0030	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0040	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0050	02677		ASPHALT PAVE MILLING & TEXTURING	4,968.00	TON		\$	
0060	02775		ARROW PANEL	2.00	EACH		\$	
0070	03240		BASE FAILURE REPAIR	160.00	SQYD		\$	
0075	04792		CONDUIT-1 IN (ADDED: 2-19-20)	60.00	LF		\$	
0080	04793		CONDUIT-1 1/4 IN (REVISED: 2-19-20)	265.00	LF		\$	
0085	04811		ELECTRICAL JUNCTION BOX TYPE B (ADDED: 2-19-20)	6.00	EACH		\$	
0090	04820		TRENCHING AND BACKFILLING	325.00	LF		\$	
0100	04830		LOOP WIRE (REVISED: 2-19-20)	2,350.00	LF		\$	
0105	04850		CABLE-NO. 14/1 PAIR (ADDED: 2-19-20)	1,270.00	LF		\$	
0110	04895		LOOP SAW SLOT AND FILL (REVISED: 2-19-20)	905.00	LF		\$	
0120	06510		PAVE STRIPING-TEMP PAINT-4 IN	72,000.00	LF		\$	
0130	06514		PAVE STRIPING-PERM PAINT-4 IN	72,000.00	LF		\$	
0140	06516		PAVE STRIPING-PERM PAINT-8 IN	2,200.00	LF		\$	
0150	06542		PAVE STRIPING-THERMO-6 IN W	130.00	LF		\$	
0160	06546		PAVE STRIPING-THERMO-12 IN W	175.00	LF		\$	
0170	06547		PAVE STRIPING-THERMO-12 IN Y	200.00	LF		\$	
0180	06562		PAVE MARKING-THERMO R 6 FT	2.00	EACH		\$	
0190	06563		PAVE MARKING-R/R XBUCKS 16 IN	42.00	LF		\$	
0200	06565		PAVE MARKING-THERMO X-WALK-6 IN	630.00	LF		\$	
0210	06568		PAVE MARKING-THERMO STOP BAR-24IN	521.00	LF		\$	
0220	06569		PAVE MARKING-THERMO CROSS-HATCH	1,035.00	SQFT		\$	
0230	06574		PAVE MARKING-THERMO CURV ARROW	84.00	EACH		\$	
0240	06575		PAVE MARKING-THERMO COMB ARROW	1.00	EACH		\$	
0250	06576		PAVE MARKING-THERMO ONLY	1.00	EACH		\$	
0260	06600		REMOVE PAVEMENT MARKER TYPE V	330.00	EACH		\$	
0270	10020NS		FUEL ADJUSTMENT	8,111.00	DOLL	\$1.00	\$	\$8,111.00
0280	10030NS		ASPHALT ADJUSTMENT	20,373.00	DOLL	\$1.00	\$	\$20,373.00
0290	22906ES403		CL3 ASPH SURF 0.38A PG64-22	4,968.00	TON		\$	
0300	23625EC		PAVE MARK THERMO-6 IN W CAT TRAXX	70.00	LF		\$	
0310	24963ED		LOOP TEST (REVISED: 2-19-20)	6.00	EACH		\$	
0320	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	25.00	TON		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0330	02569		DEMOBILIZATION	1.00	LS		\$	