



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

June 6, 2012

CALL NO. 304
CONTRACT ID NO. 121327
Addendum # 2

Subject: NELSON County, FD04 SPP 090 9002 024-030
Letting June 15, 2012

- (1) Revised - Plan Sheet - R2B
- (2) Revised - Bid Items - Pages 51-55 of 55

Proposal revisions are available at
<http://transportation.ky.gov/Construction-Procurement>

Plan Revisions are available at: <http://www.lynnimaging.com/kytransportation/>

If you have any questions, please contact us at (502) 564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:jj

Enclosures



An Equal Opportunity Employer M/F/D

CONTRACT ID: 121327
COUNTY: NELSON
PROPOSAL: FD04 SPP 090 9002 024-030

PAGE: 1
LETTING: 06/15/12
CALL NO: 304

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
SECTION 0001 PAVING						
0010	00001	DGA BASE	26,840.000	TON		
0020	00003	CRUSHED STONE BASE (REVISED: 5-30-12)	6,259.000	TON		
0030	00018	DRAINAGE BLANKET-TYPE II-ASPH	8,696.000	TON		
0040	00100	ASPHALT SEAL AGGREGATE	1,264.000	TON		
0050	00103	ASPHALT SEAL COAT	152.000	TON		
0060	00190	LEVELING & WEDGING PG64-22	1,640.000	TON		
0070	00191	ASPHALT SCRATCH COURSE PG64-22	4,557.000	TON		
0080	00212	CL2 ASPH BASE 1.00D PG64-22	9,973.000	TON		
0090	00214	CL3 ASPH BASE 1.00D PG64-22	62,645.000	TON		
0100	00301	CL2 ASPH SURF 0.38D PG64-22	4,156.000	TON		
0110	02585	EDGE KEY	700.000	LF		
0120	02676	MOBILIZATION FOR MILL & TEXT	(1.00)	LS		
0130	02677	ASPHALT PAVE MILLING & TEXTURING	2,035.000	TON		
0140	02696	SHOULDER RUMBLE STRIPS-SAWED	108,800.000	LF		
0150	10020NS	FUEL ADJUSTMENT (REVISED: 5-30-12)	150,327.000	DOLL	1.00	150,327.00
0160	10030NS	ASPHALT ADJUSTMENT	231,161.000	DOLL	1.00	231,161.00
0170	20757ED	PAVEMENT REPAIR (REVISED: 5-30-12)	322.000	SQYD		
0180	22906ES403	CL3 ASPH SURF 0.38A PG64-22	12,981.000	TON		
SECTION 0002 ROADWAY						
0190	00078	CRUSHED AGGREGATE SIZE NO 2	13,408.000	TON		

CONTRACT ID: 121327
COUNTY: NELSON
PROPOSAL: FD04 SPP 090 9002 024-030

PAGE: 2
LETTING: 06/15/12
CALL NO: 304

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0200	00461	CULVERT PIPE-15 IN (REVISED: 5-30-12)	30.000	LF		
0210	00464	CULVERT PIPE-24 IN	480.000	LF		
0220	00469	CULVERT PIPE-42 IN	8.000	LF		
0230	00471	CULVERT PIPE-54 IN	8.000	LF		
0240	01000	PERFORATED PIPE-4 IN	1,228.000	LF		
0250	01010	NON-PERFORATED PIPE-4 IN	1,950.000	LF		
0260	01020	PERF PIPE HEADWALL TY 1-4 IN	5.000	EACH		
0270	01024	PERF PIPE HEADWALL TY 2-4 IN	5.000	EACH		
0280	01028	PERF PIPE HEADWALL TY 3-4 IN	10.000	EACH		
0290	01032	PERF PIPE HEADWALL TY 4-4 IN	110.000	EACH		
0300	01432	SLOPED BOX OUTLET TYPE 1-15 IN	1.000	EACH		
0310	01451	S & F BOX INLET-OUTLET-24 IN	4.000	EACH		
0320	01690	FLUME INLET TYPE 1	4.000	EACH		
0330	01691	FLUME INLET TYPE 2	24.000	EACH		
0340	01897	ASPHALT WEDGE CURB	14,389.000	LF		
0350	01904	REMOVE CURB	1,160.000	LF		
0360	01982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL	WHITE 95.000	EACH		
0370	01983	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL	YELLOW 65.000	EACH		
0380	01984	DELINEATOR FOR BARRIER - WHITE (REVISED: 5-30-12)	7.000	EACH		
0390	02010	ADJUST MEDIAN BOX	37.000	EACH		
0400	02014	BARRICADE-TYPE III	16.000	EACH		

CONTRACT ID: 121327
COUNTY: NELSON
PROPOSAL: FD04 SPP 090 9002 024-030

PAGE: 3
LETTING: 06/15/12
CALL NO: 304

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0410	02091	REMOVE PAVEMENT	8,455.000	SQYD		
0420	02165	REMOVE PAVED DITCH	89.000	SQYD		
0430	02230	EMBANKMENT IN PLACE (REVISED: 6-6-12)	17,931.000	CUYD		
0440	02237	DITCHING	10,000.000	LF		
0450	02262	FENCE-WOVEN WIRE TYPE 1	370.000	LF		
0460	02363	GUARDRAIL CONNECTOR TO BRIDGE END TY A	4.000	EACH		
0470	02367	GUARDRAIL END TREATMENT TYPE 1	20.000	EACH		
0480	02369	GUARDRAIL END TREATMENT TYPE 2A	25.000	EACH		
0490	02377	GUARDRAIL CONNECTOR TO BRIDGE END TY C	6.000	EACH		
0500	02381	REMOVE GUARDRAIL	18,337.000	LF		
0510	02387	GUARDRAIL CONNECTOR TO BRIDGE END TY A-1	4.000	EACH		
0520	02391	GUARDRAIL END TREATMENT TYPE 4A	5.000	EACH		
0530	02397	TEMP GUARDRAIL	340.000	LF		
0540	02469	CLEAN SINKHOLE	1.000	EACH		
0550	02483	CHANNEL LINING CLASS II	2,000.000	TON		
0560	02484	CHANNEL LINING CLASS III	1,000.000	TON		
0570	02562	SIGNS	3,300.000	SQFT		
0580	02587	HOOK BOLT WITH EXPAN ANCHOR (REVISED: 5-30-12)	160.000	EACH		
0590	02599	FABRIC-GEOTEXTILE TYPE IV	12,170.000	SQYD		
0600	02650	MAINTAIN & CONTROL TRAFFIC	(1.00)	LS		
0610	02671	PORTABLE CHANGEABLE MESSAGE SIGN	4.000	EACH		

CONTRACT ID: 121327
COUNTY: NELSON
PROPOSAL: FD04 SPP 090 9002 024-030

PAGE: 4
LETTING: 06/15/12
CALL NO: 304

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0620	02726	STAKING	(1.00)	LS		
0630	02731	REMOVE STRUCTURE	(1.00)	LS		
0640	02775	ARROW PANEL	4.000	EACH		
0650	03171	CONCRETE BARRIER WALL TYPE 9T	680.000	LF		
0660	03225	TUBULAR MARKERS	375.000	EACH		
0670	03269	TRIM & REMOVE TREES & BRUSH	7,300.000	LF		
0680	05950	EROSION CONTROL BLANKET	50,254.000	SQYD		
0690	05985	SEEDING AND PROTECTION	17,000.000	SQYD		
0700	06417	FLEXIBLE DELINEATOR POST-W	220.000	EACH		
0710	06418	FLEXIBLE DELINEATOR POST-Y	235.000	EACH		
0720	06511	PAVE STRIPING-TEMP PAINT-6 IN	152,700.000	LF		
0730	06549	PAVE STRIPING-TEMP REM TAPE-B	1,750.000	LF		
0740	06550	PAVE STRIPING-TEMP REM TAPE-W	1,750.000	LF		
0750	06551	PAVE STRIPING-TEMP REM TAPE-Y	500.000	LF		
0760	06568	PAVE MARKING-THERMO STOP BAR-24IN	80.000	LF		
0770	06570	PAVE MARKING-PAINT CROSS-HATCH	1,650.000	SQFT		
0780	06592	PAVEMENT MARKER TYPE V-B W/R	774.000	EACH		
0790	06593	PAVEMENT MARKER TYPE V-B Y/R	125.000	EACH		
0800	08100	CONCRETE-CLASS A	32.000	CUYD		
0810	08150	STEEL REINFORCEMENT	1,771.000	LB		
0820	08905	CRASH CUSHION TY VI CLASS CT	2.000	EACH		

CONTRACT ID: 121327
COUNTY: NELSON
PROPOSAL: FD04 SPP 090 9002 024-030

PAGE: 5
LETTING: 06/15/12
CALL NO: 304

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0830	20411ED	LAW ENFORCEMENT OFFICER	600.000	HOUR		
0840	20467NS112	RELOCATE TUBULAR MARKER	265.000	EACH		
0850	20545ND	TEMP MEDIAN CROSSOVER	4.000	EACH		
0860	20758ED	REMOVE AND RESET PERF PIPE HEADWALL	100.000	EACH		
0870	21451ED	FILL AND GRADE MEDIAN	26,450.000	LF		
0880	21802EN	G/R STEEL W BEAM-S FACE (7 FT POST)	18,210.000	LF		
0890	22660EN	REPLACE GRATE	388.000	LB		
0900	23143ED	KPDES PERMIT AND TEMP EROSION CONTROL	(1.00)	LS		
0910	23159EN	DURABLE WATERBORNE MARKING-6 IN W	75,706.000	LF		
0920	23160EN	DURABLE WATERBORNE MARKING-6 IN Y	59,450.000	LF		
0930	23624EC	REMOVE AND RESET CRASH CUSHION (REVISED: 5-30-12)	5.000	EACH		
0940	24191ER	DURABLE WATERBORNE MARKING-12 IN W	1,760.000	LF		
0950	24381EC	G/R STEEL W BEAM-S FACE (NESTED)	1,050.000	LF		
SECTION 0003 MOBILIZATION / DEMOBILIZATION						
0960	02568	MOBILIZATION (NO MORE THAN 5%)		LUMP		
0970	02569	DEMOBILIZATION (AT LEAST 1.5%)		LUMP		
		TOTAL BID				