



**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

December 8, 2016

CALL NO. 305
CONTRACT ID NO. 162983
ADDENDUM # 2

Subject: Henderson County, FE02 051 0041 B0002R
Letting December 9, 2016

(1) Revised - Traffic Control - Pages 10-11 of 69

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:ks
Enclosures



An Equal Opportunity Employer M/F/D

SPECIAL NOTE FOR TRAFFIC CONTROL ON BRIDGE REPAIR CONTRACTS

I. TRAFFIC CONTROL GENERAL

Except as provided herein, traffic shall be maintained in accordance with the 2012 Standard Specifications, Section 112. All items of work necessary to maintain and control traffic will be paid at the lump sum bid price to “Maintain and Control Traffic”.

The contractor shall be required to submit in writing, to the department, his complete work schedule and traffic control plan 14 days prior to the Pre-Construction Conference. The contractor shall be required to coordinate his efforts with those of any other contractor in the construction area so as to eliminate any lane closures which conflict with this traffic note.

Contrary to Section 106.01, traffic control devices used on this project may be new or used in new condition, at the beginning of the work and maintained in like new condition until completion of the work.

II. TRAFFIC COORDINATOR

Furnish a Traffic Coordinator as per Section 112. The Traffic Coordinator shall inspect the project maintenance of traffic, at least three times daily, or as directed by the Engineer, during the Contractor’s operations and at any time a lane closure is in place. The personnel shall have access on the project to a radio or telephone to be used in case of emergencies or accidents.

The Traffic Coordinator shall report all incidents throughout the work zone to the Engineer on the project. The Contractor shall furnish the name and telephone number where the Traffic Coordinator can be contacted at all times.

III. SIGNS

The contractor is to install warning signs for wide loads in advance of the bridge under the direction of the Engineer. This shall be paid under the lump sum bid price to Maintain and Control Traffic. The Department will not measure installation, maintenance, or removal for payment, and will consider these incidentals to Maintain and Control Traffic.

IV. LANE CLOSURES

Northbound 051B00002R - Needed single lane closures for shall be from 8:30am - 2:00pm and/or 8:00pm-6:00am. Length of lane closure will be the entire length of the bridge plus tapers.

Southbound 051B00007L – The contractor shall limit live load during jacking operations by using a single lane closure over bearing being jacked. Needed single lane closures shall be from 8:30am – 2:00pm and/or 8:00pm – 6:00am. Length of lane closure will be the entire length of the bridge plus tapers. See Special Note for Remove and Replace Girder Bearings for jacking requirements.

Maintain one lane of traffic during construction in accordance with Standard Drawing No. TTC-115-03 for lane closures. The minimum clear lane width required is 11’-0”.

Lane closures will not be permitted on these days:

- Easter Weekend (Thursday-Sunday)
- Memorial Day Weekend (Friday-Monday)
- Independence Day Weekend, Labor Day Weekend (Friday-Monday)
- Thanksgiving Day Weekend (Thursday-Sunday)
- Christmas/New Years (December 24-January 2)

V. VARIABLE MESSAGE SIGNS

If deemed necessary by the Engineer, variable message signs will be installed, operated, and maintained by the Department.