



COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

Matthew G. Bevin  
Governor

Greg Thomas  
Secretary

June 18, 2019

CALL NO. 307  
CONTRACT ID NO. 192241  
ADDENDUM # 1

Subject: BOYLE COUNTY, FD05 011 0127 005-008  
Letting June 21, 2019

- (1) Added - Special Notes - Page 9(a) of 50
- (2) Revised - Traffic Loop Summary - Page 32 of 50
- (3) Revised - Proposal Bid Items - Pages 50-50(a) of 50

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures



An Equal Opportunity Employer M/F/D

***SPECIAL NOTE***  
**For Striping Revision Trial Period**  
**Boyle County**  
**ASPHALT RESURFACING**  
**MAIN STREET/MAPLE AVENUE (US 127)**  
**FD05 011 0127 005-008**

**Pave Striping-Temp Paint- 4 IN** and **Water Blast Existing Stripe** quantities are included to perform striping revisions prior to resurfacing operations. Striping revisions will consist of removing a four-lane striping configuration and replacing with a 3-lane striping configuration with various turning lanes. The department will provide a detailed striping plan to the contractor prior to scheduling of the Preconstruction Meeting. The revised striping plan is to be installed and in place for a period of 6 weeks before beginning milling and resurfacing operations. The striping revision shall not occur prior to August 1, 2019. After a 4-week trial period, the department will evaluate the performance of the revised striping and provide the contractor a final striping plan within 2 weeks for a total trial period of 6 weeks. Milling and resurfacing operations shall not begin until after receiving the final striping plan from the department. Layout for the striping revisions will be incidental to the bid item for Pave Striping-Temp Paint-4 IN.



**PROPOSAL BID ITEMS**

192241

Page 1 of 2

Report Date 6/18/19

**Section: 0001 - PAVING**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	140.00	TON		\$	
0020	00388		CL3 ASPH SURF 0.38B PG64-22	2,840.00	TON		\$	
0030	02562		TEMPORARY SIGNS	250.00	SQFT		\$	
0040	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0050	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0060	02677		ASPHALT PAVE MILLING & TEXTURING	2,106.00	TON		\$	
0065	04795		CONDUIT-2 IN (RS) (ADDED: 6-18-19)	496.00	LF		\$	
0070	04811		ELECTRICAL JUNCTION BOX TYPE B (REVISED: 6-18-19)	4.00	EACH		\$	
0080	04820		TRENCHING AND BACKFILLING	30.00	LF		\$	
0085	04821		OPEN CUT ROADWAY (ADDED: 6-18-19)	496.00	LF		\$	
0090	04830		LOOP WIRE	1,765.00	LF		\$	
0100	04850		CABLE-NO. 14/1 PAIR	485.00	LF		\$	
0110	04895		LOOP SAW SLOT AND FILL	710.00	LF		\$	
0120	06510		PAVE STRIPING-TEMP PAINT-4 IN	15,500.00	LF		\$	
0130	06514		PAVE STRIPING-PERM PAINT-4 IN	8,200.00	LF		\$	
0140	06542		PAVE STRIPING-THERMO-6 IN W	33,000.00	LF		\$	
0150	06543		PAVE STRIPING-THERMO-6 IN Y	26,000.00	LF		\$	
0160	06565		PAVE MARKING-THERMO X-WALK-6 IN	254.00	LF		\$	
0170	06566		PAVE MARKING-THERMO X-WALK-12 IN	1,723.00	LF		\$	
0180	06568		PAVE MARKING-THERMO STOP BAR-24IN	276.00	LF		\$	
0190	06574		PAVE MARKING-THERMO CURV ARROW	4.00	EACH		\$	
0200	06575		PAVE MARKING-THERMO COMB ARROW	1.00	EACH		\$	
0210	06576		PAVE MARKING-THERMO ONLY	2.00	EACH		\$	
0220	06577		PAVE MARKING-THERMO SCHOOL	2.00	EACH		\$	
0230	06600		REMOVE PAVEMENT MARKER TYPE V	30.00	EACH		\$	
0235	20391NS835		ELECTRICAL JUNCTION BOX TYPE A (ADDED: 6-18-19)	12.00	EACH		\$	
0240	20782NS714		PAVE MARKING THERMO-BIKE	10.00	EACH		\$	
0245	21543EN		BORE AND JACK CONDUIT (ADDED: 6-18-19)	496.00	LF		\$	
0250	22664EN		WATER BLASTING EXISTING STRIPE	4,500.00	LF		\$	
0260	23158ES505		DETECTABLE WARNINGS (RETROFIT)	106.00	SQFT		\$	
0270	23625EC		PAVE MARK THERMO-6 IN W CAT TRAXX	34.00	LF		\$	
0280	24386EC		PAVE MARKING THERMO-BIKE LANE ARROW	10.00	EACH		\$	
0290	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80	30.00	LF		\$	
0300	24963ED		LOOP TEST	1.00	EACH		\$	
0310	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING	12.00	TON		\$	

**Section: 0002 - DEMOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
------	----------	-----	-------------	----------	------	-----------	----	--------

192241

### PROPOSAL BID ITEMS

Page 2 of 2

Report Date 6/18/19

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0320	02569		DEMOBILIZATION	1.00	LS		\$	