



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

September 16, 2020

CALL NO. 310
CONTRACT ID NO. 202150
ADDENDUM # 1

Subject: BULLITT COUNTY, FD05 015 6313 000-002
Letting September 25, 2020

- (1) Revised - Traffic Loop Summary - Page 28 of 42
- (2) Revised - Proposal Bid Items - Page 42 of 42

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

**BULLITT
TRAFFIC LOOP SUMMARY
FD05 015 6313 000-002
LOOP SUMMARY FOR ASPHALT PAVEMENT BID ALTERNATE**

INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT		CONDUIT		CABLE NO. 14 LF	JUNCTION TYPE B EA	CONDUIT LF	ROADWAY LF	REMOVE AND REPLACE SIDEWALK SQ YD	Trenching and Backfilling LF	Loop Test EA	NOTES
			1 INCH LF	1 1/4 INCH LF	2 INCH LF	CONDUIT LF								
HEBRON														
6313 NB	165	370	10	40	0	50	1	0	0	0	0	40	1	6X30 STOP BAR LOOP
6313 SB	145	350	10	30	0	225	1	0	0	0	0	30	1	6X30 STOP BAR LOOP
WB HEBRON	245	600	10	30	0	80	1	0	0	0	0	30	2	2 6X30 STOP BAR LOOPS
EB HEBRON	265	600	10	50	0	440	1	0	0	0	0	50	2	2 6X30 STOP BAR LOOPS
Total	820	1920	40	150	0	795	4	0	0	0	0	150	6	
Grand Total	820	1920	40	150	0	795	4	0	0	0	0	150	6	

- Quantities are for estimating purposes only. The Contractor shall field measure and inspect items to verify quantities.
- 2 - 1/4 inch conduits may be used in place of 2" conduit. Field verify conduit to match existing facilities/tie-in to poles/cabinets. specifications. Only replace existing conduit if damaged.

PROPOSAL BID ITEMS

202150

Page 1 of 1

Report Date 9/16/20

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	220.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	1,650.00	TON		\$	
0030	00356		ASPHALT MATERIAL FOR TACK	13.00	TON		\$	
0040	02562		TEMPORARY SIGNS	570.00	SQFT		\$	
0050	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0060	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0070	02677		ASPHALT PAVE MILLING & TEXTURING	1,650.00	TON		\$	
0080	04792		CONDUIT-1 IN (ADDED: 9-16-20)	40.00	LF		\$	
0090	04811		ELECTRICAL JUNCTION BOX TYPE B (ADDED: 9-16-20)	4.00	EACH		\$	
0100	04820		TRENCHING AND BACKFILLING (REVISED: 9-16-20)	150.00	LF		\$	
0110	04830		LOOP WIRE (REVISED: 9-16-20)	1,920.00	LF		\$	
0120	04850		CABLE-NO. 14/1 PAIR (ADDED: 9-16-20)	795.00	LF		\$	
0130	04895		LOOP SAW SLOT AND FILL (REVISED: 9-16-20)	820.00	LF		\$	
0140	06510		PAVE STRIPING-TEMP PAINT-4 IN	41,456.00	LF		\$	
0150	06514		PAVE STRIPING-PERM PAINT-4 IN	41,456.00	LF		\$	
0160	06565		PAVE MARKING-THERMO X-WALK-6 IN	420.00	LF		\$	
0170	06568		PAVE MARKING-THERMO STOP BAR-24IN	96.00	LF		\$	
0180	06574		PAVE MARKING-THERMO CURV ARROW	8.00	EACH		\$	
0190	06600		REMOVE PAVEMENT MARKER TYPE V	70.00	EACH		\$	
0200	24123EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 40 (ADDED: 9-16-20)	150.00	LF		\$	
0210	24963ED		LOOP TEST (ADDED: 9-16-20)	6.00	EACH		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0220	02569		DEMOBILIZATION	1.00	LS		\$	