

Matthew G. Bevin Governor TRANSPORTATION CABINE Frankfort, Kentucky 40622 www.transportation.ky.gov/

Greg Thomas Secretary

October 22, 2019

CALL NO. 311

CONTRACT ID NO. 192367

ADDENDUM # 1

Subject: Christian County, FD05 024 068B 000-006

Letting October 25, 2019

(1)Added - Special Note - Pages 15(a)-15(c) of 58

(1)Revised - Proposal Bid Items - Page 58 of 58

Proposal revisions are available at http://transportation.ky.gov/Construction-procurement/.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills, P.E.

Director

Division of Construction Procurement

Kachel Mille

RM:ws

Enclosures



11N

- 1. DESCRIPTION. This specification covers the requirements and practices for applying an asphalt adhesive material to the longitudinal joint of the surface course of an asphalt pavement. Apply the adhesive to the face of longitudinal joint between driving lanes for the first lane paved. Then, place and compact the adjacent lane against the treated face to produce a strong, durable, waterproof longitudinal joint.
- 2. MATERIALS, EQUIPMENT, AND PERSONNEL.
 - 2.1 Joint Adhesive. Provide material conforming to Subsection 2.1.1.
 - 2.1.1 Provide an adhesive conforming to the following requirements:

Property	Specification	Test Procedure
Viscosity, 400 ° F (Pa·s)	4.0 – 10.0	ASTM D 4402
Cone Penetration, 77 ° F	60 – 100	ASTM D 5329
Flow, 140 ° F (mm)	5.0 max.	ASTM D 5329
Resilience, 77 ° F (%)	30 min.	ASTM D 5329
Ductility, 77 ° F (cm)	30.0 min.	ASTM D 113
Ductility, 39 ° F (cm)	30.0 min.	ASTM D 113
Tensile Adhesion, 77 ° F (%)	500 min.	ASTM D 5329, Type II
Softening Point, ° F	171 min.	AASHTO T 53
Asphalt Compatibility	Pass	ASTM D 5329

Ensure the temperature of the pavement joint adhesive is between 380 and 410 °F when the material is extruded in a 0.125-inch-thick band over the entire face of the longitudinal joint.

- 2.2. Equipment.
- 2.2.1 Melter Kettle. Provide an oil-jacketed, double-boiler, melter kettle equipped with any needed agitation and recirculating systems.
- 2.2.2 Applicator System. Provide a pressure-feed-wand applicator system with an applicator shoe attached.
- 2.3 Personnel. Ensure a technical representative from the manufacturer of the pavement joint adhesive is present during the initial construction activities and available upon the request of the Engineer.

3. CONSTRUCTION.

3.1 Surface Preparation. Prior to the application of the pavement joint adhesive, ensure the face of the longitudinal joint is thoroughly dry and free from dust or any other debris that would inhibit adhesion. Clean the joint face by the use of compressed air.

Ensure this preparation process occurs shortly before application to prevent the return of debris on the joint face.

- 3.2 Pavement Joint Adhesive Application. Ensure the ambient temperature is a minimum of 40 °F during the application of the pavement joint adhesive. Prior to applying the adhesive, demonstrate competence in applying the adhesive according to this note to the satisfaction of the Engineer. Heat the adhesive in the melter kettle to the specified temperature range. Pump the adhesive from the melter kettle through the wand onto the vertical face of the cold joint. Apply the adhesive in a continuous band over the entire face of the longitudinal joint. Do not use excessive material in either thickness or location. Ensure the edge of the extruded adhesive material is flush with the surface of the pavement. Then, place and compact the adjacent lane against the joint face. Remove any excessive material extruded from the joint after compaction (a small line of material may remain).
- 3.3 Pavement Joint Adhesive Certification. Furnish the joint adhesive's certification to the Engineer stating the material conforms to all requirements herein prior to use.
- 3.4 Sampling and Testing. The Department will require a random sample of pavement joint adhesive from each manufacturer's lot of material. Extrude two 5 lb. samples of the heated material and forward the sample to the Division of Materials for testing. Reynolds oven bags, turkey size, placed inside small cardboard boxes or cement cylinder molds have been found suitable. Ensure the product temperature is 400°F or below at the time of sampling.
- 4. MEASUREMENT. The Department will measure the quantity of Pavement Joint Adhesive in linear feet. The Department will not measure for payment any extra materials, labor, methods, equipment, or construction techniques used to satisfy the requirements of this note. The Department will not measure for payment any trial applications of Pavement Joint Adhesive, the cleaning of the joint face, or furnishing and placing the adhesive. The Department will consider all such items incidental to the Pavement Joint Adhesive.
- 5. PAYMENT. The Department will pay for the Pavement Joint Adhesive at the Contract unit bid price and apply an adjustment for each manufacturer's lot of material based on the degree of compliance as defined in the following schedule. When a sample fails on two or more tests, the Department may add the deductions, but the total deduction will not exceed 100 percent.

Pavement Joint Adhesive Price Adjustment Schedule										
Test	Specification	100% Pay	90% Pay	80% Pay	50% Pay	0% Pay				
Joint Adhesive Referenced in Subsection 2.1.1										
Viscosity, 400 ° F (Pa•s)			3.0-3.4	2.5-2.9	2.0-2.4	≤1.9				
ASTM D 3236	4.0-10.0	3.5-10.5	10.6-11.0	11.1-11.5	11.6-12.0	≥ 12.1				
Cone Penetration, 77 ° F			54-56	51-53	48-50	≤ 47				
ASTM D 5329	60-100	57-103	104-106	107-109	110-112	≥ 113				
Flow, 140 ° F (mm) ASTM D 5329	≤ 5.0	≤ 5.5	5.6-6.0	6.1-6.5	6.6-7.0	≥ 7.1				
Resilience, 77 ° F (%) ASTM D 5329	≥ 30	≥ 28	26-27	24-25	22-23	≤ 21				
Tensile Adhesion, 77 ° F (%) ASTM D 5329	≥ 500	≥ 490	480-489	470-479	460-469	≤ 459				
Softening Point, ° F AASHTO T 53	≥ 171	≥ 169	166-168	163-165	160-162	≤ 159				
Ductility, 77 ° F (cm) ASTM D 113	≥ 30.0	≥ 29.0	28.0-28.9	27.0-27.9	26.0-26.9	≤ 25.9				
Ductility, 39 ° F (cm) ASTM D 113	≥ 30.0	≥ 29.0	28.0-28.9	27.0-27.9	26.0-26.9	≤ 25.9				

CodePay ItemPay Unit20071ECJoint AdhesiveLinear Foot

May 7, 2014

PROPOSAL BID ITEMS

REVISED ADDENDUM #1: 10-22-19 Contract ID: 192367 Page 58 of 58

Page 1 of 1

Report Date 10/22/19

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	650.00	TON		\$	
0020	00324		CL3 ASPH SURF 0.50B PG64-22	16,180.00	TON		\$	
0030	02562		TEMPORARY SIGNS	350.00	SQFT		\$	
0040	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0050	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0060	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0070	02677		ASPHALT PAVE MILLING & TEXTURING	16,180.00	TON		\$	
0800	02775		ARROW PANEL	2.00	EACH		\$	
0090	04793		CONDUIT-1 1/4 IN	500.00	LF		\$	
0100	04811		ELECTRICAL JUNCTION BOX TYPE B	12.00	EACH		\$	
0110	04820		TRENCHING AND BACKFILLING	500.00	LF		\$	
0120	04830		LOOP WIRE	4,628.00	LF		\$	
0130	04850		CABLE-NO. 14/1 PAIR	2,000.00	LF		\$	
0140	04895		LOOP SAW SLOT AND FILL	1,948.00	LF		\$	
0150	05985		SEEDING AND PROTECTION	350.00	SQYD		\$	
0160	06510		PAVE STRIPING-TEMP PAINT-4 IN	165,876.00	LF		\$	
0170	06542		PAVE STRIPING-THERMO-6 IN W	80,000.00	LF		\$	
0180	06543		PAVE STRIPING-THERMO-6 IN Y	60,000.00	LF		\$	
0190	06568		PAVE MARKING-THERMO STOP BAR-24IN	180.00	LF		\$	
0200	06574		PAVE MARKING-THERMO CURV ARROW	50.00	EACH		\$	
0210	06600		REMOVE PAVEMENT MARKER TYPE V	672.00	EACH		\$	
0220	10020NS		FUEL ADJUSTMENT	25,185.00	DOLL	\$1.00	\$	\$25,185.00
0230	10030NS		ASPHALT ADJUSTMENT	63,257.00	DOLL	\$1.00	\$	\$63,257.00
0235	20071EC		JOINT ADHESIVE (ADDED: 10-22-19)	67,560.00	LF		\$	
0240	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING	58.00	TON		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0250	02569		DEMOBILIZATION	1.00	LS	6	\$	