



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

December 11, 2012

CALL NO. 313
CONTRACT ID NO. 121069
ADDENDUM # 3

Subject: Fayette County, FD39 034 0922 000-001
Letting December 14, 2012

(1) Revised - Note - Pages 15-19(b) of 99

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

FAYETTE COUNTY FD39 034 85884
NEWTOWN PIKE (KY-922)
WIDEN NEWTOWN PIKE TO FIVE LANE URBAN ROADWAY AT NEW BCTC CAMPUS
ENTRANCE, INCLUDING WORK ON W. LOUDON, W. FOURTH ST., AND
GEORGETOWN ST.
ITEM NUMBER – 7-375.00

GENERAL PROJECT NOTE ON UTILITY PROTECTION

Utility relocations have not begun on this project. Project Design attempted to avoid any utility relocations; however, some will be necessary. It is unknown if the highway contractor will have productive work available within the project; however, that is for the highway contractor to determine. The highway contractor should not anticipate that any utility relocation work will be complete before the letting, or by the award of the contract; consequently, the highway contractor should prepare the construction schedule accordingly.

NOTE: DO NOT DISTURB THE FOLLOWING UTILITIES LOCATED WITHIN THE PROJECT DISTURB LIMITS

- Kentucky Utilities Company – Power Distribution
- Kentucky Utilities Company – Power Transmission
- Insight Communications – Cable Television
- Kentucky American Water Company – Water transmission and distribution
- Columbia Gas of Kentucky – Natural gas distribution
- Lexington-Fayette Urban County Government – Sanitary sewer collection
- AT&T – Legacy – Copper and fiber optic interstate/intrastate telecommunications
- AT&T – Kentucky -- Copper and fiber optic intrastate telecommunications
- Windstream Communications -- Copper and fiber optic intrastate telecommunications
- Kentucky Data Link -- Copper and fiber optic interstate/intrastate telecommunications
- TW Telecom -- Copper and fiber optic interstate/intrastate telecommunications

This may not be a complete list of the Utility Companies / Facilities within the project limits.

The Contractor is fully responsible for protection of all utilities

THE FOLLOWING COMPANIES ARE RELOCATING/ADJUSTING THEIR UTILITIES WITHIN THE PROJECT LIMITS AND WILL BE COMPLETE PRIOR TO CONSTRUCTION

NONE

THE FOLLOWING COMPANIES HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE COMPANY OR THE COMPANY'S SUBCONTRACTOR AND IS TO BE COORDINATED WITH THE ROAD CONTRACT

Kentucky Utilities Company – Power Distribution. While a portion of the Company's facility may be affected by the work along Newtown Pike, **the work necessary on the property owned by the Bluegrass**

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

FAYETTE COUNTY FD39 034 85884
NEWTOWN PIKE (KY-922)
WIDEN NEWTOWN PIKE TO FIVE LANE URBAN ROADWAY AT NEW BCTC CAMPUS
ENTRANCE, INCLUDING WORK ON W. LOUDON, W. FOURTH ST., AND
GEORGETOWN ST.
ITEM NUMBER – 7-375.00

Community and Technical College cannot be completed until the current occupants (Eastern State Hospital) have vacated. This is currently scheduled to occur on April 15, 2013; however, any change in that date will have a direct impact on the Company's schedule. The utility relocation work along 4th Street has only recently been determined necessary; and, only due to the sight-distance requirements for the reconfigured railroad crossing lights and signal. With the exception of a Kentucky Utilities Transmission guy-pole (located at approximate station 56+80, and approximately 17 feet left) and anchor, all road, curb, and sidewalk work was intended to be accomplished while the existing utility facilities, located along the southwest side of the proposed 4th Street, remained as they were. And it appears that a significant portion of that work can still be accomplished while KU-Transmission places a new temporary guy-pole and anchor, to allow the removal of the existing one. ~~it is anticipated that the majority of the Company's relocations will be along 4th Street, and the new intersection of Newtown Pike / Georgetown Street / 4th Street. The relocation work along 4th Street is a recent addition due to the return of 4th Street to two-way traffic flow, and the necessary adjustment of the railroad crossing signals and gates.~~ Unfortunately, the Company has not yet completed their review of the project, and its impact on their facility. Consequently, the extent of the project's impact to their facility has not been completely determined. ~~Additionally, until the Company has presented a relocation plan and estimate, a beginning date cannot be determined, and a completion date cannot be estimated.~~ The Company's review of the additional information is still ongoing; however, based on the assumption of a timely move by the current occupants, and a timely completion and commencement of relocation construction activities, the Company has been assigned a completion date of March 1, 2013.

Kentucky Utilities Company – Power Transmission. While it had previously been determined that the Company would have no facility affected by the project, the recent addition of work along 4th Street has involved a small portion of the Company's facility. The utility relocation work along 4th Street has only recently been determined necessary; and, only due to the sight-distance requirements for the reconfigured railroad crossing lights and signal. With the exception of a Kentucky Utilities Transmission guy-pole (located at approximate station 56+80, and approximately 17 feet left) and anchor, all road, curb, and sidewalk work was intended to be accomplished while the utility facilities, located along the southwest side of the proposed 4th Street, remained as they were. And it appears that a significant portion of that work can still be accomplished while KU-Transmission places a new temporary guy-pole and anchor, to allow the removal of the existing one. Unfortunately, the Company has not yet completed their review of the project, and its impact on their facility. Consequently, the extent of the project's impact to their facility has not been completely determined. ~~Additionally, until the Company has presented a relocation plan and estimate, a beginning date cannot be determined, and a completion date cannot be estimated.~~ The Company's review of the additional information is still ongoing;

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

FAYETTE COUNTY FD39 034 85884
NEWTOWN PIKE (KY-922)
WIDEN NEWTOWN PIKE TO FIVE LANE URBAN ROADWAY AT NEW BCTC CAMPUS
ENTRANCE, INCLUDING WORK ON W. LOUDON, W. FOURTH ST., AND
GEORGETOWN ST.
ITEM NUMBER – 7-375.00

however, based on the assumption of a timely move by the current occupants, and a timely completion and commencement of relocation construction activities, the Company has been assigned a completion date of March 1, 2013.

Insight Communications – Cable Television. While a portion of the Company's facility may be affected by the work along Newtown Pike, it is anticipated that the majority of the Company's relocations will be along 4th Street, and the new intersection of Newtown Pike / Georgetown Street / 4th Street. ~~The relocation work along 4th Street is a recent addition due to the return of 4th Street to two-way traffic flow, and the necessary adjustment of the railroad crossing signals and gates.~~ The utility relocation work along 4th Street has only recently been determined necessary; and, only due to the sight-distance requirements for the reconfigured railroad crossing lights and signal. With the exception of a Kentucky Utilities Transmission guy-pole (located at approximate station 56+80, and approximately 17 feet left) and anchor, all road, curb, and sidewalk work was intended to be accomplished while the utility facilities, located along the right side of the proposed 4th Street, remained as they were. And it appears that a significant portion of that work can still be accomplished while KU-Transmission places a new temporary guy-pole and anchor, to allow the removal of the existing one. Unfortunately, the Company has not yet completed their review of the project, and its impact on their facility. Consequently, the extent of the project's impact to their facility has not been completely determined. ~~Additionally, until the Company has presented a relocation plan and estimate, a beginning date cannot be determined, and a completion date cannot be estimated.~~ The Company's review of the additional information is still ongoing; however, based on the assumption of a timely move by the current occupants, and a timely completion and commencement of relocation construction activities, the Company has been assigned a completion date of May 1, 2013.

Kentucky American Water Company – Water transmission and distribution. While the Company has facility located within the construction area of Newtown Pike, it is not anticipated that this facility will require adjustment; however, the work necessary on the property owned by the Bluegrass Community and Technical College cannot be completed until the current occupants (Eastern State Hospital) have vacated. This is currently scheduled to occur on April 15, 2013; although, any change in that date will have a direct impact on the Company's schedule. However, it is anticipated that the majority of the Company's relocations will be along 4th Street, and the new intersection of Newtown Pike / Georgetown Street / 4th Street. ~~The relocation work along 4th Street is a recent addition due to the return of 4th Street to two-way traffic flow, and the necessary adjustment of the railroad crossing signals and gates.~~ The utility relocation work along 4th Street has only recently been determined necessary; and, only due to the sight-distance requirements for the reconfigured railroad crossing lights and signal. With the

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

FAYETTE COUNTY FD39 034 85884
NEWTOWN PIKE (KY-922)
WIDEN NEWTOWN PIKE TO FIVE LANE URBAN ROADWAY AT NEW BCTC CAMPUS
ENTRANCE, INCLUDING WORK ON W. LOUDON, W. FOURTH ST., AND
GEORGETOWN ST.
ITEM NUMBER – 7-375.00

exception of a Kentucky Utilities Transmission guy-pole (located at approximate station 56+80, and approximately 17 feet left) and anchor, all road, curb, and sidewalk work was intended to be accomplished while the utility facilities, located along the southwest side of the proposed 4th Street, remained as they were. And it appears that a significant portion of that work can still be accomplished while KU-Transmission places a new temporary guy-pole and anchor, to allow the removal of the existing one. Unfortunately, the Company has not yet completed their review of the project, and its impact on their facility. Consequently, the extent of the project's impact to their facility has not been completely determined. ~~Additionally, until the Company has presented a relocation plan and estimate, a beginning date cannot be determined, and a completion date cannot be estimated.~~ The Company's review of the additional information is still ongoing; however, based on the assumption of a timely move by the current occupants, and a timely completion and commencement of relocation construction activities, the Company has been assigned a completion date of April 30, 2013.

Columbia Gas of Kentucky – Natural gas distribution. While the Company has facility located within the construction corridor of Newtown Pike, it is not anticipated that this facility will require adjustment; however, the work necessary on the property owned by the Bluegrass Community and Technical College cannot be completed until the current occupants (Eastern State Hospital) have vacated. This is currently scheduled to occur on April 15, 2013; although, any change in that date will have a direct impact on the Company's schedule. However, it is anticipated that the majority of the Company's relocations will be along 4th Street, and the new intersection of Newtown Pike / Georgetown Street / 4th Street. ~~The relocation work along 4th Street is a recent addition due to the return of 4th Street to two way traffic flow, and the necessary adjustment of the railroad crossing signals and gates.~~ The utility relocation work along 4th Street has only recently been determined necessary; and, only due to the sight-distance requirements for the reconfigured railroad crossing lights and signal. With the exception of a Kentucky Utilities Transmission guy-pole (located at approximate station 56+80, and approximately 17 feet left) and anchor, all road, curb, and sidewalk work was intended to be accomplished while the utility facilities, located along the southwest side of the proposed 4th Street, remained as they were. And it appears that a significant portion of that work can still be accomplished while KU-Transmission places a new temporary guy-pole and anchor, to allow the removal of the existing one. Unfortunately, the Company has not yet completed their review of the project, and its impact on their facility. Consequently, the extent of the project's impact to their facility has not been completely determined. ~~Additionally, until the Company has presented a relocation plan and estimate, a beginning date cannot be determined, and a completion date cannot be estimated.~~ The Company's review of the additional information is still ongoing; however, based on the assumption of a timely move by the current occupants, and a timely completion and commencement of relocation construction activities, the

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

FAYETTE COUNTY FD39 034 85884
NEWTOWN PIKE (KY-922)
WIDEN NEWTOWN PIKE TO FIVE LANE URBAN ROADWAY AT NEW BCTC CAMPUS
ENTRANCE, INCLUDING WORK ON W. LOUDON, W. FOURTH ST., AND
GEORGETOWN ST.
ITEM NUMBER – 7-375.00

Company has been assigned a completion date of April 30, 2013.

AT&T – Legacy – Copper and fiber optic interstate/intrastate telecommunications. While it is anticipated that the Company's facility will not be affected by the project, the Company has not yet completed their review of the project, and its impact on their facility. Consequently, the extent of the project's impact to their facility has not been completely determined. ~~Additionally, until the Company has presented a relocation plan and estimate, a beginning date cannot be determined, and a completion date cannot be estimated.~~

AT&T – Kentucky -- Copper and fiber optic intrastate telecommunications. The Company currently has facility attached to Kentucky Utility poles located along Georgetown Street that will require adjustment due to the realignment of the Georgetown Street intersection with Newtown Pike. Unfortunately, until the adjustments to the KU facility have been completed, the Company is unable to proceed with its adjustments. ~~Therefore, until the KU facility has been relocated, the Company cannot determine a beginning date, and a completion date cannot be estimated.~~

Windstream Communications -- Copper and fiber optic intrastate telecommunications. While a portion of the Company's facility may be affected by the work along Newtown Pike, adjustments have been made to the roadway plans to avoid relocation of the underground facility along the eastern side of Newtown Pike. ~~However, the Company's relocation will also involve the removal and placement of a 900-pair facility from approximately 4th Street to Loudon Avenue; in addition to, the relocation/adjustment of facility located along 4th Street, Loudon Avenue, and Georgetown Street. Otherwise, it is anticipated that the majority of the Company's relocations will be along 4th Street, and the new intersection of Newtown Pike / Georgetown Street / 4th Street. The utility relocation work along 4th Street has only recently been determined necessary; and, only due to the sight-distance requirements for the reconfigured railroad crossing lights and signal. With the exception of a Kentucky Utilities Transmission guy-pole (located at approximate station 56+80, and approximately 17 feet left) and anchor, all road, curb, and sidewalk work was intended to be accomplished while the utility facilities, located along the southwest side of the proposed 4th Street, remained as they were. And it appears that a significant portion of that work can still be accomplished while KU-Transmission places a new temporary guy-pole and anchor, to allow the removal of the existing one. The relocation work along 4th Street is a recent addition due to the return of 4th Street to two way traffic flow, and the necessary adjustment of the railroad crossing signals and gates. Unfortunately, the Company has not yet completed their review of the project, and its impact on their facility. Consequently, the extent of the project's impact to their facility has not been completely determined. Additionally, until the Company has presented a relocation plan and estimate, a beginning date cannot be determined, and a completion date cannot be estimated.~~The Company has delivered the relocation plans and estimate associated with the work along Newtown Pike. Currently, those documents are under review, the relocation agreement will be prepared and forwarded to the Company for signature by the end of the year (2012). Based on this and the Company's estimated time for relocation, the Company has been assigned a completion date of April 1, 2013.

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

FAYETTE COUNTY FD39 034 85884
NEWTOWN PIKE (KY-922)
WIDEN NEWTOWN PIKE TO FIVE LANE URBAN ROADWAY AT NEW BCTC CAMPUS
ENTRANCE, INCLUDING WORK ON W. LOUDON, W. FOURTH ST., AND
GEORGETOWN ST.
ITEM NUMBER – 7-375.00

Kentucky Data Link -- Copper and fiber optic interstate/intrastate telecommunications. While it is anticipated that the Company's facility will not be affected by the project, the Company has not yet completed their review of the project, and its impact on their facility. Consequently, the extent of the project's impact to their facility has not been completely determined. ~~Additionally, until the Company has presented a relocation plan and estimate, a beginning date cannot be determined, and a completion date cannot be estimated.~~

TW Telecom -- Copper and fiber optic interstate/intrastate telecommunications. While it is anticipated that the Company's facility will not be affected by the project, the Company has not yet completed their review of the project, and its impact on their facility. Consequently, the extent of the project's impact to their facility has not been completely determined. ~~Additionally, until the Company has presented a relocation plan and estimate, a beginning date cannot be determined, and a completion date cannot be estimated.~~

This may not be a complete list of the Utility Companies / Facilities within the project limits.

The Department will consider submission of a bid as the Contractor's agreement to not make any claims for additional compensation due to delays or other conditions created by the operations of the Utility Companies. Working days will not be charged for those days on which work on the Utility facilities is delayed, as provided in the current edition of the KY Standard Specifications for Road and Bridge Construction. Should a difference of opinion arise as to the rights of the Contractor and others working within the limits of, or adjacent to the project, the KYTC Resident Engineer will decide as to the respective rights of the various parties involved in order to assure the completion of the Department's work in general harmony and in a satisfactory manner, and his decision shall be final and binding upon the Contractor. |

**THE FOLLOWING COMPANIES HAVE FACILITIES TO BE RELOCATED/ADJUSTED BY THE ROAD
CONTRACTOR AS INCLUDED IN THIS CONTRACT**

LEXINGTON FAYETTE URBAN COUNTY GOVERNMENT – Sanitary Sewer. The City has arranged to include the installation of certain sanitary sewer facilities in the Cabinet's roadway contract. These items are detailed in the Proposal documents. |

SPECIAL NOTES FOR UTILITY CLEARANCE

IMPACT ON CONSTRUCTION

**FAYETTE COUNTY FD39 034 85884
NEWTOWN PIKE (KY-922)
WIDEN NEWTOWN PIKE TO FIVE LANE URBAN ROADWAY AT NEW BCTC CAMPUS
ENTRANCE, INCLUDING WORK ON W. LOUDON, W. FOURTH ST., AND
GEORGETOWN ST.
ITEM NUMBER – 7-375.00**

SPECIAL CAUTION NOTE – PROTECTION OF UTILITIES

The contractor will be responsible for contacting all utility facility owners on the subject project to coordinate his activities. The contractor will coordinate his activities to minimize and, where possible, avoid conflicts with utility facilities. The Kentucky Transportation Cabinet maintains the right to remove or alter portions of this contract if a utility conflict occurs.

The utility facilities as noted in the previous section(s) have been determined using data garnered by varied means and with varying degrees of accuracy: from the facility owners, a result of S.U.E., field inspections, and/or reviews of record drawings. The facilities defined may not be inclusive of all utilities in the project scope and are not Level A quality, unless specified as such. It is the contractor's responsibility to verify all utilities and their respective locations before excavating.

BEFORE YOU DIG

The contractor is instructed to call 1-800-752-6007 to reach KY 811, the one-call system for information on the location of existing underground utilities. The call is to be placed a minimum of two (2) and no more than ten (10) business days prior to excavation. The contractor should be aware that owners of underground facilities are not required to be members of the KY 811 one-call Before-U-Dig (BUD) service. The contractor must coordinate excavation with the utility owners, including those whom do not subscribe to KY 811. It may be necessary for the contractor to contact the County Court Clerk to determine what utility companies have facilities in the area.

Please Note: The information presented in this Utility Note is informational in nature and the information contained herein is not guaranteed.