



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

September 10, 2012

CALL NO. 318
CONTRACT ID NO. 121038
ADDENDUM # 1

Subject: Daviess County, FD04 SPP 030 9005 015-024
Letting September 14, 2012

- (1) Added - Shoulder Rumble Strips - Page 206(a) of 239
- (2) Revised - Bid Items - Pages 236-239 of 239

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

**Shoulder Rumble Strips-Sawed Summary
 Audubon Parkway Rehabilitation Project**

Roadway	2696
	Shoulder Rumble Strips- Sawed
	(Lin. Ft.)
Audubon Parkway Eastbound	78,522
Audubon Parkway Westbound	78,863
KY 1554	2,471
KY 1554 Ramp A	3,244
KY 1554 Ramp B	3,321
KY 1554 Ramp C	3,907
KY 1554 Ramp D	2,760
US 60 Ramp A	2,690
US 60 Ramp B	2,273
US 60 Ramp C	4,006
US 60 Ramp D	3,392
Project Total	185,449

CONTRACT ID: 121038
COUNTY: DAVIESS
PROPOSAL: FD04 SPP 030 9005 015-024

PAGE: 1
LETTING: 09/14/12
CALL NO: 318

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY						
0010	00078	CRUSHED AGGREGATE SIZE NO 2	300.000	TON		
0020	00309	CL2 ASPH SURF 0.50D PG64-22	12,977.000	TON		
0030	00462	CULVERT PIPE-18 IN	52.000	LF		
0040	01310	REMOVE PIPE	52.000	LF		
0050	01450	S & F BOX INLET-OUTLET-18 IN	2.000	EACH		
0060	01691	FLUME INLET TYPE 2	6.000	EACH		
0070	01718	REMOVE INLET FLUME INLET	6.000	EACH		
0080	01890	ISLAND HEADER CURB TYPE 1	8,366.000	LF		
0090	01982	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	592.000	EACH		
0100	01983	DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL YELLOW	03.000	EACH		
0110	02014	BARRICADE-TYPE III	20.000	EACH		
0120	02058	REMOVE PCC PAVEMENT	22,194.000	SQYD		
0130	02060	PCC PAVEMENT DIAMOND GRINDING	224,790.000	SQYD		
0140	02073	JPC PAVEMENT-9 IN	22,194.000	SQYD		
0150	02115	SAW-CLEAN-RESEAL TVERSE JOINT	40,470.000	LF		
0160	02116	SAW-CLEAN-RESEAL LONGIT JOINT	86,238.000	LF		
0170	02237	DITCHING	5,000.000	LF		
0180	02352	GUARDRAIL-STEEL W BEAM-D FACE	900.000	LF		
0190	02360	GUARDRAIL TERMINAL SECTION NO 1	1.000	EACH		
0200	02363	GUARDRAIL CONNECTOR TO BRIDGE END TY A	13.000	EACH		

CONTRACT ID: 121038
COUNTY: DAVIESS
PROPOSAL: FD04 SPP 030 9005 015-024

PAGE: 2
LETTING: 09/14/12
CALL NO: 318

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0210	02365	CRASH CUSHION TYPE IX-A	4.000	EACH		
0220	02367	GUARDRAIL END TREATMENT TYPE 1	3.000	EACH		
0230	02369	GUARDRAIL END TREATMENT TYPE 2A	32.000	EACH		
0240	02373	GUARDRAIL END TREATMENT TYPE 3	2.000	EACH		
0250	02381	REMOVE GUARDRAIL	35,278.000	LF		
0260	02387	GUARDRAIL CONNECTOR TO BRIDGE END TY A-1	5.000	EACH		
0270	02391	GUARDRAIL END TREATMENT TYPE 4A	2.000	EACH		
0280	02484	CHANNEL LINING CLASS III	120.000	TON		
0290	02562	SIGNS	1,800.000	SQFT		
0300	02600	FABRIC GEOTEXTILE TY IV FOR PIPE	90.000	SQYD	2.00	180.00
0310	02650	MAINTAIN & CONTROL TRAFFIC	(1.00)	LS		
0320	02671	PORTABLE CHANGEABLE MESSAGE SIGN	6.000	EACH		
0330	02676	MOBILIZATION FOR MILL & TEXT	(1.00)	LS		
0340	02677	ASPHALT PAVE MILLING & TEXTURING	12,977.000	TON		
0341	02696	SHOULDER RUMBLE STRIPS-SAWED (ADDED: 9-10-12)	185,449.000	LF		
0350	02726	STAKING	(1.00)	LS		
0360	02775	ARROW PANEL	4.000	EACH		
0370	03225	TUBULAR MARKERS	560.000	EACH		
0380	04933	TEMP SIGNAL 2 PHASE	2.000	EACH		
0390	05950	EROSION CONTROL BLANKET	37,000.000	SQYD		
0400	06417	FLEXIBLE DELINEATOR POST-W	218.000	EACH		

CONTRACT ID: 121038
COUNTY: DAVIESS
PROPOSAL: FD04 SPP 030 9005 015-024

PAGE: 3
LETTING: 09/14/12
CALL NO: 318

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0410	06418	FLEXIBLE DELINEATOR POST-Y	112.000	EACH		
0420	06511	PAVE STRIPING-TEMP PAINT-6 IN	274,656.000	LF		
0430	06549	PAVE STRIPING-TEMP REM TAPE-B	5,000.000	LF		
0440	06550	PAVE STRIPING-TEMP REM TAPE-W	5,000.000	LF		
0450	06551	PAVE STRIPING-TEMP REM TAPE-Y	5,000.000	LF		
0460	06592	PAVEMENT MARKER TYPE V-B W/R	1,076.000	EACH		
0470	06593	PAVEMENT MARKER TYPE V-B Y/R	335.000	EACH		
0480	06600	REMOVE PAVEMENT MARKER TYPE V	1,096.000	EACH		
0490	10020NS	FUEL ADJUSTMENT	12,473.000	DOLL	1.00	12,473.00
0500	10030NS	ASPHALT ADJUSTMENT	23,359.000	DOLL	1.00	23,359.00
0510	20099ES842	PAVE MARK TEMP PAINT STOP BAR	48.000	LF		
0520	20192ED	REM ASPHALT WEDGE CURB	8,666.000	LF		
0530	20409ED	SLIP RAMP #1	(1.00)	LS		
0540	20409ED	SLIP RAMP #2	(1.00)	LS		
0550	20409ED	SLIP RAMP #3	(1.00)	LS		
0560	20409ED	SLIP RAMP #4	(1.00)	LS		
0570	20467NS112	RELOCATE TUBULAR MARKER	560.000	EACH		
0580	20545ND	TEMP MEDIAN CROSSOVER	4.000	EACH		
0590	21802EN	G/R STEEL W BEAM-S FACE (7 FT POST)	34,087.500	LF		
0600	23143ED	KPDES PERMIT AND TEMP EROSION CONTROL	(1.00)	LS		
0610	23237EN10W	WATERBLAST STRIPE REMOVAL	137,328.000	LF		

CONTRACT ID: 121038
COUNTY: DAVIESS
PROPOSAL: FD04 SPP 030 9005 015-024

PAGE: 4
LETTING: 09/14/12
CALL NO: 318

LINE NO	ITEM	DESCRIPTION	APPROXIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
0620	23394EC	CRASH CUSHION TY VI CLASS C TL3-1	1.000	EACH		
0630	23845EC	SAW AND SEAL ASPHALT JOINT	4,658.000	LF		
0640	24189ER	DURABLE WATERBORNE MARKING-6 IN W	120,377.000	LF		
0650	24190ER	DURABLE WATERBORNE MARKING-6 IN Y	111,652.000	LF		
0660	24191ER	DURABLE WATERBORNE MARKING-12 IN W	4,092.000	LF		
SECTION 0002 BRIDGE						
0670	03300	ELIMINATE TRANSVERSE JOINT	219.500	LF		
0680	08150	STEEL REINFORCEMENT	9,620.000	LB		
0690	08504	EPOXY SAND SLURRY	522.000	SQYD		
0700	08510	REM EPOXY BIT FOREIGN OVERLAY	1,218.000	SQYD		
0710	08526	CONC CLASS M FULL DEPTH PATCH	8.000	CUYD		
0720	08534	CONCRETE OVERLAY-LATEX	62.800	CUYD		
0730	08549	BLAST CLEANING	2,226.000	SQYD		
0740	08551	MACHINE PREP OF SLAB	642.000	SQYD		
0750	24094EC	PARTIAL DEPTH PATCHING	12.600	CUYD		
SECTION 0003 MOB AND DEMOB						
0760	02568	MOBILIZATION (NO MORE THAN 5%)		LUMP		
0770	02569	DEMOBILIZATION (AT LEAST 1.5%)		LUMP		
		TOTAL BID				