



**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

April 23, 2018

CALL NO. 318
CONTRACT ID NO. 182157
ADDENDUM # 2

Subject: Henderson County, FD05 051 041A 014-018
Letting April 27, 2018

- (1) Revised - Special Note - Pages 10 of 55
- (2) Revised - Summary Sheets- Pages 38-39 of 55
- (3) Revised - Bid Items- Pages 55 of 55

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mw
Enclosures



An Equal Opportunity Employer M/F/D

Milling and Paving operations must take place between the hours of 7pm to 7am, Monday thru Sunday.

The contractor must pave all asphalt that is mill before the section is opened to traffic.

The concrete work, sidewalks, entrances, etc. can be done during the day with only limited impact on Green Street and side City Streets. The contractor must submit a schedule of work to insure no major disruptions will occur. The lane closures on Green Street must be only while work is active and cannot proceed during 7am-9am and 2:30pm to 6pm during the weekday, and is permitted all hours of the weekend.

Loop installation and Thermoplastic markings must also follow paving hours of operations.

In addition to the holidays in the Spec book, no work will can take place during the following local festivals.

Tri-Fest April 20-22

W.C. Handy's Blue Festival June 11-16

Sandy Watkins Song Festival July 25-28

Bluegrass in the Park August 10-11

SPECIAL NOTE

Follow the existing joints on all side roads along mainline. Mill and pave back to the existing joints. The only exception is Dixon and MLK and they need to pull back to newer joint previously paved by the City.

PROPOSAL BID ITEMS

Report Date 4/23/18

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	300.00	TON		\$	
0020	02562		TEMPORARY SIGNS	1,050.00	SQFT		\$	
0030	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0040	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0050	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0060	02677		ASPHALT PAVE MILLING & TEXTURING	7,220.00	TON		\$	
0070	02720		SIDEWALK-4 IN CONCRETE	372.00	SQYD		\$	
0080	02775		ARROW PANEL	2.00	EACH		\$	
0090	03240		BASE FAILURE REPAIR (REVISED: 4-23-18)	475.00	SQYD		\$	
0100	04792		CONDUIT-1 IN	80.00	LF		\$	
0110	04793		CONDUIT-1 1/4 IN	165.00	LF		\$	
0120	04795		CONDUIT-2 IN	85.00	LF		\$	
0130	04811		ELECTRICAL JUNCTION BOX TYPE B	8.00	EACH		\$	
0140	04820		TRENCHING AND BACKFILLING	105.00	LF		\$	
0150	04821		OPEN CUT ROADWAY	205.00	LF		\$	
0160	04830		LOOP WIRE	3,200.00	LF		\$	
0170	04850		CABLE-NO. 14/1 PAIR	1,875.00	LF		\$	
0180	04895		LOOP SAW SLOT AND FILL	785.00	LF		\$	
0190	06510		PAVE STRIPING-TEMP PAINT-4 IN	50,000.00	LF		\$	
0200	06514		PAVE STRIPING-PERM PAINT-4 IN	34,000.00	LF		\$	
0210	06566		PAVE MARKING-THERMO X-WALK-12 IN	3,642.00	LF		\$	
0220	06568		PAVE MARKING-THERMO STOP BAR-24IN	667.00	LF		\$	
0230	06574		PAVE MARKING-THERMO CURV ARROW (REVISED: 4-23-18)	20.00	EACH		\$	
0240	06575		PAVE MARKING-THERMO COMB ARROW	3.00	EACH		\$	
0250	06600		REMOVE PAVEMENT MARKER TYPE V	90.00	EACH		\$	
0260	10020NS		FUEL ADJUSTMENT	11,238.00	DOLL	\$1.00	\$	\$11,238.00
0270	10030NS		ASPHALT ADJUSTMENT	28,227.00	DOLL	\$1.00	\$	\$28,227.00
0280	21543EN		BORE AND JACK CONDUIT	205.00	LF		\$	
0290	23158ES505		DETECTABLE WARNINGS (NEW)	275.00	SQFT		\$	
0300	23158ES505		DETECTABLE WARNINGS (RETROFIT)	414.00	SQFT		\$	
0310	23176ES403		CL4 ASPH SURF 0.5A PG76-22 (REVISED: 4-11-18)	7,220.00	TON		\$	
0320	24890EC		SIDEWALK-8 IN CONCRETE	494.00	SQYD		\$	
0330	24963ED		LOOP TEST	6.00	EACH		\$	
0340	24970EC		TRACKLESS TACK	22.00	TON		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0350	02569		DEMOBILIZATION	1.00	LS		\$	