



**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

January 22, 2019

CALL NO. 325
CONTRACT ID NO. 192019
ADDENDUM # 1

Subject: DAVIESS COUNTY, FD05 030 0054 001-003
Letting January 25, 2019

- (1) Revised - Traffic Loop Summary - Page 44 of 61
- (2) Revised - Proposal Bid Items - Pages 61-61(a) of 61

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures



An Equal Opportunity Employer M/F/D

**Daviss County
TRAFFIC LOOP SUMMARY
LOOP SUMMARY FOR ASPHALT PAVEMENT**

INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT 1 INCH LF		PVC CONDUIT 1 1/4 INCH LF		PVC CONDUIT 2 INCH LF		CABLE NO. 14 LF	JUNCTION TYPE EA	Trenching and Backfilling LF	Loop Test EA	NOTES
			LF	EA	LF	EA	LF	EA					
Springs													
North Leg	250	624	10		40	0	0	200	1	40	2	(2) 6 ft x 30 ft Loop @ Stop Bar	
East Leg	150	300	10		50	0	0	400	1	50	1	(1) 6 ft x 30 ft Loop @ Stop Bar	
South Leg	300	624	10		30	0	0	400	1	30	2	(2) 6 ft x 30 ft Loop @ Stop Bar at left	
West Leg	150	300	10		20	0	0	500	1	20	1	(1) 6 ft x 30 ft Loop @ left turn	
Total	850	1848	40		140	0	0	1140	4	140	6		

INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT 1 INCH LF		PVC CONDUIT 1 1/4 INCH LF		PVC CONDUIT 2 INCH LF		CABLE NO. 14 LF	JUNCTION TYPE EA	Trenching and Backfilling LF	Loop Test EA	NOTES
			LF	EA	LF	EA	LF	EA					
byers													
North Leg	250	624	10		20	0	0	370	1	20	2	(2) 6 ft x 30 ft Loop @ Stop Bar	
East Leg	150	300	10		50	0	0	400	1	50	1	(1) 6 ft x 30 ft Loop @ Stop Bar	
South Leg	250	624	10		30	0	0	300	1	30	2	(2) 6 ft x 30 ft Loop @ Stop Bar at left	
West Leg	150	300	10		20	0	0	40	1	20	1	(1) 6 ft x 30 ft Loop @ left turn	
Total	800	1848	40		120	0	0	1110	4	120	6		

INTERSECTION	SAW, SLOT AND FILL LF	LOOP WIRE LF	CONDUIT 1 INCH LF		PVC CONDUIT 1 1/4 INCH LF		PVC CONDUIT 2 INCH LF		CABLE NO. 14 LF	JUNCTION TYPE EA	Trenching and Backfilling LF	Loop Test EA	NOTES
			LF	EA	LF	EA	LF	EA					
Heartlands crossing													
North Leg	564	1392	10		40	0	0	200	1	40	4	(4) 6 ft x 30 ft Loop @ Stop Bar	
East Leg	150	300	10		50	0	0	200	1	50	1	(1) 6 ft x 30 ft Loop @ Stop Bar	
South Leg	522	1008	10		50	0	0	930	1	50	3	(3) 6 ft x 30 ft Loop @ Stop Bar at left	
West Leg	150	300	10		20	0	0	200	1	20	1	(1) 6 ft x 30 ft Loop @ left turn	
Total	1386	3000	40		160	0	0	1530	4	160	9		

total 3036 6696 120 420 0 3780 12 420 21

- NOTES:**
- Quantities are for estimating purposes only. The Contractor shall field measure and inspect items to verify quantities.
 - 2 - 1 1/4 inch conduits may be used in place of 2" conduit. Field verify conduit to match existing facilities/tie-in to poles/cabinets.
 - Only replace existing conduit if damaged. Always replace conduit to the roadway.

PROPOSAL BID ITEMS

192019

Page 1 of 2

Report Date 1/22/19

Section: 0001 - MICROSURFACE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	24957EC		MICROSURFACING-SURFACE COURSE - TYPE B	53,206.00	SQYD		\$	

Section: 0002 - THINLAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0020	00356		ASPHALT MATERIAL FOR TACK	14.00	TON		\$	
0030	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0040	02677		ASPHALT PAVE MILLING & TEXTURING	80.00	TON		\$	
0050	23307EC		CL3 ASPH SURF NO.4B PG64-22	1,830.00	TON		\$	

Section: 0003 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0060	00001		DGA BASE	10.00	TON		\$	
0070	02562		TEMPORARY SIGNS	450.00	SQFT		\$	
0080	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0090	02720		SIDEWALK-4 IN CONCRETE	360.00	SQYD		\$	
0100	02775		ARROW PANEL	1.00	EACH		\$	
0105	04792		CONDUIT-1 IN (ADDED: 1-22-19)	120.00	LF		\$	
0120	04811		ELECTRICAL JUNCTION BOX TYPE B (REVISED: 1-22-19)	12.00	EACH		\$	
0125	04820		TRENCHING AND BACKFILLING (ADDED: 1-22-19)	420.00	LF		\$	
0130	04830		LOOP WIRE (REVISED: 1-22-19)	6,696.00	LF		\$	
0140	04850		CABLE-NO. 14/1 PAIR (REVISED: 1-22-19)	3,780.00	LF		\$	
0150	04895		LOOP SAW SLOT AND FILL (REVISED: 1-22-19)	3,036.00	LF		\$	
0160	06510		PAVE STRIPING-TEMP PAINT-4 IN	60,000.00	LF		\$	
0170	06514		PAVE STRIPING-PERM PAINT-4 IN	30,000.00	LF		\$	
0180	06566		PAVE MARKING-THERMO X-WALK-12 IN	695.00	LF		\$	
0190	06568		PAVE MARKING-THERMO STOP BAR-24IN	450.00	LF		\$	
0200	06569		PAVE MARKING-THERMO CROSS-HATCH	1,000.00	SQFT		\$	
0210	06573		PAVE MARKING-THERMO STR ARROW	2.00	EACH		\$	
0220	06574		PAVE MARKING-THERMO CURV ARROW	27.00	EACH		\$	
0230	06575		PAVE MARKING-THERMO COMB ARROW	2.00	EACH		\$	
0240	06576		PAVE MARKING-THERMO ONLY	1.00	EACH		\$	
0250	06600		REMOVE PAVEMENT MARKER TYPE V	540.00	EACH		\$	
0260	23158ES505		DETECTABLE WARNINGS	152.00	SQFT		\$	
0265	24900EC		PVC CONDUIT-1 1/4 IN-SCHEDULE 80 (ADDED: 1-22-19)	420.00	LF		\$	
0267	24963ED		LOOP TEST (ADDED: 1-22-19)	21.00	EACH		\$	

192019

PROPOSAL BID ITEMS

Report Date 1/22/19

Page 2 of 2

Section: 0004 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0270	02569		DEMOBILIZATION	1.00	LS		\$	