



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

April 11, 2013

CALL NO. 338
CONTRACT ID NO. 132077
ADDENDUM # 1

Subject: Mason County, FD05 081 0009 007-011
Letting April 19, 2013

- (1) Revised - Pavement Markings Summary - Page 31 of 67
- (2) Revised - Signal Loop Summary - Page 32 of 67
- (3) Revised - Special Note - Page 32(a) of 67
- (4) Revised - Bid Items - Page 67 of 67

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith
Acting Director
Division of Construction Procurement

RG:ks
Enclosures



An Equal Opportunity Employer M/F/D

Mason County
THERMOPLASTIC INTERSECTION PAVEMENT MARKINGS SUMMARY
FD05 081 0009 007-011

MPT.	X-WALKS	STP BARS	ARROWS			"ONLY"	CATRAXX	RAILROAD		NOTES
	6 INCH LF	24 INCH LF	CURVE EA	STR EA	COMB EA	EA	6 INCH LF	"R" 6 FOOT EA	CROSS BUCK 16" LF	
7.367			1							
7.376			1							
8.939			1							
8.947						1				
8.954			1							
8.986			1							
8.994			1			1				
9.001			1							
9.009			1							
9.201			1							
9.214			1							
9.226			1							
9.242			1							
9.257			1							
9.289			2							
9.303			1							
9.319			1							
9.359			1							
9.373			1							
9.386			1							
9.401			1							
9.417			1							
9.422		36								
9.448		48								
9.453			2							
9.468			1							
9.483			1							
9.556			1							
9.572			1			1				
9.59			2							
9.625			2							
9.636						1				
9.645			2							
9.787			1							
9.806						1				
9.825			1							
9.834		36								
9.854		36								
9.864			1							
9.901			1							
10.011			2							
10.025						2				
10.039			2							
10.195			1							
10.217			1		1					
TOTALS		156	44		1	7				

MASON COUNTY
 SIGNAL LOOP AND ADVANCE WARNING FLASHER SUMMARY
 FD05 081 0009 007 011

BEGIN MILE POST	END	SAW SLOT AND FILL	LOOP SIZE	LOOP WIRE	CABLE NO. 14/1 Pair	ADVANCE WARNING FLASHER			ELECTRIC JUNCTION BOX B
						CABLE 14/3 WIRE	1 1/4" STEEL CONDUIT	TRENCHING	
7.375		80	2-6 X 6	225					
7.375	7.472				2560	515	515	512	1
7.652	7.75				2580	520	520	517	1
7.75		80	2-6 X 6	225					
8.792	8.888				2540	510	510	507	1
8.792		80	2-6 X 6	225					
9.051	9.151				2620	530	530	528	1
9.151		80	2-6 X 6	225					
9.853		190	1-6x20 & 1-6x30	550					
9.895		70	2-6x6	160					
9.926		70	2-6x6	160					
10.179		70	2-6x6	160					
TOTALS			720	1930	10300	2075	2075	2064	4

**SPECIAL NOTE FOR
ADVANCE WARNING FLASHER (AWF) COMPONENTS**

Use the existing conduit that is in place at the locations in the Loop Summary. The quantities that are shown for Trenching, 14/3 wire and 1 1/4" conduit are included in case the existing hardware is not useable and new hardware will need to be installed.

PROPOSAL BID ITEMS

Report Date 4/11/13

Section: 0001 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	802.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	1,960.00	TON		\$	
0030	00388		CL3 ASPH SURF 0.38B PG64-22	6,980.00	TON		\$	
0040	02562		TEMPORARY SIGNS	250.00	SQFT		\$	
0050	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0060	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0070	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0080	02677		ASPHALT PAVE MILLING & TEXTURING	6,100.00	TON		\$	
0090	02696		SHOULDER RUMBLE STRIPS-SAWED	32,500.00	LF		\$	
0100	02775		ARROW PANEL	4.00	EACH		\$	
0110	04793		CONDUIT-1 1/4 IN	2,075.00	LF		\$	
0120	04811		ELECTRICAL JUNCTION BOX TYPE B	4.00	EACH		\$	
0130	04820		TRENCHING AND BACKFILLING	2,064.00	LF		\$	
0140	04830		LOOP WIRE(REVISED: 4-11-13)	1,930.00	LF		\$	
0150	04842		CABLE-NO. 14/3C	2,075.00	LF		\$	
0151	04850		CABLE-NO. 14/1 PAIR(ADDED: 4-11-13)	10,300.00	LF		\$	
0160	04895		LOOP SAW SLOT AND FILL	720.00	LF		\$	
0170	06510		PAVE STRIPING-TEMP PAINT-4 IN	40,000.00	LF		\$	
0180	06514		PAVE STRIPING-PERM PAINT-4 IN	80,000.00	LF		\$	
0190	06568		PAVE MARKING-THERMO STOP BAR-24IN	156.00	LF		\$	
0200	06574		PAVE MARKING-THERMO CURV ARROW	44.00	EACH		\$	
0210	06575		PAVE MARKING-THERMO COMB ARROW	1.00	EACH		\$	
0220	06576		PAVE MARKING-THERMO ONLY	7.00	EACH		\$	
0230	06589		PAVEMENT MARKER TYPE V-MW	500.00	EACH		\$	
0240	06591		PAVEMENT MARKER TYPE V-BY	210.00	EACH		\$	
0250	06600		REMOVE PAVEMENT MARKER TYPE V	1,300.00	EACH		\$	
0260	10020NS		FUEL ADJUSTMENT	15,164.00	DOLL	\$1.00	\$	\$15,164.00
0270	10030NS		ASPHALT ADJUSTMENT	38,087.00	DOLL	\$1.00	\$	\$38,087.00

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	FP	AMOUNT
0280	02569		DEMOBILIZATION	1.00	LS		\$	