



Matthew G. Bevin
Governor

**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**
Frankfort, Kentucky 40622
www.transportation.ky.gov/

Greg Thomas
Secretary

April 18, 2019

CALL NO. 340
CONTRACT ID NO. 192163
ADDENDUM # 1

Subject: WARREN COUNTY, FD05 114 0068 008-010
Letting April 26, 2019

- (1) Revised - Special Notes - Pages 10-11 of 92
- (2) Revised - Proposal Bid Items - Page 92 of 92

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures



An Equal Opportunity Employer M/F/D

INSTALL RADAR PRESENCE DETECTOR TYPE A

Install Radar Presence Detector Type A shall consist of installation of a pole mounted radar presence sensor, sensor mounting bracket, sensor cables, interface boxes, lead-in cable, connectors (furnished by contractor), and controller interface assembly. Radar Presence Detector Type A bid item shall include all labor required to provide a functional detection system. Radar Presence Detector Type A shall be installed and wired in accordance with the manufacturer's instructions. After the detector is installed and before the detector is powered on, the contractor shall coordinate with District Traffic Division's representatives to schedule a time to perform the detector setup. The contractor shall double check to verify that all wiring is correctly installed and connected before scheduling the setup work. Representatives from KYTC and/or the manufacturer or sales representative will assist with setup and calibration. The contractor shall provide a bucket truck and operators at this time for final aiming of the sensors. The contractor shall provide individuals capable of operating the setup software and learning the setup process so that future installations may be completed without assistance from others.

Quantity per intersection:

SB Ramp	3
NB Ramp	3
Dishman	3
Turner	4
Woodmont	4
US 231	4

**RECOMMENDATION FOR PICKUP OF ITEMS TO BE INSTALLED
ON TRAFFIC SIGNALS/LIGHTING**

Item Number: N/a

County: warren

Description: rehab us 68 from mp 8 to 10

Special items		
1	radar presense detector type A	

Electrical Contractor Name _____

Electrical Contractor Supervisor _____

Project Engineer _____

Project Engineer attests that the mentioned contractor is the actual electrical contractor on this project

Signature of Project Engineer or Designee _____

Contact number for Supervisor _____

Contact number for Project Engineer _____

PROPOSAL BID ITEMS

192163

Page 1 of 1

Report Date 4/18/19

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	89.00	TON		\$	
0020	02562		TEMPORARY SIGNS	290.00	SQFT		\$	
0030	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0040	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0050	02676		MOBILIZATION FOR MILL & TEXT	1.00	LS		\$	
0060	02677		ASPHALT PAVE MILLING & TEXTURING	3,255.00	TON		\$	
0070	02720		SIDEWALK-4 IN CONCRETE	176.00	SQYD		\$	
0080	02775		ARROW PANEL	1.00	EACH		\$	
0090	04793		CONDUIT-1 1/4 IN	40.00	LF		\$	
0100	04795		CONDUIT-2 IN	10.00	LF		\$	
0110	04820		TRENCHING AND BACKFILLING	40.00	LF		\$	
0120	04829		PIEZOELECTRIC SENSOR	4.00	EACH		\$	
0130	04830		LOOP WIRE	2,700.00	LF		\$	
0140	04895		LOOP SAW SLOT AND FILL	560.00	LF		\$	
0150	06510		PAVE STRIPING-TEMP PAINT-4 IN	28,500.00	LF		\$	
0160	06514		PAVE STRIPING-PERM PAINT-4 IN	28,500.00	LF		\$	
0170	06516		PAVE STRIPING-PERM PAINT-8 IN	300.00	LF		\$	
0180	06544		PAVE STRIPING-THERMO-8 IN W	125.00	LF		\$	
0190	06568		PAVE MARKING-THERMO STOP BAR-24IN	410.00	LF		\$	
0200	06573		PAVE MARKING-THERMO STR ARROW	2.00	EACH		\$	
0210	06574		PAVE MARKING-THERMO CURV ARROW	22.00	EACH		\$	
0220	06576		PAVE MARKING-THERMO ONLY	2.00	EACH		\$	
0230	06600		REMOVE PAVEMENT MARKER TYPE V	440.00	EACH		\$	
0240	10020NS		FUEL ADJUSTMENT	5,205.00	DOLL	\$1.00	\$	\$5,205.00
0250	10030NS		ASPHALT ADJUSTMENT	13,074.00	DOLL	\$1.00	\$	\$13,074.00
0260	20359NN		GALVANIZED STEEL CABINET	1.00	EACH		\$	
0270	20360ES818		WOOD POST	3.00	EACH		\$	
0280	20391NS835		ELECTRICAL JUNCTION BOX TYPE A	1.00	EACH		\$	
0290	20468EC		ELECTRICAL JUNCTION BOX-10 X 8 X 4	1.00	EACH		\$	
0300	22906ES403		CL3 ASPH SURF 0.38A PG64-22	3,255.00	TON		\$	
0310	23158ES505		DETECTABLE WARNINGS	110.00	SQFT		\$	
0320	23158ES505		DETECTABLE WARNINGS (RETROFIT)	20.00	SQFT		\$	
0330	24601EC		INSTALL RADAR PRESENCE DETECTOR TYPE A (REVISED: 4-18-19)	21.00	EACH		\$	
0340	24683ED		PAVE MARKING-THERMO DOTTED LANE EXTEN	34.00	LF		\$	
0350	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING	14.00	TON		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0360	02569		DEMOBILIZATION	1.00	LS		\$	