



Andy Beshear  
GOVERNOR

## TRANSPORTATION CABINET

200 Mero Street  
Frankfort, Kentucky 40601

Jim Gray  
SECRETARY

April 10, 2023

CALL NO. 341  
CONTRACT ID NO. 232982  
ADDENDUM # 1

Subject: Knott County, FD51 060 2029 002-005  
Letting April 27, 2023

- (1) Revised - Summary Sheet - Page 35 of 57
- (2) Revised - Proposal Bid Items - Page 57 of 57

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

**KNOTT COUNTY  
 SITE SUMMARY KY 2029**

Site	Begin Milepoint	End Milepoint	Length (FT)	Cribbing Depth (FT)	Excavation Width (FT)	Depth to Rock (FT)	Number of Rows	Rail Spacing (FT)	Cribbing Amount (SQ FT)	Drilled RR Rails (FT)	Excav. & Backfill (CU YD)	Geotextile Fabric Class1 (SQ YD)	DGA (TONS)	Channel Lining CL III (TONS)	Channel Lining CL II (TONS)				
1A	2.975	2.989	72	5	4	27	1	3	504	1013	54	112	14	0	0				
1B	3.019	3.029	48	10	4	27	1	3	576	689	72	128	10	0	0				
2	3.167	3.171	21	10	4	27	1	3	252	324	32	56	4	0	0				
3	3.633	3.641	39	10	4	27	1	3	468	567	58	104	8	0	0				
4	3.699	3.703	18	-	6	Site #4 to be repaired using channel lining						24	7	16	6				
5	3.825	3.843	40	-	4	Site #5 to be repaired using channel lining						36	10	16	6				
6	4.288	4.306	90	10	4	27	1	3	1080	1256	134	240	18	0	0				
<b>TOTALS</b>													<b>2880</b>	<b>3848</b>	<b>350</b>	<b>700</b>	<b>71</b>	<b>32</b>	<b>12</b>

**PROPOSAL BID ITEMS**

232982

Page 1 of 1

Report Date 4/10/23

**Section: 0001 - ROADWAY**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE (SHOULDERS AT CHANNEL LINING)	17.00	TON		\$	
0020	00001		DGA BASE (SHOULDERS AT DRILLED RR RAILS)	54.00	TON		\$	
0030	01982		DELINEATOR FOR GUARDRAIL MONO DIRECTIONAL WHITE	20.00	EACH		\$	
0040	02014		BARRICADE-TYPE III	6.00	EACH		\$	
0050	02351		GUARDRAIL-STEEL W BEAM-S FACE	575.00	LF		\$	
0060	02360		GUARDRAIL TERMINAL SECTION NO 1	3.00	EACH		\$	
0070	02371		GUARDRAIL END TREATMENT TYPE 7	4.00	EACH		\$	
0080	02383		REMOVE & RESET GUARDRAIL	62.50	LF		\$	
0090	02396		REMOVE GUARDRAIL END TREATMENT type 7	1.00	EACH		\$	
0100	02483		CHANNEL LINING CLASS II (REVISED 4-10-23)	12.00	TON		\$	
0110	02484		CHANNEL LINING CLASS III (REVISED 4-10-23)	32.00	TON		\$	
0120	02562		TEMPORARY SIGNS	256.00	SQFT		\$	
0130	02602		FABRIC-GEOTEXTILE CLASS 1 (REVISED 4-10-23)	700.00	SQYD		\$	
0140	02650		MAINTAIN & CONTROL TRAFFIC	1.00	LS		\$	
0150	03234		RAILROAD RAILS-DRILLED	3,848.00	LF		\$	
0160	03235		EXCAVATION AND BACKFILL	350.00	CUYD		\$	
0170	03236		CRIBBING	2,880.00	SQFT		\$	
0180	20257NC		SITE PREPARATION SITE 3	1.00	LS		\$	
0190	20257NC		SITE PREPARATION SITE 6	1.00	LS		\$	
0200	20257NC		SITE PREPARATION SITES 1A, 1B, & 2	1.00	LS		\$	
0210	20257NC		SITE PREPARATION SITES 4 & 5	1.00	LS		\$	
0220	21415ND		EROSION CONTROL SITE 6	1.00	LS		\$	
0230	21415ND		EROSION CONTROL sITES 1A, 1B, & 2	1.00	LS		\$	
0240	21415ND		EROSION CONTROL SITES 3	1.00	LS		\$	
0250	21415ND		EROSION CONTROL SITES 4 & 5	1.00	LS		\$	
0260	21554EN		EXCAVATION	25.00	CUYD		\$	

**Section: 0002 - DEMOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0270	02569		DEMOBILIZATION	1.00	LS		\$	