



Matthew G. Bevin
Governor

**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Greg Thomas
Secretary

October 22, 2018

CALL NO. 400
CONTRACT ID NO. 182912
ADDENDUM # 1

Subject: HARLAN COUNTY, 048GR18M080-FD04
Letting October 26, 2018

(1) Revised - Special Note - Page 23 of 65

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures



An Equal Opportunity Employer M/F/D

048B00110N, 048B00111N, 048B00101N, 048B00112N, 048B00113N, 048B00114N, 048B00115N, 048B00116N, 048B00117N, 048B00118N, 048B00119N, 048B00120N, 048B00121N, 048B00122N, 048B00123N, 048B00124N, 048B00162N, 048B00163N, 048B00164N, 048B00165N, 048B00161N and 048B00160N

Maintain one usable 12 foot minimum lane on US 119. Flagging or traffic signals shall be used. If traffic signals are used the Contractor shall use flagging to minimize impact on school bus traffic when school is in session. The Contractor shall be responsible for establishing the dates and times when school bus traffic will impact the job site. on Shoulder closures may be used. All lane closures and shoulder closures must be removed when not working. Lane closures for will be permitted to stay in place for the expansion joint replacement work if required for that bridge.

048B00126N and 048B00107N

Maintain a 12'-0" usable lane each direction on US 119. Shoulder closures may be used. All lane closures and shoulder closures must be removed when not working. Lane closures for will be permitted to stay in place for the expansion joint replacement work if required for that bridge.

MEASUREMENT.

A. Maintain and Control Traffic: The Department will measure the quantity by Lump Sum, completed and accepted.

PAYMENT.

A. Maintain and Control Traffic (02650). Payment of the contract lump sum amount for "maintain and control traffic" shall be full compensation for all items necessary to maintain and control traffic as specified for this project. All traffic control items shall remain the property of the contractor when the work is complete.