



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET

www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

April 9, 2021

CALL NO. 400
CONTRACT ID NO. 212954
ADDENDUM # 1

Subject: Ohio County, 092GR21M005 - FD04
Letting April 23, 2021

- (1) Revised - Special Notes - Page 9 of 41
- (2) Revised - Special Note for Maintain and Control Traffic - Page 22 of 41

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

**SPECIAL NOTES
DISTRICT NO. 2
BRIDGE CLEANING AND PAINTING
OHIO COUNTY
CID212954 ~ 092GR21M005 ~ SYP ITEM NO. 2-10060**

FD04 092 9001 B00072L 76.77

Ohio County ~ WK 9001 WB (Western Kentucky Parkway) over I-165

Geographic Coordinates

Latitude – 37° 23' 05.00''

Longitude – 086° 48' 33.00''

Description

52'-71'-71'-52' Steel Girder Spans, Drawing No. 18094

FD04 092 9001 B00072R 76.77

Ohio County ~ WK 9001 EB (Western Kentucky Parkway) over I-165

Geographic Coordinates

Latitude – 37° 23' 04.00''

Longitude – 086° 48' 33.00''

Description

52'-71'-71'-52' Steel Girder Spans, Drawing No. 18094

9. TRUCK MOUNTED DC ATTENUATOR

Any lane or shoulder closure will include the use of a Truck Mounted Attenuator placed between oncoming traffic and equipment or vehicles.

10. MISC.

The Contractor shall reduce the speed limit to **55 MPH**.

The use of Double Fine Zones may be used at the Contractor's discretion.

The Engineer may elect to use Variable Message Boards when necessary.

11. NARRATIVE

Single lane and shoulder closures on WN 9001 (route above) maintaining a 12' driving lane will be permitted for rigging and containment installation **only**.

Single lane and shoulder closures on I-165 (route below) maintaining a 12' driving lane will be permitted for all work. All lane closures must be removed when not working. Shoulder closures will be permitted to remain on I-165 (route below) see Items 6 and 7 in this note.

12. MEASUREMENT.

A. Maintain and Control Traffic: The Department will measure the quantity as "Lump Sum".

B. Portable Changeable Message Sign: The Department will measure the quantity for "Each".

13. PAYMENT.

A. Maintain and Control Traffic (02650): Payment of the contract lump sum amount for "maintain and control traffic" shall be full compensation for all items necessary to maintain and control traffic as specified for this project. All traffic control items shall remain the property of the contractor when the work is complete.

B. Portable Changeable Message Sign (02671): Payment at "each" shall be full compensation to furnish, install, maintain and remove all portable message signs as specified.