



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET
www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

October 13, 2021

CALL NO. 400
CONTRACT ID NO. 212417
ADDENDUM # 1

Subject: Todd County, 110GR21P103-FD05 & FD04
Letting October 22, 2021

- (1) Added - Special Note - Page of 23(a) of 53
- (2) Revised - Material Summary - Pages 30-31 of 53
- (3) Revised - Proposal Bid Items - Page 53 of 53

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

SPECIAL NOTE FOR STAKING

The Staking Bid Item and Note are for the intersection of KY 507 and KY 181 only.

In addition to the requirements of Section 201, perform the following:

1. Contrary to Section 201.03.01, perform items 1-3 usually performed by the Engineer; and
2. Field survey the existing pavement in order to establish the existing cross slopes, transitions and profile. Irregularities in the existing pavement are to be eliminated with the construction of a smooth line and grade of the new JPC pavement to ensure the best rideability possible.
3. Verify intersection and lane profile and alignment and prepare a Drainage Development Worksheet to provide for positive drainage upon completion of construction; and
4. Prior to incorporating into the work, obtain the Engineers approval of all designs and revisions to be provided by the Contractor; and
5. Produce and furnish to the Engineer "As Built" plans; and
6. Perform any and all other staking operations required to control and construct the work.

MATERIAL SUMMARY

CONTRACT ID: 212417

110GR21P103 - FD05 & FD04

MP11001812101

GREENVILLE ROAD (KY 181) BEGIN AT US 68 EXTENDING NORTH TO KY 507 ASPHALT RESURFACING, A DISTANCE OF 6.26 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00001	DGA BASE	600.00	TON
0010	00190	LEVELING & WEDGING PG64-22	638.00	TON
0015	00301	CL2 ASPH SURF 0.38D PG64-22	4,910.00	TON
0020	02562	TEMPORARY SIGNS	450.00	SQFT
0025	02650	MAINTAIN & CONTROL TRAFFIC - (FD05)	1.00	LS
0030	02676	MOBILIZATION FOR MILL & TEXT - (FD05)	1.00	LS
0035	02677	ASPHALT PAVE MILLING & TEXTURING	590.00	TON
0040	02697	EDGE LINE RUMBLE STRIPS	66,190.00	LF
0045	06510	PAVE STRIPING-TEMP PAINT-4 IN	64,550.00	LF
0050	06515	PAVE STRIPING-PERM PAINT-6 IN	129,100.00	LF
0055	06568	PAVE MARKING-THERMO STOP BAR-24IN	12.00	LF
0060	06574	PAVE MARKING-THERMO CURV ARROW	4.00	EACH
0065	06575	PAVE MARKING-THERMO COMB ARROW	4.00	EACH
0070	10020NS	FUEL ADJUSTMENT	8,636.00	DOLL
0075	10030NS	ASPHALT ADJUSTMENT	21,692.00	DOLL
0080	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	29.00	TON
0085	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 212417

110GR21P103 - FD05 & FD04

MP11001812102

GREENVILLE ROAD (181) BEGIN 100 FEET SOUTH OF THE KY 181/KY 507 INTERSECTION EXTENDING NORTH TO 100 FEET NORTH OF THE KY 181/KY 507 INTERSECTION GRADE & DRAIN WITH ASPHALT SURFACE, A DISTANCE OF .03 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0090	00001	DGA BASE	50.00	TON
0095	00078	CRUSHED AGGREGATE SIZE NO 2	60.00	TON
0100	00221	CL2 ASPH BASE 0.75D PG64-22	135.00	TON
0105	00301	CL2 ASPH SURF 0.38D PG64-22	65.00	TON
0110	00462	CULVERT PIPE-18 IN	135.00	LF
0115	01310	REMOVE PIPE	96.00	LF
0120	02187	SITE PREPARATION	1.00	EACH
0125	02562	TEMPORARY SIGNS	208.00	SQFT
0130	02607	FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	120.00	SQYD
0135	02625	REMOVE HEADWALL	2.00	EACH
0140	02650	MAINTAIN & CONTROL TRAFFIC - (FD04)	1.00	LS
0145	02676	MOBILIZATION FOR MILL & TEXT - (FD04)	1.00	LS
0150	02677	ASPHALT PAVE MILLING & TEXTURING	35.00	TON
0155	06568	PAVE MARKING-THERMO STOP BAR-24IN	24.00	LF
0160	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	2.00	TON
0165	02569	DEMOBILIZATION	1.00	LS
0170	02726	STAKING - (ADDED 10-13-2021)	1.00	LS

PROPOSAL BID ITEMS

212417

Page 1 of 1

Report Date 10/13/21

Section: 0001 - ROADWAY

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	650.00	TON		\$	
0020	00078		CRUSHED AGGREGATE SIZE NO 2	60.00	TON		\$	
0030	00190		LEVELING & WEDGING PG64-22	638.00	TON		\$	
0040	00221		CL2 ASPH BASE 0.75D PG64-22	135.00	TON		\$	
0050	00301		CL2 ASPH SURF 0.38D PG64-22	4,975.00	TON		\$	
0060	00462		CULVERT PIPE-18 IN	135.00	LF		\$	
0070	01310		REMOVE PIPE	96.00	LF		\$	
0080	02187		SITE PREPARATION	1.00	EACH		\$	
0090	02562		TEMPORARY SIGNS	658.00	SQFT		\$	
0100	02607		FABRIC-GEOTEXTILE CLASS 2 FOR PIPE	120.00	SQYD	\$2.00	\$	\$240.00
0110	02625		REMOVE HEADWALL	2.00	EACH		\$	
0120	02650		MAINTAIN & CONTROL TRAFFIC (FD04)	1.00	LS		\$	
0130	02650		MAINTAIN & CONTROL TRAFFIC (FD05)	1.00	LS		\$	
0140	02676		MOBILIZATION FOR MILL & TEXT (FD04)	1.00	LS		\$	
0150	02676		MOBILIZATION FOR MILL & TEXT (FD05)	1.00	LS		\$	
0160	02677		ASPHALT PAVE MILLING & TEXTURING	625.00	TON		\$	
0170	02697		EDGE LINE RUMBLE STRIPS	66,190.00	LF		\$	
0175	02726		STAKING (ADDED 10-13-2021)	1.00	LS		\$	
0180	06510		PAVE STRIPING-TEMP PAINT-4 IN	64,550.00	LF		\$	
0190	06515		PAVE STRIPING-PERM PAINT-6 IN	129,100.00	LF		\$	
0200	06568		PAVE MARKING-THERMO STOP BAR-24IN	36.00	LF		\$	
0210	06574		PAVE MARKING-THERMO CURV ARROW	4.00	EACH		\$	
0220	06575		PAVE MARKING-THERMO COMB ARROW	4.00	EACH		\$	
0230	10020NS		FUEL ADJUSTMENT	8,636.00	DOLL	\$1.00	\$	\$8,636.00
0240	10030NS		ASPHALT ADJUSTMENT	21,692.00	DOLL	\$1.00	\$	\$21,692.00
0250	24970EC		ASPHALT MATERIAL FOR TACK NON-TRACKING	31.00	TON		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0260	02569		DEMOBILIZATION	1.00	LS		\$	