



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET

www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

April 21, 2021

CALL NO. 401
CONTRACT ID NO. 212965
ADDENDUM # 1

Subject: HOPKINS - CALDWELL COUNTIES, 121GR21M004 - FD04
Letting April 23, 2021

- (1) Revised - Special Notes for Bridge Deck Restoration and Waterproofing - Page 11 of 82
- (2) Revised - Special Note for Contract Completion Date and Penalties on Bridge Repair Contracts - Page 27 of 82
- (3) Revised - Material Summary - Pages 51-55 of 82
- (4) Revised - Proposal Bid Items - Pages 78-82 of 82

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

**SPECIAL NOTES FOR BRIDGE DECK RESTORATION
AND WATERPROOFING**

SPECIAL NOTE FOR BRIDGE DECK RESTORATION AND WATERPROOFING
WITH CONCRETE OVERLAYS

SPECIAL NOTE FOR REPLACING EXPANSION JOINTS AND/OR INSTALLING
ARMORED EDGES FOR CONCRETE ON BRIDGES

SPECIAL NOTE FOR ELIMINATING TRANSVERSE JOINTS ON BRIDGES

SPECIAL NOTE FOR CONCRETE PATCHING REPAIR

SPECIAL NOTE FOR DECK DRAIN RETROFIT

SPECIAL NOTE FOR BRIDGE CLEANING AND PREVENTIVE MAINTENANCE

SPECIAL NOTE FOR CONTRACT COMPLETION DATE AND PENALTIES ON
BRIDGE REPAIR CONTRACTS

SPECIAL NOTE FOR MAINTAINING AND CONTROLLING TRAFFIC

**SPECIAL NOTE FOR CONTRACT COMPLETION DATE AND
PENALTIES ON BRIDGE REPAIR CONTRACTS**

1. **COMPLETION DATE.** The Contractor has the option of selecting the starting date for this Contract. Once selected, notify the Department in writing of the date selected at least two weeks prior to beginning work. All work is to be completed by the date listed below. An allotted number of Calendar days are assigned to each structure in this contract as shown below.

<u>STRUCTURE</u>	<u>NO. OF CALENDAR DAYS</u>	<u>COMPLETION DATE</u>
017B00037N	30	August 1, 2021
054B00161N	30	November 30, 2021
054B00073N	30	November 30, 2021
054B00019N	30	November 30, 2021
054B00018N	30	November 30, 2021

Contrary to Section 108.07.03, the Engineer will begin charging calendar days for a structure on the day the Contractor starts work or sets up traffic control on that particular structure. A **penalty of \$500.00 per day** will be assessed when the allotted number of calendar days is exceeded for each structure.

All construction must be completed in accordance with the weather limitations specified in Section 606 and/or Section 601 as applicable. No extension of Contract time will be granted due to inclement weather or temperature limitations that occur due to starting work on the Contract or a structure late in the construction season.

MATERIAL SUMMARY

CONTRACT ID: 212965

121GR21M004 - FD04

MB01700912101

MARION ROAD (KY 91) BRIDGE 017B00037N OVER I-69 AT MP 12.32 BRIDGE DECK RESTORATION & WATERPROOFING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0405	02562	TEMPORARY SIGNS - - 017B00037N	235.00	SQFT
0410	02650	MAINTAIN & CONTROL TRAFFIC - - 017B00037N	1.00	LS
0415	02653	LANE CLOSURE - - 017B00037N	2.00	EACH
0420	03298	EXPAN JOINT REPLACE 4 IN - - 017B00037N	89.40	LF
0425	03299	ARMORED EDGE FOR CONCRETE - - 017B00037N	89.40	LF
0430	03304	BRIDGE OVERLAY APPROACH PAVEMENT - - 017B00037N	667.00	SQYD
0435	04933	TEMP SIGNAL 2 PHASE - - 017B00037N	1.00	EACH
0440	06514	PAVE STRIPING-PERM PAINT-4 IN - - 017B00037N	1,298.00	LF
0445	06549	PAVE STRIPING-TEMP REM TAPE-B - - 017B00037N	2,000.00	LF
0450	06550	PAVE STRIPING-TEMP REM TAPE-W - - 017B00037N	2,000.00	LF
0455	06551	PAVE STRIPING-TEMP REM TAPE-Y - - 017B00037N	2,000.00	LF
0460	08150	STEEL REINFORCEMENT - - 017B00037N	270.00	LB
0465	08504	EPOXY SAND SLURRY - - 017B00037N	236.30	SQYD
0470	08510	REM EPOXY BIT FOREIGN OVERLAY - - 017B00037N	1,063.00	SQYD
0475	08526	CONC CLASS M FULL DEPTH PATCH - - 017B00037N	11.00	CUYD
0480	08534	CONCRETE OVERLAY-LATEX - - 017B00037N	44.30	CUYD
0485	08549	BLAST CLEANING - - 017B00037N	1,300.00	SQYD
0490	24094EC	PARTIAL DEPTH PATCHING - - 017B00037N	11.00	CUYD
0495	24981EC	BRIDGE CLEANING - - 017B00037N	1.00	LS
0500	24982EC	CONCRETE COATING - - 017B00037N	1.00	LS
0505	24983EC	BEARING LUBRICATION - - 017B00037N	8.00	EACH
0510	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 212965

121GR21M004 - FD04

MB05400412101

HOPKINSVILLE ROAD (US 41) BRIDGE 054B00161N OVER EAST LOUISVILLE AVENUE (CS 4018) AT MP 04.86
 BRIDGE DECK RESTORATION & WATERPROOFING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0195	02562	TEMPORARY SIGNS - - 054B00161N	145.00	SQFT
0200	02650	MAINTAIN & CONTROL TRAFFIC - - 054B00161N	1.00	LS
0205	02653	LANE CLOSURE - - 054B00161N	2.00	EACH
0210	03293	EXPAN JOINT REPLACE 1 IN - - 054B00161N	47.50	LF
0215	03299	ARMORED EDGE FOR CONCRETE - - 054B00161N	47.50	LF
0220	03300	ELIMINATE TRANSVERSE JOINT - - 054B00161N	119.50	LF
0225	03304	BRIDGE OVERLAY APPROACH PAVEMENT - - 054B00161N	530.00	SQYD
0230	04933	TEMP SIGNAL 2 PHASE - - 054B00161N	1.00	EACH
0235	06514	PAVE STRIPING-PERM PAINT-4 IN - - 054B00161N	2,145.00	LF
0240	06549	PAVE STRIPING-TEMP REM TAPE-B - - 054B00161N	2,000.00	LF
0245	06550	PAVE STRIPING-TEMP REM TAPE-W - - 054B00161N	2,000.00	LF
0250	06551	PAVE STRIPING-TEMP REM TAPE-Y - - 054B00161N	2,000.00	LF
0255	08150	STEEL REINFORCEMENT - - 054B00161N	1,650.00	LB
0260	08504	EPOXY SAND SLURRY - - 054B00161N	243.00	SQYD
0265	08510	REM EPOXY BIT FOREIGN OVERLAY - - 054B00161N	1,378.00	SQYD
0270	08526	CONC CLASS M FULL DEPTH PATCH - - 054B00161N	12.00	CUYD
0275	08534	CONCRETE OVERLAY-LATEX - - 054B00161N	36.90	CUYD
0280	08549	BLAST CLEANING - - 054B00161N	1,620.00	SQYD
0285	22146EN A	CONCRETE PATCHING REPAIR - - 054B00161N - TYPE A	22.00	SQFT
0290	22146EN B	CONCRETE PATCHING REPAIR - - 054B00161N - TYPE B	10.00	SQFT
0295	24094EC	PARTIAL DEPTH PATCHING - - 054B00161N	14.00	CUYD
0300	24692EC	DECK DRAIN RETROFIT - - 054B00161N	28.00	EACH
0305	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 212965

121GR21M004 - FD04

MB05401092101

CHARLESTON ROAD (KY109) BRIDGE 054B00073N OVER LICK CREEK AT MP 07.25 BRIDGE DECK RESTORATION & WATERPROOFING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	02562	TEMPORARY SIGNS - - 054B00073N	145.00	SQFT
0010	02650	MAINTAIN & CONTROL TRAFFIC - - 054B00073N	1.00	LS
0015	02653	LANE CLOSURE - - 054B00073N	2.00	EACH
0020	03299	ARMORED EDGE FOR CONCRETE - - 054B00073N (REVISED: 4-21-21)	67.20	LF
0025	03300	ELIMINATE TRANSVERSE JOINT - - 054B00073N	144.80	LF
0030	03304	BRIDGE OVERLAY APPROACH PAVEMENT - - 054B00073N	530.00	SQYD
0035	04933	TEMP SIGNAL 2 PHASE - - 054B00073N	1.00	EACH
0040	06514	PAVE STRIPING-PERM PAINT-4 IN - - 054B00073N	730.00	LF
0045	06549	PAVE STRIPING-TEMP REM TAPE-B - - 054B00073N	2,000.00	LF
0050	06550	PAVE STRIPING-TEMP REM TAPE-W - - 054B00073N	2,000.00	LF
0055	06551	PAVE STRIPING-TEMP REM TAPE-Y - - 054B00073N	2,000.00	LF
0060	08150	STEEL REINFORCEMENT - - 054B00073N	1,048.00	LB
0065	08504	EPOXY SAND SLURRY - - 054B00073N	132.00	SQYD
0070	08526	CONC CLASS M FULL DEPTH PATCH - - 054B00073N	4.00	CUYD
0075	08534	CONCRETE OVERLAY-LATEX - - 054B00073N	18.10	CUYD
0080	08549	BLAST CLEANING - - 054B00073N	535.00	SQYD
0085	08551	MACHINE PREP OF SLAB - - 054B00073N	403.00	SQYD
0090	24094EC	PARTIAL DEPTH PATCHING - - 054B00073N	4.00	CUYD
0095	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 212965

121GR21M004 - FD04

MB05408622102

LENIN ROAD (KY862) BRIDGE 054B00019 OVER I-69 AT MP 00.26 BRIDGE DECK RESTORATION & WATERPROOFING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0100	02562	TEMPORARY SIGNS - - 054B00019N	145.00	SQFT
0105	02650	MAINTAIN & CONTROL TRAFFIC - - 054B00019N	1.00	LS
0110	02653	LANE CLOSURE - - 054B00019N	2.00	EACH
0115	03298	EXPAN JOINT REPLACE 4 IN - - 054B00019N	52.40	LF
0120	03299	ARMORED EDGE FOR CONCRETE - - 054B00019N	52.40	LF
0125	03304	BRIDGE OVERLAY APPROACH PAVEMENT - - 054B00019N	578.00	SQYD
0130	04933	TEMP SIGNAL 2 PHASE - - 054B00019N	1.00	EACH
0135	06514	PAVE STRIPING-PERM PAINT-4 IN - - 054B00019N	805.00	LF
0140	06549	PAVE STRIPING-TEMP REM TAPE-B - - 054B00019N	2,000.00	LF
0145	06550	PAVE STRIPING-TEMP REM TAPE-W - - 054B00019N	2,000.00	LF
0150	06551	PAVE STRIPING-TEMP REM TAPE-Y - - 054B00019N	2,000.00	LF
0155	08150	STEEL REINFORCEMENT - - 054B00098N	268.00	LB
0160	08504	EPOXY SAND SLURRY - - 054B00019N	150.00	SQYD
0165	08526	CONC CLASS M FULL DEPTH PATCH - - 054B00019N	6.00	CUYD
0170	08534	CONCRETE OVERLAY-LATEX - - 054B00019N	24.30	CUYD
0175	08549	BLAST CLEANING - - 054B00019N	733.00	SQYD
0180	08551	MACHINE PREP OF SLAB - - 054B00019N	584.00	SQYD
0185	24094EC	PARTIAL DEPTH PATCHING - - 054B00019N	6.00	CUYD
0190	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 212965

121GR21M004 - FD04

MB05426572101

FOWLER ROAD (KY 2657) BRIDGE 054B00018N OVER I-69 AT MP 00.36 BRIDGE DECK RESTORATION & WATERPROOFING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0310	02562	TEMPORARY SIGNS - - 054B00018N	145.00	SQFT
0315	02650	MAINTAIN & CONTROL TRAFFIC - - 054B00018N	1.00	LS
0320	02653	LANE CLOSURE - - 054B00018N	2.00	EACH
0325	03298	EXPAN JOINT REPLACE 4 IN - - 054B00018N	55.50	LF
0330	03299	ARMORED EDGE FOR CONCRETE - - 054B00018N	55.50	LF
0335	03304	BRIDGE OVERLAY APPROACH PAVEMENT - - 054B00018N	578.00	SQYD
0340	04933	TEMP SIGNAL 2 PHASE - - 054B00018N	1.00	EACH
0345	06514	PAVE STRIPING-PERM PAINT-4 IN - - 054B00018N	830.00	LF
0350	06549	PAVE STRIPING-TEMP REM TAPE-B - - 054B00018N	2,000.00	LF
0355	06550	PAVE STRIPING-TEMP REM TAPE-W - - 054B00018N	2,000.00	LF
0360	06551	PAVE STRIPING-TEMP REM TAPE-Y - - 054B00018N	2,000.00	LF
0365	08150	STEEL REINFORCEMENT - - 054B00018N	268.00	LB
0370	08504	EPOXY SAND SLURRY - - 054B00018N	158.00	SQYD
0375	08526	CONC CLASS M FULL DEPTH PATCH - - 054B00018N	6.00	CUYD
0380	08534	CONCRETE OVERLAY-LATEX - - 054B00018N	25.60	CUYD
0385	08549	BLAST CLEANING - - 054B00018N	773.00	SQYD
0390	08551	MACHINE PREP OF SLAB - - 054B00018N	615.00	SQYD
0395	24094EC	PARTIAL DEPTH PATCHING - - 054B00018N	6.00	CUYD
0400	02569	DEMOBILIZATION	1.00	LS

PROPOSAL BID ITEMS

212965

Page 1 of 5

Report Date 4/21/21

Section: 0001 - BRIDGES

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	02562		TEMPORARY SIGNS - 017B00037N	235.00	SQFT		\$	
0020	02650		MAINTAIN & CONTROL TRAFFIC - 017B00037N	1.00	LS		\$	
0030	02653		LANE CLOSURE - 017B00037N	2.00	EACH		\$	
0040	03298		EXPAN JOINT REPLACE 4 IN - 017B00037N	89.40	LF		\$	
0050	03299		ARMORED EDGE FOR CONCRETE - 017B00037N	89.40	LF		\$	
0060	03304		BRIDGE OVERLAY APPROACH PAVEMENT - 017B00037N	667.00	SQYD		\$	
0070	04933		TEMP SIGNAL 2 PHASE - 017B00037N	1.00	EACH		\$	
0080	06514		PAVE STRIPING-PERM PAINT-4 IN - 017B00037N	1,298.00	LF		\$	
0090	06549		PAVE STRIPING-TEMP REM TAPE-B - 017B00037N	2,000.00	LF		\$	
0100	06550		PAVE STRIPING-TEMP REM TAPE-W - 017B00037N	2,000.00	LF		\$	
0110	06551		PAVE STRIPING-TEMP REM TAPE-Y - 017B00037N	2,000.00	LF		\$	
0120	08150		STEEL REINFORCEMENT - 017B00037N	270.00	LB		\$	
0130	08504		EPOXY SAND SLURRY - 017B00037N	236.30	SQYD		\$	
0140	08510		REM EPOXY BIT FOREIGN OVERLAY - 017B00037N	1,063.00	SQYD		\$	
0150	08526		CONC CLASS M FULL DEPTH PATCH - 017B00037N	11.00	CUYD		\$	
0160	08534		CONCRETE OVERLAY-LATEX - 017B00037N	44.30	CUYD		\$	
0170	08549		BLAST CLEANING - 017B00037N	1,300.00	SQYD		\$	
0180	24094EC		PARTIAL DEPTH PATCHING - 017B00037N	11.00	CUYD		\$	
0190	24981EC		BRIDGE CLEANING - 017B00037N	1.00	LS		\$	
0200	24982EC		CONCRETE COATING - 017B00037N	1.00	LS		\$	
0210	24983EC		BEARING LUBRICATION - 017B00037N	8.00	EACH		\$	

Section: 0002 - BRIDGES

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0220	02562		TEMPORARY SIGNS - 054B00161N	145.00	SQFT		\$	
0230	02650		MAINTAIN & CONTROL TRAFFIC - 054B00161N	1.00	LS		\$	
0240	02653		LANE CLOSURE - 054B00161N	2.00	EACH		\$	

PROPOSAL BID ITEMS

212965

Page 2 of 5

Report Date 4/21/21

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0250	03293		EXPAN JOINT REPLACE 1 IN - 054B00161N	47.50	LF		\$	
0260	03299		ARMORED EDGE FOR CONCRETE - 054B00161N	47.50	LF		\$	
0270	03300		ELIMINATE TRANSVERSE JOINT - 054B00161N	119.50	LF		\$	
0280	03304		BRIDGE OVERLAY APPROACH PAVEMENT - 054B00161N	530.00	SQYD		\$	
0290	04933		TEMP SIGNAL 2 PHASE - 054B00161N	1.00	EACH		\$	
0300	06514		PAVE STRIPING-PERM PAINT-4 IN - 054B00161N	2,145.00	LF		\$	
0310	06549		PAVE STRIPING-TEMP REM TAPE-B - 054B00161N	2,000.00	LF		\$	
0320	06550		PAVE STRIPING-TEMP REM TAPE-W - 054B00161N	2,000.00	LF		\$	
0330	06551		PAVE STRIPING-TEMP REM TAPE-Y - 054B00161N	2,000.00	LF		\$	
0340	08150		STEEL REINFORCEMENT - 054B00161N	1,650.00	LB		\$	
0350	08504		EPOXY SAND SLURRY - 054B00161N	243.00	SQYD		\$	
0360	08510		REM EPOXY BIT FOREIGN OVERLAY - 054B00161N	1,378.00	SQYD		\$	
0370	08526		CONC CLASS M FULL DEPTH PATCH - 054B00161N	12.00	CUYD		\$	
0380	08534		CONCRETE OVERLAY-LATEX - 054B00161N	36.90	CUYD		\$	
0390	08549		BLAST CLEANING - 054B00161N	1,620.00	SQYD		\$	
0400	22146EN		CONCRETE PATCHING REPAIR - 054B00161N - TYPE A	22.00	SQFT		\$	
0410	22146EN		CONCRETE PATCHING REPAIR - 054B00161N - TYPE B	10.00	SQFT		\$	
0420	24094EC		PARTIAL DEPTH PATCHING - 054B00161N	14.00	CUYD		\$	
0430	24692EC		DECK DRAIN RETROFIT - 054B00161N	28.00	EACH		\$	

Section: 0003 - BRIDGES

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0440	02562		TEMPORARY SIGNS - 054B00073N	145.00	SQFT		\$	
0450	02650		MAINTAIN & CONTROL TRAFFIC - 054B00073N	1.00	LS		\$	
0460	02653		LANE CLOSURE - 054B00073N	2.00	EACH		\$	
0470	03299		ARMORED EDGE FOR CONCRETE - 054B00073N (REVISED: 4-21-21)	67.20	LF		\$	
0480	03300		ELIMINATE TRANSVERSE JOINT - 054B00073N	144.80	LF		\$	
0490	03304		BRIDGE OVERLAY APPROACH PAVEMENT - 054B00073N	530.00	SQYD		\$	

PROPOSAL BID ITEMS

212965

Page 3 of 5

Report Date 4/21/21

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0500	04933		TEMP SIGNAL 2 PHASE - 054B00073N	1.00	EACH		\$	
0510	06514		PAVE STRIPING-PERM PAINT-4 IN - 054B00073N	730.00	LF		\$	
0520	06549		PAVE STRIPING-TEMP REM TAPE-B - 054B00073N	2,000.00	LF		\$	
0530	06550		PAVE STRIPING-TEMP REM TAPE-W - 054B00073N	2,000.00	LF		\$	
0540	06551		PAVE STRIPING-TEMP REM TAPE-Y - 054B00073N	2,000.00	LF		\$	
0550	08150		STEEL REINFORCEMENT - 054B00073N	1,048.00	LB		\$	
0560	08504		EPOXY SAND SLURRY - 054B00073N	132.00	SQYD		\$	
0570	08526		CONC CLASS M FULL DEPTH PATCH - 054B00073N	4.00	CUYD		\$	
0580	08534		CONCRETE OVERLAY-LATEX - 054B00073N	18.10	CUYD		\$	
0590	08549		BLAST CLEANING - 054B00073N	535.00	SQYD		\$	
0600	08551		MACHINE PREP OF SLAB - 054B00073N	403.00	SQYD		\$	
0610	24094EC		PARTIAL DEPTH PATCHING - 054B00073N	4.00	CUYD		\$	

Section: 0004 - BRIDGES

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0620	02562		TEMPORARY SIGNS - 054B00019N	145.00	SQFT		\$	
0630	02650		MAINTAIN & CONTROL TRAFFIC - 054B00019N	1.00	LS		\$	
0640	02653		LANE CLOSURE - 054B00019N	2.00	EACH		\$	
0650	03298		EXPAN JOINT REPLACE 4 IN - 054B00019N	52.40	LF		\$	
0660	03299		ARMORED EDGE FOR CONCRETE - 054B00019N	52.40	LF		\$	
0670	03304		BRIDGE OVERLAY APPROACH PAVEMENT - 054B00019N	578.00	SQYD		\$	
0680	04933		TEMP SIGNAL 2 PHASE - 054B00019N	1.00	EACH		\$	
0690	06514		PAVE STRIPING-PERM PAINT-4 IN - 054B00019N	805.00	LF		\$	
0700	06549		PAVE STRIPING-TEMP REM TAPE-B - 054B00019N	2,000.00	LF		\$	
0710	06550		PAVE STRIPING-TEMP REM TAPE-W - 054B00019N	2,000.00	LF		\$	
0720	06551		PAVE STRIPING-TEMP REM TAPE-Y - 054B00019N	2,000.00	LF		\$	
0730	08150		STEEL REINFORCEMENT - 054B00098N	268.00	LB		\$	
0740	08504		EPOXY SAND SLURRY - 054B00019N	150.00	SQYD		\$	

PROPOSAL BID ITEMS

212965

Page 4 of 5

Report Date 4/21/21

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0750	08526		CONC CLASS M FULL DEPTH PATCH - 054B00019N	6.00	CUYD		\$	
0760	08534		CONCRETE OVERLAY-LATEX - 054B00019N	24.30	CUYD		\$	
0770	08549		BLAST CLEANING - 054B00019N	733.00	SQYD		\$	
0780	08551		MACHINE PREP OF SLAB - 054B00019N	584.00	SQYD		\$	
0790	24094EC		PARTIAL DEPTH PATCHING - 054B00019N	6.00	CUYD		\$	

Section: 0005 - BRIDGES

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0800	02562		TEMPORARY SIGNS - 054B00018N	145.00	SQFT		\$	
0810	02650		MAINTAIN & CONTROL TRAFFIC - 054B00018N	1.00	LS		\$	
0820	02653		LANE CLOSURE - 054B00018N	2.00	EACH		\$	
0830	03298		EXPAN JOINT REPLACE 4 IN - 054B00018N	55.50	LF		\$	
0840	03299		ARMORED EDGE FOR CONCRETE - 054B00018N	55.50	LF		\$	
0850	03304		BRIDGE OVERLAY APPROACH PAVEMENT - 054B00018N	578.00	SQYD		\$	
0860	04933		TEMP SIGNAL 2 PHASE - 054B00018N	1.00	EACH		\$	
0870	06514		PAVE STRIPING-PERM PAINT-4 IN - 054B00018N	830.00	LF		\$	
0880	06549		PAVE STRIPING-TEMP REM TAPE-B - 054B00018N	2,000.00	LF		\$	
0890	06550		PAVE STRIPING-TEMP REM TAPE-W - 054B00018N	2,000.00	LF		\$	
0900	06551		PAVE STRIPING-TEMP REM TAPE-Y - 054B00018N	2,000.00	LF		\$	
0910	08150		STEEL REINFORCEMENT - 054B00018N	268.00	LB		\$	
0920	08504		EPOXY SAND SLURRY - 054B00018N	158.00	SQYD		\$	
0930	08526		CONC CLASS M FULL DEPTH PATCH - 054B00018N	6.00	CUYD		\$	
0940	08534		CONCRETE OVERLAY-LATEX - 054B00018N	25.60	CUYD		\$	
0950	08549		BLAST CLEANING - 054B00018N	773.00	SQYD		\$	
0960	08551		MACHINE PREP OF SLAB - 054B00018N	615.00	SQYD		\$	
0970	24094EC		PARTIAL DEPTH PATCHING - 054B00018N	6.00	CUYD		\$	

Section: 0006 - DEMOB

212965

PROPOSAL BID ITEMS

Page 5 of 5

Report Date 4/21/21

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0980	02569		DEMOBILIZATION	1.00	LS		\$	