



**COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET**

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

February 7, 2018

CALL NO. 402
CONTRACT ID NO. 182076
ADDENDUM # 1

Subject: Jefferson County, 056GR18P021-FD05
Letting February 23, 2018

- (1) Revised - Summary - Pages 42-44 of 60
- (2) Added - Summary - Pages 44(a)-44(b) of 60

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mw
Enclosures



An Equal Opportunity Employer M/F/D

TRAFFIC LOOP SUMMARY
FD05 056 0864 013-015

INTERSECTION	SAW, SLOT AND FILL		LOOP WIRE		CONDUIT 1 INCH		CONDUIT 1 1/4 INCH		CONDUIT 2 INCH		CABLE NO. 14/1		JUNCTION BOX TYPE B		TRENCHING & BACKFILLING		LOOP TEST		NOTES
	LF		LF		LF		LF		LF		LF	EA	EA	EA	EA	EA	EA		
Germantown Kroger																			
North Leg	102		264	10	40	50	120	1							150	2		(2) 6 ft x 30 ft Loop @ Stop Bar in Right & Left Turn Lane	
East Leg	122		304	10	20	0	220	1							20	1		(1) 6 ft x 30 ft Loop @ Stop Bar	
West Leg	254		528	10	20	0	240	1							20	2		(2) 6 ft x 30 ft Loop @ Stop Bar in Thru & Left Turn Lane	
Texas Ave																			
North Leg	150		300	10	40	0	200	1							50	1		(1) 6 ft x 30 ft Loop @ Stop Bar	
East Leg	224		548	10	20	0	200	1							20	2		(2) 6 ft x 30 ft Loop @ Stop Bar at Left & Right turn	
South Leg	150		300	10	20	0	200	1							40	1		(1) 6 ft x 30 ft Loop @ Stop Bar	
West Leg	150		300	10	20	0	200	1							40	1		(1) 6 ft x 30 ft Loop @ Stop Bar	
TOTALS	1,152		2,544	70	180	50	1,380	7							340	10			

- NOTES:**
1. Consider quantities to be estimates only. The Contractor shall field measure and inspect items to verify quantities.
 2. 2 - 1 1/4 inch conduits may be used in place of 2" conduit. Field verify conduit to match existing facilities/tie-in to poles/cabinets. Only replace existing conduit if damaged.

SIDEWALK RAMP AND DETECTABLE WARNING SUMMARY FD05 056 0864 013-015

MILEPOINT	INTERSECTION	RAMP		DETECTABLE WARNINGS		NOTES
		TYPE	SY	QUANTITY	SF	
GOSS AVENUE						
13.785	Sidestreet	1	12	2	20	
13.766	Reasor Ave	1	12	2	20	
13.933	Texas Ave	3	100	4	160	
14.038	Hickory St	1	12	2	20	
14.068	Spratt St	1	12	2	20	
14.144	Hoertz Ave	1	12	2	20	
14.203	Krieger St	1	12	2	20	
14.277	McHenry St	1	12	2	20	
14.339	Boyle St	1	12	2	20	
LOGAN STREET						
14.468	Dandridge Ave	1	16	2	20	
14.544	Shelby Parkway	1	16	2	2	
14.615	East Oak St	3	100	4	160	
14.691	Mary St	3	100	4	160	
14.760	East St. Catherine St	3	100	4	160	
14.831	East Kentucky St	3	100	4	160	
TOTAL			628	40	982	

**SIDEWALK RAMP AND DETECTABLE WARNING SUMMARY
FD05 056 864C 014-015**

MILEPOINT	INTERSECTION	RAMP		DETECTABLE WARNINGS		NOTES
		TYPE	SY	QUANTITY	SF	
	GOSS AVENUE					
14.476	Chester Ave	1	6	1	10	
14.523	Shelby Street	1	16	2	20	
	SHELBY STREET					
14.543	Camp Street	1	16	2	20	
14.599	Shelby Parkway	1	16	2	20	
14.659	Gwendolyn Street	1	16	2	20	
14.703	East Oak Street	3	75	3	120	
14.794	East St. Catherine/Mary St	3	75	3	120	
14.841	East St. Catherine St	1	16	2	20	
	TOTAL		236	17	350	

THERMOPLASTIC INTERSECTION PAVEMENT MARKINGS SUMMARY
FD05 056 864 013-015

MILEPOINT	INTERSECTION	X-WALKS 12 INCH LF	STOP BARS 24 INCH LF	ARROWS			RAILROAD		NOTES
				CURVE EA	STR EA	COMB EA	"R" 6 FOOT EA	CROSS BUCK 16" LF	
	GOSS AVENUE								
13.725	Eastern Parkway		40	5					
13.766	Parkway Gardens			1					
13.834	Kroger	314	36	3		1			
13.933	Texas Ave	232	48						
14.411	Railroad Crossing		66				4	88	
	LOGAN STREET								
14.615	East Oak Street	215	25						
14.691	Mary Street	235	24						
14.831	East Kentucky Street	229	24						
	TOTAL	1,225	263	9	0	1	4	88	

