



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Secretary

June 6, 2012

CALL NO. 403  
CONTRACT ID NO. 122954  
Addendum # 1

Subject: Christian County, 024GR12M074-FE02  
Letting June 15, 2012

(1) Revised - Traffic Note - Page 34 of 67

Proposal revisions are available at  
<http://transportation.ky.gov/Construction-Procurement>

Plan Revisions are available at: <http://www.lynnimaging.com/kytransportation/>

If you have any questions, please contact us at (502) 564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Ryan Griffith".

Ryan Griffith  
Director  
Division of Construction Procurement

RG:jj

Enclosures



An Equal Opportunity Employer M/F/D

**FE02 024 0189 B00064N 03.18**

Maintain one usable 11 foot lane. Flagging or traffic signals shall be used. If traffic signals are used the Contractor shall use flagging to minimize impact on school bus traffic when school is in session. The Contractor shall be responsible for establishing the dates and times when school bus traffic will impact the job site. The Contractor will be permitted to briefly close the structure to traffic using flagging to move any equipment that exceeds the 20 ton weight limit (See Special Note for Weight Limits on Structure) across the structure as directed by the Engineer. The equipment must be centered on the structure and shall not exceed 40 tons.

**FE02 024 0508 B00080N 04.16**

Maintain one usable 11 foot lane. Flagging or traffic signals shall be used. If traffic signals are used the Contractor shall use flagging to minimize impact on school bus traffic when school is in session. The Contractor shall be responsible for establishing the dates and times when school bus traffic will impact the job site. The Contractor will be permitted to briefly close the structure to traffic using flagging to move any equipment that exceeds the 37 ton weight limit (See Special Note for Weight Limits on Structure) across the structure as directed by the Engineer. The equipment must be centered on the structure and shall not exceed 74 tons.

**FE02 024 0107 B00117N 19.57**

Maintain one usable 12 foot lane in each direction on KY 9004. The exit ramp for Southbound KY 9004 to KY 80 will require a closure to clean and paint the portions of the structure above. The contractor will be permitted to close this ramp of a period of **21 consecutive calendar days** to clean and paint the portion the structure above this ramp. See attached Detour Plan. The entrance ramp for KY 80 Northbound KY 9004 will require a closure to clean and paint the portions of the structure above. The contractor will be permitted to close this ramp of a period of **21 consecutive calendar days** to clean and paint the portion the structure above this ramp. See attached plan sheet S1 for Suggested Detour Plan. Contrary to section 108.09 of the KYTC Standard Specification the contractor will be assessed a liquidated damage of \$1,000.00 per day for any ramp closure outside the allotted 21 consecutive calendar days for each ramp. Shoulder, Right and Left lane closures will be permitted to clean and paint portions of the structure above.