



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Matthew G. Bevin
Governor

Greg Thomas
Secretary

June 4, 2019

CALL NO. 403
CONTRACT ID NO. 192104
ADDENDUM # 1

Subject: GRAYSON-BUTLER COUNTIES, 121GR19P023-FE01
Letting June 21, 2019

- (1) Revised - Culvert Lining Summary - Page 33 of 52
- (2) Revised - Material Summary - Page 32 of 52
- (3) Added - Material Summary - Page 32(a) of 52
- (4) Revised - Proposal Bid Items - Page 52 of 52

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures



An Equal Opportunity Employer M/F/D

Culvert Lining Summary

Milepoint	15"	18"	24"	30"	36"	42"	54"	66"	72"
87.570				200					
87.805						252			
87.922		124							
88.040				120					
88.279					152				
88.450				168					
88.570					212				
88.640			132						
88.870				268					
89.465									264
89.700		120							
89.800		136							
89.885				184					
90.330							368		
90.448	84								
90.468								360	
90.500	120								
90.550	84								
90.600						200			
90.620	56								
90.680			132						
90.685	64								
90.692	64								
90.730	64								
90.860	64								
90.878		116							
90.980	64								
91.080		64							
Totals	664	560	264	940	364	452	368	360	264

Clean Pipe Structure Summary

Milepoint	42"	54"	66"	72"
87.805	1			
88.950				
89.080				
89.465				1
90.330		1		
90.468			1	
90.600	1			
90.900				

1. In accordance with Section 209.04.06 of the Standard Specifications, cleaning of culverts 36" and less in diameter shall be incidental to the item Ditching and Shouldering and should be performed prior to culvert lining.
2. Clean Pipe Structure shall be paid in accordance with Section 209.04.08 of the Standard Specifications.
3. Removing and resetting of headwalls shall be incidental to culvert lining.

MATERIAL SUMMARY

CONTRACT ID: 192104

121GR19P023-FE01

MP01690011902

WESTERN KENTUCKY PARKWAY (WK 9001) FROM OHIO COUNTY LINE EXTENDING EAST TO GRAYSON COUNTY LINE GRADE & DRAIN, A DISTANCE OF .89 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	02562	TEMPORARY SIGNS	150.00	SQFT
0010	02650	MAINTAIN & CONTROL TRAFFIC - (BUTLER)	1.00	LS
0015	02671	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH
0020	02775	ARROW PANEL	1.00	EACH
0025	00078	CRUSHED AGGREGATE SIZE NO 2	850.00	TON
0030	02483	CHANNEL LINING CLASS II	400.00	TON
0035	02575	DITCHING AND SHOULDERING	4,700.00	LF
0040	03262	CLEAN PIPE STRUCTURE	1.00	EACH
0045	24862EC	PVC FOLD AND FORM PIPE LINER-18 IN	124.00	LF
0050	24865EC	PVC FOLD AND FORM PIPE LINER-36 IN	152.00	LF
0055	02569	DEMOBILIZATION	1.00	LS
0060	02383	REMOVE & RESET GUARDRAIL	4,625.00	LF
0065	24864EC	PVC FOLD AND FORM PIPE LINER-30 IN - (ADDED: 6-4-19)	320.00	LF
0070	24583EC	HDPE PIPE LINER - (42 INCH) (REVISED: 6-4-19)	252.00	LF

MATERIAL SUMMARY

CONTRACT ID: 192104

121GR19P023-FE01

MP04390011902

WESTERN KENTUCKY PARKWAY (WK 9001) FROM BUTLER COUNTY LINE EXTENDING EAST TO PAVEMENT JOINT 0.198 MILES EAST OF DOG CREEK CULVERT GRADE & DRAIN, A DISTANCE OF 2.77 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0075	02562	TEMPORARY SIGNS	150.00	SQFT
0080	02650	MAINTAIN & CONTROL TRAFFIC - (GRAYSON)	1.00	LS
0085	02671	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH
0090	02775	ARROW PANEL	1.00	EACH
0095	02483	CHANNEL LINING CLASS II	9,000.00	TON
0100	02575	DITCHING AND SHOULDERING	14,610.00	LF
0105	03262	CLEAN PIPE STRUCTURE	4.00	EACH
0110	24861EC	PVC FOLD AND FORM PIPE LINER-15 IN	664.00	LF
0115	24862EC	PVC FOLD AND FORM PIPE LINER-18 IN	436.00	LF
0120	24583EC	HDPE PIPE LINER - (42 INCH) (REVISED: 6-4-19)	200.00	LF
0125	24583EC	HDPE PIPE LINER - (66 INCH)	360.00	LF
0130	24583EC	HDPE PIPE LINER - (72 INCH)	264.00	LF
0135	02569	DEMOBILIZATION	1.00	LS
0140	24583EC	HDPE PIPE LINER - (36 INCH)	212.00	LF
0145	00078	CRUSHED AGGREGATE SIZE NO 2	1,000.00	TON
0150	02383	REMOVE & RESET GUARDRAIL	15,175.00	LF
0155	24583EC	HDPE PIPE LINER - (54 INCH) (ADDED: 6-4-19)	368.00	LF
0160	24864EC	PVC FOLD AND FORM PIPE LINER-30 IN - (ADDED: 6-4-19)	620.00	LF
0165	24863EC	PVC FOLD AND FORM PIPE LINER-24 IN - (ADDED: 6-4-19)	264.00	LF

PROPOSAL BID ITEMS

192104

Page 1 of 1

Report Date 6/4/19

Section: 0001 - DRAINAGE

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00078		CRUSHED AGGREGATE SIZE NO 2	1,850.00	TON		\$	
0020	02383		REMOVE & RESET GUARDRAIL	19,800.00	LF		\$	
0030	02483		CHANNEL LINING CLASS II	9,400.00	TON		\$	
0040	02562		TEMPORARY SIGNS	300.00	SQFT		\$	
0050	02575		DITCHING AND SHOULDERING	19,310.00	LF		\$	
0060	02650		MAINTAIN & CONTROL TRAFFIC (BUTLER)	1.00	LS		\$	
0070	02650		MAINTAIN & CONTROL TRAFFIC (GRAYSON)	1.00	LS		\$	
0080	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0090	02775		ARROW PANEL	2.00	EACH		\$	
0100	03262		CLEAN PIPE STRUCTURE	5.00	EACH		\$	
0120	24583EC		HDPE PIPE LINER (36 INCH)	212.00	LF		\$	
0130	24583EC		HDPE PIPE LINER (42 INCH) (REVISED: 6-4-19)	452.00	LF		\$	
0135	24583EC		HDPE PIPE LINER (54 INCH) (ADDED: 6-4-19)	368.00	LF		\$	
0140	24583EC		HDPE PIPE LINER (66 INCH)	360.00	LF		\$	
0150	24583EC		HDPE PIPE LINER (72 INCH)	264.00	LF		\$	
0160	24861EC		PVC FOLD AND FORM PIPE LINER-15 IN	664.00	LF		\$	
0170	24862EC		PVC FOLD AND FORM PIPE LINER-18 IN	560.00	LF		\$	
0172	24863EC		PVC FOLD AND FORM PIPE LINER-24 IN (ADDED:6-4-19)	264.00	LF		\$	
0173	24864EC		PVC FOLD AND FORM PIPE LINER-30 IN (ADDED: 6-4-19)	940.00	LF		\$	
0180	24865EC		PVC FOLD AND FORM PIPE LINER-36 IN	152.00	LF		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0190	02569		DEMOBILIZATION	1.00	LS		\$	