



**TRANSPORTATION CABINET**

Frankfort, Kentucky 40622  
www.transportation.ky.gov/

**Steven L. Beshear**  
Governor

**Michael W. Hancock, P.E.**  
Secretary

October 19, 2015

CALL NO. 403  
CONTRACT ID NO. 152966  
ADDENDUM # 1

Subject: Hopkins-Mclean-Muhlenberg Counties, 121GR15M062-FE02  
Letting October 23, 2015

- (1) Revised - Note - Page 45 of 114
- (2) Revised - Material Summary - Pages 65-66 of 114
- (3) Revised - Bid Items - Pages 113-114 of 114

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:ks  
Enclosures



An Equal Opportunity Employer M/F/D

**Payment**

Payment of the contract lump sum amount for "maintain and control traffic" shall be full compensation for all items necessary to maintain and control traffic on this project. All traffic control items shall remain the property of the contractor when the work is complete.

**054B00079N, 075B00030N and 089B00038N**

Maintain one usable 11 foot minimum lane. Flagging or traffic signals shall be used. If traffic signals are used the Contractor shall use flagging to minimize impact on school bus traffic when school is in session. The Contractor shall be responsible for establishing the dates and times when school bus traffic will impact the job site. The Contractor will be permitted to briefly close the structure to traffic using flagging to move any equipment that exceeds weight limit (See Special Note for Weight Limits on Structure) across the structures as directed by the Engineer. The equipment must be centered on the structure and shall not exceed 2 times the load rating for the structure. Both lanes shall be restored to traffic during the off season November 15, 2015-April 1 2016, See section 614.03.02 for Seasonal and Weather Limitations for exceptions.

**075B00030N and 089B00038N**

To accommodate the planting and harvest seasons the contractor may be required clear the bridge for passage of agricultural equipment during the planting and harvest seasons. This will only require the removal of traffic cones/barrels, contractor's equipment in the lane closure and all other items that would obstruct the passage of the agricultural equipment. All temporary striping, signage, etc. will be permitted to remain. The time period will be for no longer than two hours. The two hour time period will be scheduled with coordination between the Department and the Agricultural Community to have the least impact on the Contractor's production. **All cost to clear the bridge for passage as required shall be included in the unit bid price per each "Clear Bridge".**

# MATERIAL SUMMARY

**CONTRACT ID: 152966**

**121GR15M062 - FE02**

**MB05401091502**

KY 109 OVER TRADE WATER RIVER 054B00079N DAWSON SPRINGS ROAD  
 KY 109 OVER TRADE WATER RIVER MP 00.12 BRIDGE PAINTING & CLEANING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	02650	MAINTAIN & CONTROL TRAFFIC - - 054B00079N	1.00	LS
0010	08434	CLEAN & PAINT STRUCTURAL STEEL - - 054B00079N	1.00	LS
0015	02568	MOBILIZATION	1.00	LS
0020	02569	DEMOBILIZATION	1.00	LS

**CONTRACT ID: 152966**

**121GR15M062 - FE02**

**MB07502561501**

KY 256 OVER LONG FALLS CREEK 075B00030N BEECH GROVE-CALHOUN ROAD  
 KY 256 OVER LONG FALLS CREEK MP 09.87 BRIDGE PAINTING & CLEANING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0025	02650	MAINTAIN & CONTROL TRAFFIC - - 075B00030N	1.00	LS
0030	08434	CLEAN & PAINT STRUCTURAL STEEL - - 075B00030N	1.00	LS
0035	02568	MOBILIZATION	1.00	LS
0040	02569	DEMOBILIZATION	1.00	LS
0045	02403	REMOVE CONCRETE MASONRY - - 075B00030N	5.00	CUYD
0050	08104	CONCRETE-CLASS AA - - 075B00030N	26.80	CUYD
0055	08151	STEEL REINFORCEMENT-EPOXY COATED - - 075B00030N	1,440.00	LB
0060	03299	ARMORED EDGE FOR CONCRETE - - 075B00030N	51.00	LF
0065	03294	EXPAN JOINT REPLACE 1 1/2 IN - - 075B00030N	51.00	LF
0070	24775EC	CLEAR BRIDGE - - 075B00030N (ADDED: 10-19-15)	1.00	EACH

# MATERIAL SUMMARY

**CONTRACT ID: 152966**

**121GR15M062 - FE02**

**MB08901891502**

KY 189 OVER POND CREEK 089B00038N GREENVILLE-HOPKINSVILLE ROAD  
 KY 189 OVER POND CREEK MP 00.02 BRIDGE PAINTING & CLEANING.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0070	02650	MAINTAIN & CONTROL TRAFFIC - - 089B00035N	1.00	LS
0075	08434	CLEAN & PAINT STRUCTURAL STEEL - - 089B00038N	1.00	LS
0080	02568	MOBILIZATION	1.00	LS
0085	02569	DEMOBILIZATION	1.00	LS
0090	03300	ELIMINATE TRANSVERSE JOINT - - 089B00038N	275.30	LF
0095	03294	EXPAN JOINT REPLACE 1 1/2 IN - - 089B00038N	72.00	LF
0100	03297	EXPAN JOINT REPLACE 3 IN - - 89B00038N	48.00	LF
0105	02403	REMOVE CONCRETE MASONRY - - 089B00038N	9.00	CUYD
0110	08104	CONCRETE-CLASS AA - - 089B00038N	16.40	CUYD
0115	08151	STEEL REINFORCEMENT-EPOXY COATED - - 089B00038N	4,168.00	LB
0120	03299	ARMORED EDGE FOR CONCRETE - - 089B00038N	48.00	LF
0125	22146EN	CONCRETE PATCHING REPAIR - - 089B00038N	100.00	SQFT
0130	24775EC	CLEAR BRIDGE - - 089B00038N (ADDED: 10-19-15)	1.00	EACH

**PROPOSAL BID ITEMS**

REVISED ADDENDUM #1: 10-19-15

152966

Page 1 of 2

Report Date 10/19/15

**Section: 0001 - BRIDGES**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	02650		MAINTAIN & CONTROL TRAFFIC - 054B00079N	1.00	LS		\$	
0020	08434		CLEAN & PAINT STRUCTURAL STEEL - 054B00079N	1.00	LS		\$	

**Section: 0002 - BRIDGES**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0030	02403		REMOVE CONCRETE MASONRY - 075B00030N	5.00	CUYD		\$	
0040	02650		MAINTAIN & CONTROL TRAFFIC - 075B00030N	1.00	LS		\$	
0050	03294		EXPAN JOINT REPLACE 1 1/2 IN - 075B00030N	51.00	LF		\$	
0060	03299		ARMORED EDGE FOR CONCRETE - 075B00030N	51.00	LF		\$	
0070	08104		CONCRETE-CLASS AA - 075B00030N	26.80	CUYD		\$	
0080	08151		STEEL REINFORCEMENT-EPOXY COATED - 075B00030N	1,440.00	LB		\$	
0090	08434		CLEAN & PAINT STRUCTURAL STEEL - 075B00030N	1.00	LS		\$	
0091	24775EC		CLEAR BRIDGE - 075B00030N (ADDED: 10-19-15)	1.00	EACH		\$	

**Section: 0003 - BRIDGES**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0100	02403		REMOVE CONCRETE MASONRY - 089B00038N	9.00	CUYD		\$	
0110	02650		MAINTAIN & CONTROL TRAFFIC - 089B00035N	1.00	LS		\$	
0120	03294		EXPAN JOINT REPLACE 1 1/2 IN - 089B00038N	72.00	LF		\$	
0130	03297		EXPAN JOINT REPLACE 3 IN - 89B00038N	48.00	LF		\$	
0140	03299		ARMORED EDGE FOR CONCRETE - 089B00038N	48.00	LF		\$	
0150	03300		ELIMINATE TRANSVERSE JOINT - 089B00038N	275.30	LF		\$	
0160	08104		CONCRETE-CLASS AA - 089B00038N	16.40	CUYD		\$	
0170	08151		STEEL REINFORCEMENT-EPOXY COATED - 089B00038N	4,168.00	LB		\$	
0180	08434		CLEAN & PAINT STRUCTURAL STEEL - 089B00038N	1.00	LS		\$	
0190	22146EN		CONCRETE PATCHING REPAIR - 089B00038N	100.00	SQFT		\$	

### PROPOSAL BID ITEMS

152966

Page 2 of 2

Report Date 10/19/15

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0191	24775EC		CLEAR BRIDGE - 089B00038N (ADDED: 10-19-15)	1.00	EACH		\$	

#### Section: 0004 - DEMOB

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0200	02568		MOBILIZATION	1.00	LS		\$	
0210	02569		DEMOBILIZATION	1.00	LS		\$	