



COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET

[www.transportation.ky.gov/](http://www.transportation.ky.gov/)

Andy Beshear  
GOVERNOR

Jim Gray  
SECRETARY

September 17, 2021

CALL NO. 404  
CONTRACT ID NO. 212393  
ADDENDUM # 1

Subject: Harrison County, 049GR21P099 - FD05  
Letting September 24, 2021

- (1) Revised - Provisions - Page 9 of 47
- (2) Revised - Material Summary - Pages 25-26 of 47
- (3) Revised - Summary Sheet - Page 32 of 47
- (4) Revised - Proposal Bid Items - Page 47 of 47

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

**SURFACING AREAS (FD05 049 0982 002-006)**

The Department estimates the mainline surfacing width to be varied 24 to 30 feet.  
The Department estimates the total mainline area to be surfaced to be 29,895 square yards.  
The Department estimates the shoulder width to be varied 0 to 1 foot on each side.  
The Department estimates the total shoulder area to be surfaced to be 2,194 square yards.

**SURFACING AREAS (FD05 049 0036 010-0136)**

The Department estimates the mainline surfacing width to be 22 feet.  
The Department estimates the total mainline area to be surfaced to be 24,551 square yards.  
The Department estimates the shoulder width to be 1 foot on each side.  
The Department estimates the total shoulder area to be surfaced to be 2,040 square yards.

**ASPHALT MIXTURE**

Unless otherwise noted, the Department estimates the rate of application for all asphalt mixtures to be 110 lbs/sy per inch of depth.

**INCIDENTAL SURFACING**

The Department has included in the quantities of asphalt mixtures established in the proposal estimated quantities required for resurfacing or surfacing mailbox turnouts, farm field entrances, residential and commercial entrances, curve widening, ramp gores and tapers, and road and street approaches, as applicable. Pave these areas to the limits as shown on Standard Drawing RPM-110-06 or as directed by the Engineer. In the event signal detectors are present in the intersecting streets or roads, pave the crossroads to the right of way limit or back of the signal detector, whichever is the farthest back of the mainline. Surface or resurface these areas as directed by the Engineer. The Department will not measure placing and compacting for separate payment but shall be incidental to the Contract unit price for the asphalt mixtures.

**FUEL AND ASPHALT PAY ADJUSTMENT**

The Department has included the Contract items Asphalt Adjustment and Fuel Adjustment for possible future payments at an established Contract unit price of \$1.00. The Department will calculate actual adjustment quantities after work is completed. If existing Contract amount is insufficient to pay all items on the contract with the adjustments, the Department will establish additional monies with a change order.

**OPTION B**

Be advised that the Department will control and accept compaction of asphalt mixtures furnished on this project under OPTION B in accordance with Sections 402 and 403.

# MATERIAL SUMMARY

**CONTRACT ID: 212393**

**049GR21P099 - FD05**

**MP04900322101**

CYNTHIANA TO COLVILLE ROAD (KY 32) BEGIN AT CULPEPPER LANE EXTENDING EAST TO 90 FEET WEST OF KY 1940 ASPHALT RESURFACING, A DISTANCE OF 1.73 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0105	00190	LEVELING & WEDGING PG64-22	49.00	TON
0110	00301	CL2 ASPH SURF 0.38D PG64-22	1,465.00	TON
0115	00356	ASPHALT MATERIAL FOR TACK	12.00	TON
0120	02562	TEMPORARY SIGNS	270.00	SQFT
0125	02650	MAINTAIN & CONTROL TRAFFIC - (KY 32)	1.00	LS
0130	02676	MOBILIZATION FOR MILL & TEXT - (KY 32)	1.00	LS
0135	02677	ASPHALT PAVE MILLING & TEXTURING	25.00	TON
0140	02697	EDGE LINE RUMBLE STRIPS	12,040.00	LF
0145	03240	BASE FAILURE REPAIR - (REVISED 9-16-2021)	280.00	SQYD
0150	06510	PAVE STRIPING-TEMP PAINT-4 IN	17,825.00	LF
0155	06515	PAVE STRIPING-PERM PAINT-6 IN	35,650.00	LF
0160	02569	DEMOBILIZATION	1.00	LS
0165	10020NS	FUEL ADJUSTMENT - (ADDED 9-16-2021)	2,356.00	DOLL
0170	10030NS	ASPHALT ADJUSTMENT - (ADDED 9-16-2021)	5,919.00	DOLL

# MATERIAL SUMMARY

**CONTRACT ID: 212393**

**049GR21P099 - FD05**

**MP04909822101**

NEW LAIR ROAD (KY 982) (OMIT MP 3.1 - 4.6) BEGIN AT US 27 EXTENDING NORTH TO KY 32 ASPHALT RESURFACING, A DISTANCE OF 1.91 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00190	LEVELING & WEDGING PG64-22	127.00	TON
0010	00301	CL2 ASPH SURF 0.38D PG64-22	1,770.00	TON
0015	02562	TEMPORARY SIGNS	350.00	SQFT
0020	02650	MAINTAIN & CONTROL TRAFFIC - (KY982)	1.00	LS
0025	02676	MOBILIZATION FOR MILL & TEXT - (KY982)	1.00	LS
0030	02677	ASPHALT PAVE MILLING & TEXTURING	170.00	TON
0035	02697	EDGELINE RUMBLE STRIPS	12,900.00	LF
0040	02720	SIDEWALK-4 IN CONCRETE	20.00	SQYD
0045	03240	BASE FAILURE REPAIR - (REVISED 9-16-2021)	275.00	SQYD
0050	06510	PAVE STRIPING-TEMP PAINT-4 IN	15,000.00	LF
0055	06515	PAVE STRIPING-PERM PAINT-6 IN	30,381.00	LF
0060	06565	PAVE MARKING-THERMO X-WALK-6 IN	40.00	LF
0065	06568	PAVE MARKING-THERMO STOP BAR-24IN	72.00	LF
0070	06574	PAVE MARKING-THERMO CURV ARROW	2.00	EACH
0075	06576	PAVE MARKING-THERMO ONLY	2.00	EACH
0080	20458ES403	CENTERLINE RUMBLE STRIPS	6,450.00	LF
0085	23158ES505	DETECTABLE WARNINGS - (NEW)	16.00	SQFT
0090	23756EC	PAVE MARK-THERM R/R ADVANCE WARN SYMBOL	1.00	EACH
0095	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	10.00	TON
0100	02569	DEMOBILIZATION	1.00	LS
0105	10020NS	FUEL ADJUSTMENT - (ADDED 9-16-2021)	2,953.00	DOLL
0110	10030NS	ASPHALT ADJUSTMENT - (ADDED 9-16-2021)	7,417.00	DOLL



**PROPOSAL BID ITEMS**

212393

Page 1 of 1

Report Date 9/16/21

**Section: 0001 - PAVING**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	176.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	3,235.00	TON		\$	
0030	00356		ASPHALT MATERIAL FOR TACK	12.00	TON		\$	
0031	10020NS		FUEL ADJUSTMENT (ADDED 9-16-2021)	5,309.00	DOLL	\$1.00	\$	\$5,309.00
0032	10030NS		ASPHALT ADJUSTMENT (ADDED 9-16-2021)	13,336.00	DOLL	\$1.00	\$	\$13,336.00
0040	02562		TEMPORARY SIGNS	620.00	SQFT		\$	
0050	02650		MAINTAIN & CONTROL TRAFFIC (KY 32)	1.00	LS		\$	
0060	02650		MAINTAIN & CONTROL TRAFFIC (KY982)	1.00	LS		\$	
0070	02676		MOBILIZATION FOR MILL & TEXT (KY 32)	1.00	LS		\$	
0080	02676		MOBILIZATION FOR MILL & TEXT (KY982)	1.00	LS		\$	
0090	02677		ASPHALT PAVE MILLING & TEXTURING	195.00	TON		\$	
0100	02697		EDGE LINE RUMBLE STRIPS	24,940.00	LF		\$	
0110	02720		SIDEWALK-4 IN CONCRETE	20.00	SQYD		\$	
0120	03240		BASE FAILURE REPAIR (REVISED 9-16-2021)	555.00	SQYD		\$	
0130	06510		PAVE STRIPING-TEMP PAINT-4 IN	32,825.00	LF		\$	
0140	06515		PAVE STRIPING-PERM PAINT-6 IN	66,031.00	LF		\$	
0150	06565		PAVE MARKING-THERMO X-WALK-6 IN	40.00	LF		\$	
0160	06568		PAVE MARKING-THERMO STOP BAR-24IN	72.00	LF		\$	
0170	06574		PAVE MARKING-THERMO CURV ARROW	2.00	EACH		\$	
0180	06576		PAVE MARKING-THERMO ONLY	2.00	EACH		\$	
0190	20458ES403		CENTERLINE RUMBLE STRIPS	6,450.00	LF		\$	
0200	23158ES505		DETECTABLE WARNINGS (NEW)	16.00	SQFT		\$	
0210	23756EC		PAVE MARK-THERM R/R ADVANCE WARN SYMBOL	1.00	EACH		\$	
0220	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING	10.00	TON		\$	

**Section: 0002 - DEMOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0230	02569		DEMOBILIZATION	1.00	LS		\$	