



COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET  
[www.transportation.ky.gov/](http://www.transportation.ky.gov/)

Andy Beshear  
GOVERNOR

Jim Gray  
SECRETARY

May 5, 2021

CALL NO. 404  
CONTRACT ID NO. 212223  
ADDENDUM # 1

Subject: Knott County, 060GR219053-FD51  
Letting May 21, 2021

(1) Added - Summary Sheets - Pages 1-8 of 8

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:mr  
Enclosures

# SITE SUMMARY KY 160

Site	Begin	End	Length	Cribbing Depth	Excavation Width	Depth to Rock	Number of Rows	Rail Spacing (FT)	Cribbing Amount (SQ FT)	Drilled RR Steel (FT)	Excav. & Backfill (CU YD)	Geotextile Fabric Class 2 (SQ YD)
1	13.412	13.420	45	8	4	27	1	3	360	648	54	100
2	14.057	14.063	30	10	4	27	1	3	300	446	45	80
3	15.321	15.335	75	8	4	27	1	3	600	1,053	89	167
<b>TOTALS</b>									<b>1,260</b>	<b>2,147</b>	<b>188</b>	<b>347</b>

# SITE SUMMARY KY 721

Site	Begin	End	Length	Cribbing Depth	Excavation Width	Depth to Rock	Number of Rows	Rail Spacing (FT)	Cribbing Amount (SQ FT)	Drilled RR Steel (FT)	Excav. & Backfill (CU YD)	Geotextile Fabric Class 2 (SQ YD)
1	5.066	5.070	24	7	4	27	1	3	168	364.5	25	48
<b>TOTALS</b>									<b>168</b>	<b>365</b>	<b>25</b>	<b>48</b>

# SITE SUMMARY KY 1088

Site	Begin	End	Length	Cribbing Depth	Excavation Width	Depth to Rock	Number of Rows	Rail Spacing (FT)	Cribbing Amount (SQ FT)	Drilled RR Steel (FT)	Excav. & Backfill (CU YD)	Geotextile Fabric Class 2 (SQ YD)	
<b>1</b>	<b>NOT PART OF THIS CONTRACT</b>												
2	2.528	2.533	24	8	4	27	1	3	192	364.5	29	53	
3	2.630	2.636	30	5	4	27	1	3	150	445.5	23	47	
4A	4.902	4.916	75	8	4	27	1	3	600	1053	89	167	
4B	4.924	4.933	45	8	4	27	1	3	360	648	54	100	
<b>5</b>	<b>5.079</b>	<b>5.321</b>										<b>670</b>	
6A	7.358	7.362	18	6	4	27	1	3	108	284	16	32	
6B	7.424	7.430	30	10	4	27	1	3	300	446	45	80	
7A	7.629	7.631	12	8	4	27	1	3	96	203	15	27	
7B	7.648	7.658	51	8	4	27	1	3	408	729	61	113	
7C	7.683	7.687	24	6	4	27	1	3	144	365	22	43	
8	7.774	7.788	75	10	4	27	1	3	750	1,053	112	200	
9A	7.884	7.888	24	10	4	27	1	3	240	365	36	64	
9B	7.901	7.911	57	10	4	27	1	3	570	810	85	152	
<b>TOTALS</b>										<b>3,918</b>	<b>6,764</b>	<b>587</b>	<b>1,747</b>

# SITE SUMMARY KY 1231

Site	Begin	End	Length	Cribbing Depth	Excavation Width	Depth to Rock	Number of Rows	Rail Spacing (FT)	Cribbing Amount (SQ FT)	Drilled RR Steel (FT)	Excav. & Backfill (CU YD)	Geotextile Fabric Class 2 (SQ YD)
1A	7.437	7.445	45	8	4	27	1	3	360	648	54	100
1B	7.448	7.457	45	8	4	27	1	3	360	648	54	100
<b>TOTALS</b>									<b>720</b>	<b>1,296</b>	<b>108</b>	<b>200</b>

GUARDRAIL SUMMARY KY 160

NEW GUARDRAIL						REMOVE & RESET GUARDRAIL					
LANE	END TREAT.	BEGIN MILEPOINT	END MILEPOINT	END TREAT.	LIN FEET	REMARKS	LANE	BEGIN MILEPOINT	END MILEPOINT	LIN FEET	REMARKS
Non Cardinzi	Type 7	14.057	14.063	Type 7	37.5		Non Cardinal	13.410	13.422	75.0	
Non Cardinzi	Type 7	15.321	15.335	TS No, 1	87.5						

Totals = 125.0

75.0

Type 1	0
Type 2A	0
Type 3	0
Type 4	0
Type 7	3
TS No. 1	1

GUARDRAIL SUMMARY KY 721

NEW GUARDRAIL						REMOVE & RESET GUARDRAIL					
LANE	END TREAT.	BEGIN MILEPOINT	END MILEPOINT	END TREAT.	LIN FEET	REMARKS	LANE	BEGIN MILEPOINT	END MILEPOINT	LIN FEET	REMARKS
Non Cardinal	Tie to Existing	5.067	5.072	Type 7	37.5		Non Cardinal	5.066	5.067	12.5	

Totals = 37.5

12.5

Type 1 0  
 Type 2A 0  
 Type 3 0  
 Type 4 0  
 Type 7 1  
 TS No. 1 0





GUARDRAIL SUMMARY KY 1231

NEW GUARDRAIL						REMOVE & GUARDRAIL			
LANE	END TREAT.	BEGIN MILEPOINT	END MILEPOINT	END TREAT.	REMARKS	LANE	BEGIN MILEPOINT	END MILEPOINT	REMARKS
Non Cardinal	Type 7	7.437	7.457	Type 7	112.5				
Totals = 112.5						0.0			

Type 1 0  
 Type 2A 0  
 Type 3 0  
 Type 4 0  
 Type 7 2  
 TS No. 1 0