



**COMMONWEALTH OF KENTUCKY  
TRANSPORTATION CABINET**  
Frankfort, Kentucky 40622  
[www.transportation.ky.gov/](http://www.transportation.ky.gov/)

**Matthew G. Bevin**  
Governor

**Greg Thomas**  
Secretary

July 20, 2016

CALL NO. 410  
CONTRACT ID NO. 162164  
ADDENDUM # 1

Subject: Pike County, 098GR16P057-FD05  
Letting July 29, 2016

- (1) Revised - Project Description - Page 4 of 93
- (2) Revised - Note - Page 13 of 93
- (3) Revised - Material Summary - Pages 31-31(a) of 93
- (4) Revised - Bid Items - Page 93 of 93

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in cursive script that reads "Rachel Mills".

Rachel Mills, P.E.  
Director  
Division of Construction Procurement

RM:ks  
Enclosures



An Equal Opportunity Employer M/F/D

## ADMINISTRATIVE DISTRICT - 12

**CONTRACT ID - 162164**

**098GR16P057-FD05**

**COUNTY - PIKE**

**PCN - MP09801191601**

**FD05 098 0119 016-019**

CANADA TO SOUTH WILLIAMSON ROAD (US 119) (MP 16.853) BEGIN AT THE END OF THE NEW PAVEMENT AT KY 3220 INTERSECTION EXTENDING NORTH TO 75 FEET NORTH OF THE FOREST TRACE ENTRANCE (MP 18.918), A DISTANCE OF 02.06 MILES.ASPHALT RESURFACING

GEOGRAPHIC COORDINATES LATITUDE 37:35:42.00 LONGITUDE 82:16:54.00

**PCN - MP09832201601**

**FD05 098 3220 000-005**

SIDNEY TO CANADA ROAD (KY 3220) (MP 0.200) BEGIN AT THE BOTTOM OFF US 119 RAMP EXTENDING NORTH TO THE NEW US 119 (MP 4.028), A DISTANCE OF 03.82 MILES.ASPHALT RESURFACING

GEOGRAPHIC COORDINATES LATITUDE 37:25:53.00 LONGITUDE 82:17:33.00

**COMPLETION DATE(S):**

COMPLETED BY 06/30/2017

APPLIES TO ENTIRE CONTRACT

**SPECIAL NOTE FOR  
ASPHALT MILLING AND TEXTURING**

---

Begin paving operations within **48 hours** of commencement of the milling operation. Continue paving operations continuously until completed. If paving operations are not begun within this time period, the Department will assess liquidated damages at the rate prescribed by Section 108.09 until such time as paving operations are begun.

Contrary to Section 408, the Department will retain possession of 4000 Tons of cuttings obtained from the milling operations. Deliver 2000 tons of this material to the State Maintenance facility in Shelbiana, Pike County and 2000 Tons to the State Maintenance facility in Canada, Pike County. Accept payment at the contract unit price per ton as full compensation for all labor, equipment, materials, and incidentals required to perform the milling and deliver the cuttings to the Departments Pike County maintenance facilities.

**NOTICE TO CONTRACTOR: The Department considers transfer of millings to the state maintenance facility to be a part of the construction project, therefore truck operators are subject to receiving prevailing wages.**

Take possession of the remainder of the cuttings and recycle the cuttings or dispose of the cuttings off the Right-of-Way at sites obtained by the Contractor at no additional cost to the Department. Accept payment at the contract unit price per ton as full compensation for all labor, equipment, materials, and incidentals required to perform the milling and recycle or dispose of the cuttings.

# MATERIAL SUMMARY

**CONTRACT ID: 162164**

**098GR16P057-FD05**

**MP09801191601**

CANADA TO SOUTH WILLIAMSON ROAD (US 119) BEGIN AT THE END OF THE NEW PAVEMENT AT KY 3220 INTERSECTION EXTENDING NORTH TO 75 FEET NORTH OF THE FOREST TRACE ENTRANCE ASPHALT RESURFACING, A DISTANCE OF 2.06 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00190	LEVELING & WEDGING PG64-22	400.00	TON
0010	00301	CL2 ASPH SURF 0.38D PG64-22	670.00	TON
0015	00388	CL3 ASPH SURF 0.38B PG64-22	7,175.00	TON
0020	02562	TEMPORARY SIGNS	500.00	SQFT
0025	02650	MAINTAIN & CONTROL TRAFFIC - (US 119)	1.00	LS
0030	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0035	02676	MOBILIZATION FOR MILL & TEXT - (US 119)	1.00	LS
0040	02677	ASPHALT PAVE MILLING & TEXTURING - (CONTRACTOR TAKE POSSESSION) (REVISED: 7-20-16)	3,845.00	TON
0045	02696	SHOULDER RUMBLE STRIPS-SAWED	42,000.00	LF
0050	02775	ARROW PANEL - (REVISED: 7-20-16)	2.00	EACH
0055	06510	PAVE STRIPING-TEMP PAINT-4 IN	78,000.00	LF
0060	06514	PAVE STRIPING-PERM PAINT-4 IN	78,000.00	LF
0065	06569	PAVE MARKING-THERMO CROSS-HATCH	3,500.00	SQFT
0070	06582	PAVEMENT MARKER TYPE IV-BY	900.00	EACH
0075	06600	REMOVE PAVEMENT MARKER TYPE V	850.00	EACH
0080	10020NS	FUEL ADJUSTMENT	11,791.00	DOLL
0085	10030NS	ASPHALT ADJUSTMENT	29,615.00	DOLL
0090	02569	DEMOBILIZATION	1.00	LS
0095	02677	ASPHALT PAVE MILLING & TEXTURING - (DELIVER TO CANADA FACILITY) (ADDED: 7-20-16)	2,000.00	TON
0100	02677	ASPHALT PAVE MILLING & TEXTURING - (DELIVER TO SHELBIANA FACILITY) (ADDED: 7-20-16)	2,000.00	TON

# MATERIAL SUMMARY

**CONTRACT ID: 162164**

**098GR16P057-FD05**

**MP09832201601**

SIDNEY TO CANADA ROAD (KY 3220) BEGIN AT THE BOTTOM OFF US 119 RAMP EXTENDING NORTH TO THE NEW US 119 ASPHALT RESURFACING, A DISTANCE OF 3.82 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00190	LEVELING & WEDGING PG64-22	150.00	TON
0010	00301	CL2 ASPH SURF 0.38D PG64-22	4,315.00	TON
0015	02562	TEMPORARY SIGNS	210.00	SQFT
0020	02650	MAINTAIN & CONTROL TRAFFIC - (KY 3220)	1.00	LS
0025	02676	MOBILIZATION FOR MILL & TEXT - (KY 3220)	1.00	LS
0030	02677	ASPHALT PAVE MILLING & TEXTURING - (CONTRACTOR TAKE POSSESSION) (REVISED: 7-20-16)	260.00	TON
0035	06510	PAVE STRIPING-TEMP PAINT-4 IN	20,000.00	LF
0040	06514	PAVE STRIPING-PERM PAINT-4 IN	85,000.00	LF
0045	06600	REMOVE PAVEMENT MARKER TYPE V	505.00	EACH
0050	10020NS	FUEL ADJUSTMENT	6,950.00	DOLL
0055	10030NS	ASPHALT ADJUSTMENT	17,456.00	DOLL
0060	02569	DEMOBILIZATION	1.00	LS

**PROPOSAL BID ITEMS**

Report Date 7/20/16

**Section: 0001 - PAVING**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	550.00	TON		\$	
0020	00301		CL2 ASPH SURF 0.38D PG64-22	4,985.00	TON		\$	
0030	00388		CL3 ASPH SURF 0.38B PG64-22	7,175.00	TON		\$	
0040	02562		TEMPORARY SIGNS	710.00	SQFT		\$	
0050	02650		MAINTAIN & CONTROL TRAFFIC (KY 3220)	1.00	LS		\$	
0060	02650		MAINTAIN & CONTROL TRAFFIC (US 119)	1.00	LS		\$	
0070	02671		PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH		\$	
0080	02676		MOBILIZATION FOR MILL & TEXT (KY 3220)	1.00	LS		\$	
0090	02676		MOBILIZATION FOR MILL & TEXT (US 119)	1.00	LS		\$	
0100	02677		ASPHALT PAVE MILLING & TEXTURING (CONTRACTOR TAKE POSSESSION) (REVISED: 7-20-16)	4,105.00	TON		\$	
0101	02677		ASPHALT PAVE MILLING & TEXTURING (DELIVER TO SHELBIANA FACILITY) (ADDED: 7-20-16)	2,000.00	TON		\$	
0102	02677		ASPHALT PAVE MILLING & TEXTURING (DELIVER TO CANADA FACILITY) (ADDED: 7-20-16)	2,000.00	TON		\$	
0110	02696		SHOULDER RUMBLE STRIPS-SAWED	42,000.00	LF		\$	
0120	02775		ARROW PANEL (REVISED: 7-20-16)	2.00	EACH		\$	
0130	06510		PAVE STRIPING-TEMP PAINT-4 IN	98,000.00	LF		\$	
0140	06514		PAVE STRIPING-PERM PAINT-4 IN	163,000.00	LF		\$	
0150	06569		PAVE MARKING-THERMO CROSS-HATCH	3,500.00	SQFT		\$	
0160	06582		PAVEMENT MARKER TYPE IV-BY	900.00	EACH		\$	
0170	06600		REMOVE PAVEMENT MARKER TYPE V	1,355.00	EACH		\$	
0180	10020NS		FUEL ADJUSTMENT	18,741.00	DOLL	\$1.00	\$	\$18,741.00
0190	10030NS		ASPHALT ADJUSTMENT	47,071.00	DOLL	\$1.00	\$	\$47,071.00

**Section: 0002 - DEMOBILIZATION**

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0200	02569		DEMOBILIZATION	1.00	LS		\$	