



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

April 25, 2023

CALL NO. 411
CONTRACT ID NO. 232307
ADDENDUM # 1

Subject: Carroll-Gallatin Counties, 121GR23P040 - FD04
Letting April 27, 2023

- (1) Revised - Notes - Page 10 of 70
- (2) Revised - Material Summary - Pages 42-43 of 70
- (3) Revised - Proposal Bid Items - Page 70 of 70

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

NATIONAL HIGHWAY

Be advised this project is on the NATIONAL HIGHWAY SYSTEM.

PROJECT TRAFFIC COORDINATOR (PTC)

Be advised this project is a significant project pursuant to section 112.03.12.

SURFACING AREAS FD04 021 0071 038-054

The Department estimates the mainline surfacing width to be 24 feet.

The Department estimates the total mainline area to be surfaced to be 97,040 square yards.

The Department estimates the shoulder width to be N/A foot on each side.

The Department estimates the total shoulder area to be surfaced to be N/A square yards.

SURFACING AREAS FD04 039 0071 053-060

The Department estimates the mainline surfacing width to be varied 24 to 36 feet.

The Department estimates the total mainline area to be surfaced to be 35,106 square yards.

The Department estimates the shoulder width to be N/A foot on each side.

The Department estimates the total shoulder area to be surfaced to be N/A square yards.

ASPHALT MIXTURE

Unless otherwise noted, the Department estimates the rate of application for all asphalt mixtures to be 110 lbs/sy per inch of depth.

INCIDENTAL SURFACING

The Department has included in the quantities of asphalt mixtures established in the proposal estimated quantities required for resurfacing or surfacing mailbox turnouts, farm field entrances, residential and commercial entrances, curve widening, ramp gores and tapers, and road and street approaches, as applicable. Pave these areas to the limits as shown on Standard Drawing RPM-110-06 or as directed by the Engineer. In the event signal detectors are present in the intersecting streets or roads, pave the crossroads to the right of way limit or back of the signal detector, whichever is the farthest back of the mainline. Surface or resurface these areas as directed by the Engineer. The Department will not measure placing and compacting for separate payment but shall be incidental to the Contract unit price for the asphalt mixtures.

FUEL AND ASPHALT PAY ADJUSTMENT

The Department has included the Contract items Asphalt Adjustment and Fuel Adjustment for possible future payments at an established Contract unit price of \$1.00. The Department will calculate actual adjustment quantities after work is completed. If existing Contract amount is insufficient to pay all items on the contract with the adjustments, the Department will establish additional monies with a change order.

OPTION B

Be advised that the Department will control and accept compaction of asphalt mixtures furnished on this project under OPTION B in accordance with Sections 402 and 403.

MATERIAL SUMMARY

CONTRACT ID: 232307

121GR23P040 - FD04

MP02100712301

I-71 BEGIN AT THE TRIMBLE/CARROLL COUNTY LINE EXTENDING NORTH TO THE CARROLL/GALLATIN COUNTY LINE ASPHALT RESURFACING, A DISTANCE OF 14.62 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00190	LEVELING & WEDGING PG64-22	1,400.00	TON
0010	00208	CL4 ASPH BASE 1.50D PG64-22	6,830.00	TON
0015	00342	CL4 ASPH SURF 0.38A PG76-22	5,400.00	TON
0020	00356	ASPHALT MATERIAL FOR TACK	60.00	TON
0025	02562	TEMPORARY SIGNS	1,000.00	SQFT
0030	02650	MAINTAIN & CONTROL TRAFFIC - Carroll County	1.00	LS
0035	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0040	02676	MOBILIZATION FOR MILL & TEXT - Carroll County	1.00	LS
0045	02677	ASPHALT PAVE MILLING & TEXTURING	12,230.00	TON
0050	02775	ARROW PANEL	4.00	EACH
0055	06542	PAVE STRIPING-THERMO-6 IN W	41,000.00	LF
0060	06543	PAVE STRIPING-THERMO-6 IN Y	41,000.00	LF
0065	06613	INLAID PAVEMENT MARKER-B W/R	350.00	EACH
0070	10020NS	FUEL ADJUSTMENT	33,614.00	DOLL
0075	10030NS	ASPHALT ADJUSTMENT	84,428.00	DOLL
0080	20411ED	LAW ENFORCEMENT OFFICER	300.00	HOURL
0085	25075EC	QUEUE PROTECTION VEHICLE	300.00	HOURL
0090	25117EC	FURNISH QUEUE PROTECTION VEHICLES	3.00	MONT
0095	26136EC	PORTABLE QUEUE WARNING ALERT SYSTEM	1.50	MONT
0100	26137EC	QUEUE WARNING PCMS	9.00	MONT
0105	26138EC	QUEUE WARNING PORTABLE RADAR SENSORS	9.00	MONT
0110	02569	DEMOBILIZATION	1.00	LS
0115	02568	MOBILIZATION - (ADDED 4-25-23)	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 232307

121GR23P040 - FD04

MP03900712301

I-71 BEGIN AT THE CARROLL/GALLATIN COUNTY LINE EXTENDING NORTH TO 0.423 MILES SOUTH OF KY 455 ASPHALT RESURFACING, A DISTANCE OF 6.5 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0115	00190	LEVELING & WEDGING PG64-22	500.00	TON
0120	00208	CL4 ASPH BASE 1.50D PG64-22	710.00	TON
0125	00342	CL4 ASPH SURF 0.38A PG76-22	1,935.00	TON
0130	00356	ASPHALT MATERIAL FOR TACK	20.00	TON
0135	02562	TEMPORARY SIGNS	1,000.00	SQFT
0140	02650	MAINTAIN & CONTROL TRAFFIC - Gallatin County	1.00	LS
0145	02671	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0150	02676	MOBILIZATION FOR MILL & TEXT - Gallatin County	1.00	LS
0155	02677	ASPHALT PAVE MILLING & TEXTURING	2,645.00	TON
0160	02775	ARROW PANEL	6.00	EACH
0165	06542	PAVE STRIPING-THERMO-6 IN W	900.00	LF
0170	06543	PAVE STRIPING-THERMO-6 IN Y	200.00	LF
0175	06613	INLAID PAVEMENT MARKER-B W/R	70.00	EACH
0180	10020NS	FUEL ADJUSTMENT	8,250.00	DOLL
0185	10030NS	ASPHALT ADJUSTMENT	20,721.00	DOLL
0190	20411ED	LAW ENFORCEMENT OFFICER	300.00	HOURL
0195	25075EC	QUEUE PROTECTION VEHICLE	300.00	HOURL
0200	25117EC	FURNISH QUEUE PROTECTION VEHICLES	3.00	MONT
0205	26136EC	PORTABLE QUEUE WARNING ALERT SYSTEM	3.00	MONT
0210	26137EC	QUEUE WARNING PCMS	9.00	MONT
0215	26138EC	QUEUE WARNING PORTABLE RADAR SENSORS	9.00	MONT
0220	02569	DEMOBILIZATION	1.00	LS
0225	02568	MOBILIZATION - (ADDED 4-25-23)	1.00	LS

PROPOSAL BID ITEMS

232307

Page 1 of 1

Report Date 4/25/23

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00190		LEVELING & WEDGING PG64-22	1,900.00	TON		\$	
0020	00208		CL4 ASPH BASE 1.50D PG64-22	7,540.00	TON		\$	
0030	00342		CL4 ASPH SURF 0.38A PG76-22	7,335.00	TON		\$	
0040	00356		ASPHALT MATERIAL FOR TACK	80.00	TON		\$	
0050	02562		TEMPORARY SIGNS	2,000.00	SQFT		\$	
0060	02650		MAINTAIN & CONTROL TRAFFIC Carroll County	1.00	LS		\$	
0070	02650		MAINTAIN & CONTROL TRAFFIC Gallatin County	1.00	LS		\$	
0080	02671		PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH		\$	
0090	02676		MOBILIZATION FOR MILL & TEXT Carroll County	1.00	LS		\$	
0100	02676		MOBILIZATION FOR MILL & TEXT Gallatin County	1.00	LS		\$	
0110	02677		ASPHALT PAVE MILLING & TEXTURING	14,875.00	TON		\$	
0120	02775		ARROW PANEL	10.00	EACH		\$	
0130	06542		PAVE STRIPING-THERMO-6 IN W	41,900.00	LF		\$	
0140	06543		PAVE STRIPING-THERMO-6 IN Y	41,200.00	LF		\$	
0150	06613		INLAID PAVEMENT MARKER-B W/R	420.00	EACH		\$	
0160	10020NS		FUEL ADJUSTMENT	41,864.00	DOLL	\$1.00	\$	\$41,864.00
0170	10030NS		ASPHALT ADJUSTMENT	105,149.00	DOLL	\$1.00	\$	\$105,149.00
0180	20411ED		LAW ENFORCEMENT OFFICER	600.00	HOUR		\$	
0190	25075EC		QUEUE PROTECTION VEHICLE	600.00	HOUR		\$	
0200	25117EC		FURNISH QUEUE PROTECTION VEHICLES	6.00	MONT		\$	
0210	26136EC		PORTABLE QUEUE WARNING ALERT SYSTEM	4.50	MONT		\$	
0220	26137EC		QUEUE WARNING PCMS	18.00	MONT		\$	
0230	26138EC		QUEUE WARNING PORTABLE RADAR SENSORS	18.00	MONT		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0235	02568		MOBILIZATION (ADDED 4-25-23)	1.00	LS		\$	
0240	02569		DEMOBILIZATION	1.00	LS		\$	