



TRANSPORTATION CABINET

Frankfort, Kentucky 40622
www.transportation.ky.gov/

Steven L. Beshear
Governor

Michael W. Hancock, P.E.
Secretary

May 21, 2014

CALL NO. 416
CONTRACT ID NO. 142268
ADDENDUM # 1

Subject: Hopkins County, 054GR14P065-FE01
Letting May 30, 2014

(1) Revised - Summary Sheets - Pages 41-44 of 93

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

A handwritten signature in blue ink that reads "Diana Castle Radcliffe".

Diana Castle Radcliffe
Director
Division of Construction Procurement

DR:ks
Enclosures



An Equal Opportunity Employer M/F/D

Hopkins County
FE01 054 0041 012-016
US 41 (South Main St) Concrete Patches

Northbound Lanes

Passing Lane				
MP	Width	x	Length	SY
13.159	24	x	12	32
13.373	12	x	40	53
14.158	12	x	12	16
14.187	24	x	30	80
14.206	12	x	12	16
14.32	12	x	15	20
14.41	24	x	30	80
14.471	24	x	60	160
14.761	12	x	30	40
14.764	12	x	15	20
15.38	24	x	8	21
15.39	12	x	12	16
TOTAL				555

Driving Lane				
MP	Width	x	Length	SY
13.159	12	x	12	16
13.436	12	x	12	16
14.187	12	x	15	20
14.206	24	x	45	120
14.208	12	x	15	20
14.273	12	x	12	16
14.283	12	x	15	20
14.692	12	x	24	32
14.761	12	x	12	16
14.764	12	x	24	32
15.115	12	x	10	13
15.137	24	x	55	147
15.37	12	x	15	20
15.418	24	x	45	120
TOTAL				608

Southbound Lanes

Passing Lane				
MP	Width	x	Length	SY
15.746	24	x	12	32
15.641	12	x	15	20
15.521	12	x	60	80
15.452	12	x	12	16
15.398	12	x	8	11
14.721	12	x	12	16
14.705	24	x	15	40
14.702	12	x	15	20
14.598	12	x	12	16
14.513	12	x	15	20
14.418	12	x	25	33
14.3	12	x	12	16
14.085	12	x	12	16
14.065	12	x	15	20
14.42	12	x	12	16
14.03	12	x	15	20
13.347	12	x	12	16
13.645	12	x	24	32
13.623	12	x	8	11
13.1	12	x	12	16
TOTAL				467

Driving Lane				
MP	Width	x	Length	SY
15.679	12	x	60	80
15.661	12	x	25	33
15.632	12	x	12	16
15.452	12	x	12	16
15.398	12	x	8	11
14.705	12	x	12	16
14.702	12	x	15	20
14.604	12	x	8	11
14.496	12	x	12	16
14.489	24	x	50	133
14.422	12	x	12	16
14.419	12	x	100	133
14.151	12	x	30	40
14.094	24	x	15	40
14.076	12	x	15	20
14.043	12	x	12	16
14.03	12	x	24	32
13.725	12	x	15	20
13.645	12	x	30	40
13.1	12	x	12	16
TOTAL				725

NOTE: Any DGA required to bring the subgrade up to the correct elevation after removal of the existing concrete pavement, will be incidental to the 10" JPC pavement bid item.

Hopkins County
FE01 054 0041 019-020
Concrete Repair Locations
Pennyrile Ramp 9004-711 and US 41

Route	MP	Passing Lane			Driving Lane			SY
		Length		Width	Length		Width	
EB 9004-711	0.194				6	x	12	8
EB 9004-711	0.204	6	x	12	6	x	12	16
EB 9004-711	0.213				6	x	12	8
EB 9004-711	0.223	25	x	12	25	x	12	67
EB 9004-711	0.309				6	x	12	8
EB 9004-711	0.463	6	x	12	6	x	12	16
EB 9004-711	0.473	6	x	12	6	x	12	16
EB 9004-711	0.482	6	x	12	6	x	12	16
EB 9004-711	0.498	25	x	12	25	x	12	67
EB 9004-711	0.532	30	x	12				40
EB 9004-711	0.550							
EB 9004-711	0.609							
EB 9004-711	0.636				25	x	12	33
EB 9004-711	0.646	6	x	12	6	x	12	16
EB 9004-711	0.684				6	x	12	8
EB 9004-711	0.702				6	x	12	8
EB 9004-711	0.737				20	x	12	27
EB 9004-711	0.835				6	x	12	8
US 41	19.057	6	x	12	6	x	12	16
US 41	19.067	6	x	12	6	x	12	16
US 41	19.076	6	x	12				8
US 41	19.097	25	x	12	25	x	12	67
US 41	19.114	25	x	12	25	x	12	67
US 41	19.131				6	x	12	8
US 41	19.141	6	x	12				8
US 41	19.159				25	x	12	33
US 41	19.227	6	x	12				8
US 41	19.238	10	x	12				13
US 41	19.241	30	x	12	50	x	12	107
US 41	19.275	6	x	12	6	x	12	16
US 41	19.294				6	x	12	8
US 41	19.313	6	x	12	6	x	12	16
US 41	19.323	6	x	12				8
US 41	19.333	6	x	12	6	x	12	16
US 41	19.352	24	x	12	25	x	12	65
US 41	19.361	6	x	12	6	x	12	16
US 41	19.400	6	x	12	6	x	12	16

TOTAL 612

NOTE: Any DGA required to bring the subgrade up to the correct elevation after removal of the existing concrete pavement, will be incidental to the 10" JPC pavement bid item.

Hopkins County
FE01 054 0041 019-020
Concrete Repair Locations
Pennyrile Ramp 9004-741

MP	Passing Lane			Drving Lane			SY
	Length		Width	Length		Width	
0.121				6	x	12	8
0.150				6	x	12	8
0.219				6	x	12	8
0.236				6	x	12	8
0.256	6	x	12	6	x	12	16
0.276	6	x	12	6	x	12	16
0.284	25	x	12	25	x	12	67
0.297	25	x	12				33
0.304	25	x	12	25	x	12	67
0.324				6	x	12	8
0.331	40	x	12	40	x	12	107
0.353	6	x	12	6	x	12	16
0.363	6	x	12				8
0.382	25	x	12	25	x	12	67
0.392	6	x	12				8
0.402	6	x	12				8
0.411	6	x	12	6	x	12	16
0.421	6	x	12	6	x	12	16
0.430	25	x	12	25	x	12	67
0.446				6	x	12	8
0.449	6	x	12				8
0.460	6	x	12	6	x	12	16
0.479	6	x	12	6	x	12	16
0.508				6	x	12	8
0.635				6	x	12	8
0.655				6	x	12	8
0.703	6	x	12	6	x	12	16
0.770	6	x	12	6	x	12	16
0.779				6	x	12	8
0.895				24	x	6	16
0.942				20	x	40	89

TOTAL 768

NOTE:Any DGA required to bring the subgrade up to the correct elevation after removal of the existing concrete pavement, will be incidental to the 10" JPC pavement bid item.