



Andy Beshear
GOVERNOR

TRANSPORTATION CABINET

200 Mero Street
Frankfort, Kentucky 40601

Jim Gray
SECRETARY

March 14, 2023

CALL NO. 416
CONTRACT ID NO. 232119
ADDENDUM # 1

Subject: Warren County, 114GR23P028 - FD05
Letting March 23, 2023

(1) Added - Summary Sheet - Page 85A of 106

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

Warren County
SIDEWALK, DETECTABLE WARNING & TRAFFIC ISLAND SUMMARY
FD05 114 0231 010-013

MILEPOINT	INTERSECTION	REMOVE		INSTALL		Description
		SIDEWALK CONCRETE SY	CONCRETE ISLAND SY	CONCRETE 4" SIDEWALK SY	DETECTABLE WARNING SF	
10.679	Gary Farms Blvd			SE: 8 SW: 12	SE: 10 SW: 20	SE: Remove/Replace w/ TY I (curb repair incidental) SW: Remove/Replace w/ TY III
10.942	Walton Ave			SE: 12 SW: 16	SE: 10 SW: 20	SE: Remove/Replace w/ TY I SW: Remove/Replace w/ TY III (Condition No. 2)
11.092	American Ave			NE: 18 NW: 20 SE: 8	NE: 20 NW: 20 SE: 10	NE: Remove/Replace w/ TY I NW: Remove/Replace w/ TY III (Condition No. 2) NE: Add Warnings to Ramp / 32LF of Sidewalk Repair
11.313	West Park Dr			SW: 10	SW: 10	NW: Add Warnings
11.438	Merrick Place Ct			NE: 12 NW: 12	NE: 10 NW: 10	NE: Remove/Replace w/ TY I NW: Remove/Replace w/ TY I
11.837	Mcintosh St			NE: 12 NW: 12	NE: 10 NW: 10	NE: Remove/Replace w/ TY I NW: Remove/Replace w/ TY I & 25LF of Sidewalk Repair
11.996	Destiny Ln			NE: 14 NW: 10	NE: 10 NW: 10	NE: Remove/Replace w/ TY I NW: Remove/Replace w/ TY I
12.201	Christian Care Way		M:14	NE: 18 NW: 10	NE: 10 NW: 10 M: 20	M(Median) - Saw and Remove 6' walkway through raised island. All work necessary to remove portion of island to below grade will be incidental to remove island. Replace sidewalk flush with asphalt pavement through the width of the island, incidental to sidewalk bid item. Formation of a curb along each side of new walkway will be incidental to sidewalk bid item also. See Site Map Attached. SE: Remove/Replace w/ TY III SW: Remove/Replace w/ TY III SE: Remove/Replace w/ TY I SW: Remove/Replace w/ TY III SE: Add Detectable Warnings Only
12.287	Smallhouse Rd			SE: 10 SW: 10	SE: 10 SW: 10	SE: Remove/Replace w/ TY III SW: Remove/Replace w/ TY III
12.551	Thoroughbred Dr			NE: 10 NW: 15	NE: 10 NW: 20	NE: Remove/Replace w/ TY I NW: Remove/Replace w/ TY III
12.751	Fields Dr				SE: 10	SE: Add Detectable Warnings Only
12.893	Harvard Dr			SE: 18 SW: 10	NE: 10 NW: 10	NE: Add Detectable Warnings Only NW: Add Detectable Warnings Only
12.97	Kroger Entrance			SE: 20	SE: 10	SE: Remove/Replace w/ TY I (30 LF of Sidewalk Repair)
13.042	US 31W			SW: 10	SW: 10	SW: Remove and Repair area around sidewalk ramp and drainage box
TOTALS			14	375	430	