



COMMONWEALTH OF KENTUCKY
TRANSPORTATION CABINET

www.transportation.ky.gov/

Andy Beshear
GOVERNOR

Jim Gray
SECRETARY

September 15, 2021

CALL NO. 449
CONTRACT ID NO. 213178
ADDENDUM # 1

Subject: Union County, 113GR21R106-CB06
Letting September 24, 2021

- (1) Revised - Special Note - Page 19 of 52
- (2) Revised - Material Summary - Pages 28-29 of 52
- (3) Revised - Proposal Bid Items - Page 52 of 52

Proposal revisions are available at <http://transportation.ky.gov/Construction-Procurement/>.

If you have any questions, please contact us at 502-564-3500.

Sincerely,

Rachel Mills,

A handwritten signature in black ink that reads "Rachel Mills".

Rachel Mills, P.E.
Director
Division of Construction Procurement

RM:mr
Enclosures

SPECIAL NOTE FOR ASPHALT MILLING AND TEXTURING

The Asphalt Milling and Texturing Bid Item on KY 2091 is intended to be used only as needed through the superlevation corrections. Exact locations will be determined by the Engineer.

For KY 141 and KY 270 Begin paving operations within **2 weeks** of commencement of the milling operation. Continue paving operations continuously until completed. If paving operations are not begun within this time period, the Department will assess liquidated damages at the rate prescribed by Section 108.09 until such time as paving operations are begun.

The approximate pavement removal areas for KY 270 at KY 141 as shown on the drawings will be paid for as ASPHALT MILLING AND TEXTURING by the TON. The contractor shall mill approximately 4 IN at all Pavement Removal areas and backfill with DGA. Final Pavement Removal areas will be determined by the Engineer.

Contrary to Section 408, the Department will retain possession of the material obtained from the milling operations. Deliver this material to the State Maintenance facility in Union County.

MATERIAL SUMMARY

CONTRACT ID: 213178

113GR21R106-CB06

0211301412101

STATE HIGHWAY 141 (KY 141) FROM T.L. BISHOP ROAD EXTENDING NORTH TO US 60 ASPHALT RESURFACING, A DISTANCE OF 3.48 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0145	00001	DGA BASE	235.00	TON
0150	00190	LEVELING & WEDGING PG64-22	225.00	TON
0155	00301	CL2 ASPH SURF 0.38D PG64-22	2,475.00	TON
0160	02562	TEMPORARY SIGNS	240.00	SQFT
0165	02650	MAINTAIN & CONTROL TRAFFIC - KY 141	1.00	LS
0170	02676	MOBILIZATION FOR MILL & TEXT - KY 141	1.00	LS
0175	02677	ASPHALT PAVE MILLING & TEXTURING - (REVISED 9-15-2021)	40.00	TON
0180	06510	PAVE STRIPING-TEMP PAINT-4 IN	18,500.00	LF
0185	06514	PAVE STRIPING-PERM PAINT-4 IN	33,000.00	LF
0190	10020NS	FUEL ADJUSTMENT	4,203.00	DOLL
0195	10030NS	ASPHALT ADJUSTMENT	10,556.00	DOLL
0200	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	10.20	TON
0205	02569	DEMOBILIZATION	1.00	LS

CONTRACT ID: 213178

113GR21R106-CB06

0211302702101

STATE HIGHWAY 270 (KY 270) FROM 0.5 MILES WEST OF GENERAL HOLT ROAD EXTENDING EAST TO KY 141 ASPHALT RESURFACING, A DISTANCE OF 2.54 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0070	00001	DGA BASE	185.00	TON
0075	00190	LEVELING & WEDGING PG64-22	175.00	TON
0080	00212	CL2 ASPH BASE 1.00D PG64-22	95.00	TON
0085	00301	CL2 ASPH SURF 0.38D PG64-22	1,935.00	TON
0090	02562	TEMPORARY SIGNS	180.00	SQFT
0095	02650	MAINTAIN & CONTROL TRAFFIC - KY 270	1.00	LS
0100	02676	MOBILIZATION FOR MILL & TEXT - KY 270	1.00	LS
0105	02677	ASPHALT PAVE MILLING & TEXTURING - (REVISED 9-15-2021)	60.00	TON
0110	06510	PAVE STRIPING-TEMP PAINT-4 IN	13,450.00	LF
0115	06514	PAVE STRIPING-PERM PAINT-4 IN	24,000.00	LF
0120	10020NS	FUEL ADJUSTMENT	3,432.00	DOLL
0125	10030NS	ASPHALT ADJUSTMENT	8,621.00	DOLL
0130	21554EN	EXCAVATION	30.00	CUYD
0135	24970EC	ASPHALT MATERIAL FOR TACK NON-TRACKING	7.60	TON
0140	02569	DEMOBILIZATION	1.00	LS

MATERIAL SUMMARY

CONTRACT ID: 213178

113GR21R106-CB06

0211320912101

STATE HIGHWAY 2091 (KY 2091) KY 2091 - MP 2.0 TO MP 2.2 SUPERELEVATION CORRECTION
KY 2091 - MP 2.7 TO MP 3.7 BASE FAILURE REPAIRS ASPHALT RESURFACING, A DISTANCE OF 1.7 MILES.

Project Line No	Bid Code	DESCRIPTION	Quantity	Unit
0005	00001	DGA BASE	75.00	TON
0010	00190	LEVELING & WEDGING PG64-22	200.00	TON
0015	02022	JPC PAVEMENT-8 IN/24	30.00	SQYD
0020	02562	TEMPORARY SIGNS	240.00	SQFT
0025	02650	MAINTAIN & CONTROL TRAFFIC - KY 2091	1.00	LS
0030	02676	MOBILIZATION FOR MILL & TEXT - KY 2091	1.00	LS
0035	02677	ASPHALT PAVE MILLING & TEXTURING - (REVISED 9-15-2021)	70.00	TON
0040	03240	BASE FAILURE REPAIR	344.00	SQYD
0045	06514	PAVE STRIPING-PERM PAINT-4 IN	1,300.00	LF
0050	10020NS	FUEL ADJUSTMENT	591.00	DOLL
0055	10030NS	ASPHALT ADJUSTMENT	1,486.00	DOLL
0060	23647ES400	CL2 ASPH SURF 0.50A PG64-22	380.00	TON
0065	02569	DEMOBILIZATION	1.00	LS

PROPOSAL BID ITEMS

Report Date 9/15/21

Page 1 of 1

Section: 0001 - PAVING

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0010	00001		DGA BASE	495.00	TON		\$	
0020	00190		LEVELING & WEDGING PG64-22	600.00	TON		\$	
0030	00212		CL2 ASPH BASE 1.00D PG64-22	95.00	TON		\$	
0040	00301		CL2 ASPH SURF 0.38D PG64-22	4,410.00	TON		\$	
0050	02022		JPC PAVEMENT-8 IN/24	30.00	SQYD		\$	
0060	02562		TEMPORARY SIGNS	660.00	SQFT		\$	
0070	02650		MAINTAIN & CONTROL TRAFFIC KY 141	1.00	LS		\$	
0080	02650		MAINTAIN & CONTROL TRAFFIC KY 2091	1.00	LS		\$	
0090	02650		MAINTAIN & CONTROL TRAFFIC KY 270	1.00	LS		\$	
0100	02676		MOBILIZATION FOR MILL & TEXT KY 141	1.00	LS		\$	
0110	02676		MOBILIZATION FOR MILL & TEXT KY 2091	1.00	LS		\$	
0120	02676		MOBILIZATION FOR MILL & TEXT KY 270	1.00	LS		\$	
0130	02677		ASPHALT PAVE MILLING & TEXTURING (REVISED 9-15-2021)	170.00	TON		\$	
0140	03240		BASE FAILURE REPAIR	344.00	SQYD		\$	
0150	06510		PAVE STRIPING-TEMP PAINT-4 IN	31,950.00	LF		\$	
0160	06514		PAVE STRIPING-PERM PAINT-4 IN	58,300.00	LF		\$	
0170	10020NS		FUEL ADJUSTMENT	8,226.00	DOLL	\$1.00	\$	\$8,226.00
0180	10030NS		ASPHALT ADJUSTMENT	20,663.00	DOLL	\$1.00	\$	\$20,663.00
0190	21554EN		EXCAVATION	30.00	CUYD		\$	
0200	23647ES400		CL2 ASPH SURF 0.50A PG64-22	380.00	TON		\$	
0210	24970EC		ASPHALT MATERIAL FOR TACK NON- TRACKING	17.80	TON		\$	

Section: 0002 - DEMOBILIZATION

LINE	BID CODE	ALT	DESCRIPTION	QUANTITY	UNIT	UNIT PRIC	FP	AMOUNT
0220	02569		DEMOBILIZATION	1.00	LS		\$	