# LOUISVILLE-SOUTHERN INDIANA OHIO RIVER BRIDGES PROJECT UTILITY COORDINATION PRESENTATION








KYTC Partnering Conference – September 11, 2012 By: Cindy M. Kowalski, PMP

### **KYTC Partnering Conference 2012**



Louisville-Southern Indiana Ohio River Bridges Project: How the bridge's impacts to utilities are being handled.



### **Presentation Agenda**



- Bridges Project Overview
  - Downtown Crossing
  - East End Crossing
- Project Schedule
- Two States Twenty Companies
- High Profile Utility Impacts
- Traditional Project Utility Coordination process
- Design Build Project Utility Coordination process
  - KYTC Utility Coordination for Downtown Crossing
  - INDOT Utility Coordination for East End Crossing
- Questions

# **Project Overview**





# Project Schedule



#### Project Schedule

- April 24, 2012 .... RFQ Selection of qualifying teams
- May 3, 2012 ...... Draft RFP provided to selected teams
- August 1, 2012 .. Final RFP
- October 2012 ..... Proposals due
- Late 2012 ..... Developer Team selected
- Early 2013 ...........Contract execution / Begin final design
- June 30, 2017 .... East End Crossing complete
- June 30, 2018 .... Downtown Crossing complete

### Two States / Twenty Companies



- Downtown Bridge and Approaches -
  - KY Utility Companies 11
  - IN Utility Companies 12
  - KYTC responsible for utility relocations in both states
- East End Bridge and Approaches -
  - KY Utility Companies 6
  - IN Utility Companies 9
  - INDOT responsible for utility relocations in both states
- KYTC and INDOT met
  - Agree permits to be processed in governing state
  - Share policies and procedure manuals

## High Profile Utility Impacts



- Downtown Bridge and Approaches
  - LG&E Transmission towers
    - Vertical elevation conflict affecting two lattice towers
  - MSD twin 24" force main sewers
    - CCTV all sanitary and combined sewers
    - Designed relocation of twin 24" force mains
  - Seven Fiber Optic Providers
  - Insight's nodes and power supply
  - City of Jeffersonville Wastewater Pump Station
  - Duke 138 KV Transmission Route




### High Profile Utility Impacts



- East End Bridge and Approaches
  - LWC 60" transmission water main
    - Failure Risk Analysis and Construction Mitigation Report
    - Blasting Mitigation
  - LWC Water Treatment Plant
    - RBI / Pier Placement
    - Sludge Lagoon Study of Options
  - AT&T Remote Terminal
  - MSD Pump Station and Shadowwood Treatment Plant
    - Study of Options
  - Level 3 Long Haul Fiber Optics
    - One conflict = 5 miles of relocation
  - AT&T Controlled Temperature Vault
  - Watson Rural Water Company 20" transmission water main


# LWC Sludge Lagoon






## Traditional Project Approach





### Design Build Project Approach





### **KYTC - Utility Coordination**



#### **During Procurement Phase**

- Reimbursement Letters
- Authorization Letters
- Kick -off meeting with DBT's
- DBT's have access to Utility Companies
- Engineering Service Agreements (if requested)
  - Meet with DBT's
  - Coordinate with DBT's
  - Preliminary engineering
  - Conceptual lay-outs (cost estimate, schedules, etc,)

### **INDOT- Utility Coordination**



#### **During Procurement Phase**

- Reimbursement Letters
- Authorization Letters
- Kick -off meeting with DBT's
- DBT's need permission to contact Utility Companies
  - Advance notice required
  - INDOT must be included via conference call or in person
- Utility Adjustment Types
  - Type 1 work that can be done with 30% plans INDOT pays
  - Type 2 work that depends on final plans DBT controls and pays
  - Type 3 work that depends on final plans Utility controls / DBT pays

### **INDOT- Utility Coordination**



#### <u>During Procurement Phase (cont.)</u>

- One-on-One Meetings
  - Discussed / Agreed on Utility Adjustment Types
  - Meeting Summaries\*
- Request for Draft Work Plan\*
  - Preliminary plan, schedule and cost estimate
- Preliminary Engineering Agreements
  - To prepare draft work plan
  - Meet with DBT
  - Consultant Approvals
- Type 2 and Type 3 Agreements\*
- NTP with Type 1 Relocations
  - \* information provided to DBT's

### **KYTC - Utility Coordination**



#### **During Design-Build Phase**

- DBT responsible for Utility Coordination
- Utility Meetings
- Provide project plans as updated
- Assist in Utility Relocation design lay-outs
- Prepare Agreements
  - Utility Design and Construct
  - Utility Design and DBT Construct
  - DBT Design and Construct
- Coordinate Permit application process

### **INDOT- Utility Coordination**



#### **During Design-Build Phase**

- DBT responsible for Utility Coordination
- Utility Meetings
- Provide project plans as updated
- Assist in Utility Relocation type 2 and 3 designs
  - LWC Lagoon
- Prepare Agreements
- Acquire utility easements, if needed
- Coordinate Permit application process
- Type 1 relocations complete or relief event

# Summary



How the Bridges Impact on Utilities is being handled:

Coordination,
Coordination,
More Coordination
and then....
Relocation!

#### Questions



Cindy M. Kowalski, PMP - CTS

Jennifer McCleve, PE - KYTC Central Office

Carl Jenkins, PE - KYTC District 5